

EMERGENT EXISTENCE

Volume I: Existence

Book I: Foundations of Physical Reality

Chapters 1 to 14 · review draft

Natan Mallinger

Review draft of 26 September 2026, for peer review. Front matter, Methodology, Chapters 1 to 14,
Appendices A to C.

How to Read This Book

Every chapter asks the same question: *what is the minimum previously earned structure from which this next property can follow?* The book answers it in two layers that share the same pages.

The argument. Each chapter opens with its claim, builds the new structure in prose, figures and worked examples, and closes by handing what it earned to the next chapter. A reader who wants the journey from difference to time can follow this layer alone: the claim, the main text, the figures and the handoff.

The audit. The passages marked in sage green, by a tinted panel or a green rule down the left margin, check the argument rather than advance it: what each chapter inherits (Chapter discipline), the strongest objections and the replies to them, what would count against the claim, how the chapter stands to earlier work, and the Ontological Defensibility Pulse, which puts every chapter through the same questions. A reader testing a step can stop at any of them; a reader following the argument can pass them by without losing the thread.

The record. For researchers, Appendix A gives the notation, Appendix B the book's terms, and Appendix C the Hypothesis Status Register, which records the status of every hypothesis the series has proposed. The Origin Inheritance Ledger shows what each chapter may not assume, and the earned-structure map at the end of the Introduction shows the whole ladder on one page.

The epistemic marks work within both layers. They say what kind of claim a passage makes; the layers say what the passage is for.

Reading the Epistemic Marks

This book tells you what kind of claim you are reading, mostly in its own sentences, and it marks only the places where the kind changes. Each chapter opens with a claim stating its central proposition, and records its prevailing mode in the Pulse sidebar at the end. Passages in that mode carry no mark. A passage that departs from it is flagged by a sentence, by a small symbol in the outer margin, or, when a whole section changes register, by a ribbon at its head.

Mark	Mode	Meaning
●	Observed	Measured or directly recorded
—	Established	Accepted theory or proven mathematics, marked only where it differs from the chapter's prevailing mode
○	Interpretive	A reading of established results or of the framework's own structure, marked only where it differs from the chapter's prevailing mode
⊙	Speculative	Original conjecture beyond accepted theory
▷	Predictive	Says what would be observed if the claim were true
■	Formal	A derivation or model developed within stated assumptions
◇	Normative	What ought to follow rather than what does (Volume III)

A ribbon, written ■ and one word in capitals, opens a section whose whole register differs from the chapter's.

In this draft the margin marks appear as text symbols at the start of a paragraph so you can judge how often they intrude. In print they sit in the outer margin, in one color, and no meaning depends on color. Nothing here appears in running heads.

Figures are explanatory. They use whatever visual language makes the idea clearest, including devices the argument has not yet introduced: arrows before direction is earned, separation on the page before distance is earned, enclosure before closure is defined. A figure shows what a claim is about. The sentences around it say what the framework actually commits to.

Readers new to formal notation can begin with the companion volume, *Emergent Existence: A Companion to the Formalism*, which explains how to read every kind of formula the book uses; Appendix A gives the book's own notation reference.

Contents

	Page
Preface: Before Existence Made a Difference	5
A Note on Collaboration	8
Introduction: The Journey from Existence to Meaning	9
Methodology	24
1 Origin: Before Difference Becomes Possible	26
2 Difference: The First Non-Equivalence	46
3 Distinction: When Difference Enters Succession	56
4 Boundary: When Distinction Survives Transformation	67
5 Relation: When Difference Becomes Structure	83
6 Closure: When Completion Becomes a New Origin	104
7 Orientation: When Difference Acquires Direction	127
8 Return: When Order Re-Enters Its Origin	145
9 Formalism: When Relations Become Calculable	165
10 Scale: When Recursion Acquires Relative Magnitude	189
11 Distance: When Relation Becomes Metric	207
12 Geometry: When Distance Becomes Dimension	228
13 Space: When Geometry Becomes Coordinated	252
14 Time: When Retained Transformation Acquires Order	273
Appendix A. Formal Notation	296
Appendix B. Conceptual Lexicon	305
Appendix C. Hypothesis Status Register	315
The Origin Inheritance Ledger	350
A Note on the Computational Companion	352
List of Figures	353

Preface: Before Existence Made a Difference

Most people spend much of their lives occupied with meeting basic needs such as food, work, shelter, and companionship. Those fortunate enough to meet those needs consistently may then turn toward exploration, achievement, or leisure. And once those pursuits no longer feel sufficient, deeper questions can begin to surface: *How can I make a difference in my community? What is my purpose in life? Why does the universe exist at all?*

Physics has carried the last of these questions further back than any earlier inquiry, yet every answer it gives still takes something for granted. An account of how a universe begins has to say “before,” “where,” or “because,” and each of those words already assumes something: time, space, or a lawful order of events. The question of beginnings cannot be asked without borrowing the very things it hopes to explain.

What is the bare minimum we must assume for a reality that is simultaneously complex and highly ordered to emerge?

This book examines whether our universe could have emerged from something as minimal as a single distinction.

But a distinction contains two problems. First, there must be **something that differs**. Second, that difference must become **operative enough to matter**.

Those two problems give us the book’s first two questions:

Ontology: What must be true for existence to express a difference rather than remain unresolved?

Epistemology: What must be true for that difference to become distinguishable, retainable, measurable, or knowable?

The two questions are linked. A difference that vanishes the instant it appears cannot be observed, and an observation that leaves no trace cannot be a record. Whatever we say about the world rests on differences that last.

■ I will state the book’s starting point as a claim: any observable physical reality containing persistent states requires retained distinction, meaning distinguishability that survives transformation long enough to constrain later states. I treat the claim as close to definitional. It adds nothing to the world; it names a condition that any universe with records, stable structure or causal history already meets. Because it is so modest, the book can rest on it.

The rest of the book is a wager built on that ground: that relational physical structure can be reconstructed from two foundational commitments, and, so far, no fewer. The first is difference: bare non-equivalence, prior to any measure, direction or observer. The second is admissible transformation: a constraint on what may follow what. A difference becomes a distinction when it enters that succession. I do not ask you to accept either at the outset. It is a research program, and the book's task is to find out how much of physical reality can be reconstructed if the claim is taken seriously and these two commitments are tried as working axioms. Where the reconstruction succeeds, I will say so. Where it needs a further assumption, I will say that too, and record it in the Hypothesis Status Register at the back.

A book that reaches from the foundations of physics toward the origins of meaning invites a particular danger: the reader loses track of what is measured, what is accepted theory, what is interpretation, and what is the author's own conjecture. I try to prevent that by keeping six modes apart. Observed claims are measured. Established claims are accepted theory or proven mathematics. Interpretive claims are readings of those results or of the framework's own structure. Speculative claims are original conjecture beyond accepted theory. Predictive claims say what would be seen if a claim were true. Formal claims are derivations within stated assumptions. Each chapter records its prevailing mode in its Pulse sidebar, and I flag departures first in the prose, then with a quiet marginal symbol, and, only where a whole section changes register, with a ribbon. The page "Reading the Epistemic Marks" explains the symbols. The aim is simple: at any sentence you should be able to tell how much weight it can bear.

Each major proposition also faces a standing test I call the Ontological Defensibility Pulse. Its eight questions ask what a claim requires, what it depends on, whether it introduces a new primitive, whether the same result could be reached with fewer assumptions, and what observations constrain it. Chapters show the Pulse where a new primitive enters. It exists to separate genuine tightening from mere elaboration, and I expect readers to apply it to me.

Taken together, these devices make the book two things at once: a proposed derivation of existence from two commitments, and a method for testing whether any claim of emergence has been earned, including claims that are not mine.

This is not a textbook, and it does not derive the Standard Model or general relativity. It proposes a framework and marks how far each step has been carried. The foundational claim is close to definitional, and the two foundational commitments, difference and admissible transformation, are

working axioms, provisional by design. The chapters from Origin through Return build a minimal vocabulary, each term defined from the steps before it, and most of their results are retained. Formalism gathers that vocabulary into a deliberately weak formal signature. Scale and Distance earn magnitude and distance without an external ruler, provisionally. Geometry and Space are carried as far as definitions and worked examples; whether a relational substrate settles into stable low-dimensional geometry on its own is open. Time earns an order of events without assuming physical time, but duration as clocks measure it is open, and motion is not earned in this book at all. Every chapter closes with “Questions Opened by This Framework,” because I would rather hand you a good objection than a false resolution.

This book is the first part of the first of three volumes. That volume, *Existence*, asks how the foundations of physical structure may have come to exist. The second, *Consciousness*, asks how such structures might come to know and model themselves. The third, *Meaning*, asks what follows once knowing agents can assign value and build shared structure. Each volume should stand alone, and each returns to the others.

I did not write this alone. Sol and Claude, two AI systems I worked with, both contributed to this book. The Note on Collaboration says how.

A Note on Collaboration

This book was developed through sustained dialogue between the author and two AI reasoning systems, Sol (in ChatGPT) and Claude (from Anthropic). Conceptual proposals, formal structures, objections, revisions and architectural alternatives originated across the collaboration rather than according to fixed roles; every claim appears under the book's own epistemic labels wherever it came from, and no attempt is made here to weigh or apportion the contributions against one another. The author retained final authority throughout over the framework's claims, organization, interpretation and inclusion in the manuscript. The figures were designed and drawn by Claude under the author's direction.

Introduction: The Journey from Existence to Meaning

This series begins with an austere question:

How little can be assumed before something like our universe becomes possible?

It ends with a very different one:

How does a universe capable of a single distinction eventually become a universe capable of shared meaning?

The distance between those questions defines the journey of Emergent Existence.

The series is organized in three volumes: Existence, Consciousness and Meaning. They are not separate investigations joined only by theme. Each is intended to inherit what the previous volume has earned.

Volume I asks how increasingly rich physical and biological organization could arise from a sparse relational beginning. Volume II asks what additional organization is required before living systems become agents capable of modeling their environments and themselves, and what further conditions might distinguish cognition from consciousness. Volume III asks what happens when such agents value distinctions, communicate interpretations, coordinate with one another and stabilize significance across communities.

The proposed trajectory is therefore continuous:

■ distinction ⇌ persistence ⇌ relation ⇌ organization ⇌ physics ⇌ life ⇌ agency
⇌ consciousness ⇌ meaning

The ambition is large. The starting vocabulary is deliberately small.

The central wager of the series is not that one primitive explains everything. It is that many structures usually treated as primitive at one level of explanation may turn out to be consequences of structures available at a lower one.

That distinction matters. A theory may quite reasonably begin with particles, causal relations, graphs, spacetime, probability distributions, organisms or observers if those are the appropriate primitives for the problem it is trying to solve. Emergent Existence asks a different question. It repeatedly takes such starting points and asks whether they can themselves become destinations.

The series therefore follows a methodological rule that recurs throughout all three volumes:

Do not use at one stage what a later stage is supposed to explain.

If orientation has not yet been derived, directional arrows cannot quietly do the explanatory work. If metric distance has not yet appeared, “near” and “far” cannot function as hidden premises. If physical time remains under construction, duration cannot already inhabit the foundational ontology. If the emergence of objecthood is being investigated, fully constituted objects cannot simply be waiting at the beginning. If consciousness is an eventual explanandum, primitive relations cannot be granted awareness merely because doing so would shorten the journey.

This discipline is not an aesthetic preference for minimalism. It is an attempt to keep track of explanatory debt. Whenever the framework must introduce something genuinely new, that addition should be visible. Whenever an apparent derivation merely disguises an assumption in new terminology, the derivation has failed. Parsimony, in this sense, does not mean using the fewest words or symbols. It means minimizing unearned ontological commitments. The Methodology that follows states the standards this implies.

Part One • Introducing the Series

What follows in this part is the shape of the argument itself: what each volume undertakes, and in what order. The second part turns outward, to the research programs this series stands among.

Volume I: Existence

The first volume begins before ordinary physical description. Its initial concern is not what matter does, but what must already be true before something like matter could become describable at all.

Origin introduces the minimally resolved reference condition available to the framework. It is not intended as a spatial location, a moment before the Big Bang, or a metaphysical claim to have surveyed reality at every inaccessible depth. It marks the condition from which no operative distinction is yet available within the framework’s initial relational frame.

Distinction then asks what is minimally required for non-equivalence to become available.

Boundary asks what allows such difference to persist strongly enough to remain consequential across transformation.

Relation considers what happens when retained distinctions no longer exist independently but begin to constrain one another.

Closure asks when a relational organization becomes sufficiently internally integrated that it can function as a higher-order unit without requiring its lower-order organization to disappear.

The next problem is Orientation. Rather than placing arrows into the ontology at the outset, the framework asks whether directional organization can arise when relational roles cease to be interchangeable. Persistent asymmetric constraint becomes a candidate precursor to orientation.

Return then asks what it means for an oriented relational process to re-satisfy the identity criterion of an earlier organization without requiring exact repetition. A returned identity need not be an identical microscopic state.

At this point the framework may possess distinction, retention, organization, closure, orientation and return while still lacking meters, seconds, coordinates or physical forces. That is where quantitative construction begins, still on the formal side of the book.

Formalism introduces mathematical structure only after determining which operations the preceding ontology has earned.

Scale asks whether recursively related organizations can establish stable comparative relations without presupposing an external ruler.

Distance asks when relational separation becomes metrically expressible, once magnitude can be applied to the mediation between relational positions.

Geometry asks when metric relations stop being merely pairwise and begin to constrain one another, so that neighborhoods persist and an effective dimension can be counted.

Space asks when geometric organization becomes consequential: when localizations constrain localizations, so that where something stands limits what else can be the case.

Time asks when retained dependency yields an intrinsic order among relational events, and under what conditions that order admits a measure without any external clock.

Those chapters close Book I, which ends not with spacetime assumed but with spacetime made into a precise problem. Physical construction begins in Book II, which opens on that problem: whether the space and time derived here can

be forced into a single causal geometry, and what would have to be true for them to be.

The subsequent chapters enter recognizably physical territory. Gravity asks whether relationally generated geometry can acquire effective curvature dynamics. Quantum Gravity asks where the smooth description must fail and what more primitive organization may become visible there. Matter asks whether persistent relational modes can appear as localized physical excitations with stable internal properties. Black Holes examine a regime in which geometry, accessibility, information retention and extreme closure meet. Recursive Cosmogenesis considers, speculatively, whether sufficiently extreme closure could recreate conditions analogous to origin at another organizational level.

The closing movement turns toward biology. Complexity examines the multiscale organization required before physical structures can support durable, recursively integrated systems. Life asks when a bounded system begins participating in the maintenance of the conditions necessary for its own continued organization. Only after this does Memory acquire its stronger sense: retained change becoming internally consequential to a self-maintaining system. Finally, Knowing asks when an organized system becomes capable of using retained distinctions to model conditions beyond its immediate state, including aspects of itself.

The endpoint of Volume I is therefore not merely an organism. It is the appearance of a region of the universe within which other regions of the universe can become represented.

Reality becomes locally capable of taking itself as a reference.

Volume II: Consciousness

Volume II begins by refusing an easy equivalence. Life is not consciousness. Memory is not consciousness. Agency is not consciousness. Self-modeling is not consciousness.

The second volume therefore follows the same strategy as the first: separate capacities commonly bundled together and ask which dependencies actually connect them. Reactive behavior can become regulation. Regulation can support valuation. Valuation can guide action selection. Action selection can be modified by learning. Learning can support counterfactual comparison. Counterfactual comparison can become recursively directed toward the system's own representations.

Social interaction introduces additional layers. Communication allows one agent's retained distinctions to alter another's. Multimodal communication may allow relations distributed across gesture, timing, spatial action, language and shared context to produce forms of coordination unavailable to any channel alone.

Sleep introduces another transformation of the reference frame: external coupling can decrease while memory, affect, endogenous association and internal integration become relatively dominant.

Altered cognitive states raise a further question. Can the relational aperture of a biological reference frame temporarily widen, allowing combinations that ordinary cognitive filtering rarely permits? If so, such states may expand the search space from which hypotheses emerge without granting those hypotheses any privileged claim to truth.

Across these problems, Volume II asks whether consciousness appears at a particular point along a continuum of increasing recursive organization or whether some additional principle becomes necessary. If another primitive is required, the framework must admit it.

Volume III: Meaning

Meaning comes later still. A distinction can exist without referring to anything. A physical signal can transmit information without understanding it. An organism can respond adaptively without possessing language. An agent can internally represent a state without participating in a shared semantic world.

Volume III therefore begins where private representation becomes socially consequential. Its subjects include interpretation, value, communication, coordination, norm formation, shared reference, institutions, technology, culture and collective cognition.

A working hypothesis of the series is that meaning may arise when retained distinctions acquire interpretations stable enough to coordinate multiple agents toward shared outcomes. That would make meaning neither a mysterious substance nor merely a synonym for information. It would be a higher-order relational achievement. The full trajectory could then be written:

■ difference ↔ information ↔ organization ↔ agency ↔ interpretation ↔ shared significance

Whether that chain survives detailed examination is a question the later volumes must earn the right to answer.

Part Two • Situating the Series

The first part described what this series attempts. This one asks where it stands: which established programs share its intuitions, where it begins earlier or later than they do, and what each of them would treat as a primitive that this series tries to earn.

The Intellectual Neighborhood

A project with this breadth does not begin in an empty landscape. Its major questions intersect with established research programs in mathematical physics, the foundations of quantum theory, philosophy of science, process metaphysics, information theory, complex systems, theoretical biology and cognitive science. The similarities are important. So are the differences.

Those differences should not be mistaken for a contest over which theory begins with the fewest axioms. A causal-set model does not become inadequate because it takes causal order as primitive, any more than thermodynamics becomes inadequate because it does not derive chemistry from quantum field theory. Explanatory starting points are chosen relative to explanatory aims. The comparisons that follow are therefore intended as coordinates. They identify the landscape into which this series enters.

Distinction as a beginning: Laws of Form. The calculus George Spencer-Brown developed in *Laws of Form* (1969) begins with the making of a distinction. A boundary separates what is marked from what is unmarked, and increasingly elaborate logical structure is generated through operations on those distinctions. The family resemblance to the beginning of this series is unmistakable. Both approaches refuse to begin with a world already populated by richly constituted physical things. Both recognize that distinction precedes many of the categories with which ordinary description begins. Both explore the possibility that surprising complexity can follow from an initially sparse formal vocabulary. The difference appears in what is demanded of that beginning. For *Emergent Existence*, distinction is not intended to arrive already equipped with space, time, information processing, physical interpretation or an observer who performs the distinction. The series asks how much additional structure must accumulate before those interpretations become legitimate. This is the first example of a pattern that recurs throughout the book: a concept that constitutes a foundational operation in one framework may become only the first unresolved stage of another.

“It from bit” and informational pregeometry. The informational turn in foundational physics raises a related possibility: perhaps physical things are

not prior to information but emerge from distinctions capable of carrying informational significance. John Archibald Wheeler's phrase "it from bit" (1989) captures the inversion elegantly. Instead of asking how information describes an already given physical reality, it asks whether physical reality itself may depend on more elementary informational alternatives. This series shares the inversion but treats the word information cautiously. A binary answer already presupposes distinctions that can be stably resolved. Measurement already implies conditions under which one state can function as evidence about another. Information therefore appears here only after difference becomes persistent enough to constrain subsequent relational possibilities (Boundary). The deeper affinity lies in the suspicion that ordinary physical ontology may not occupy the bottom layer.

Structural realism: when relations outlive their relata. Ontic structural realism argues, in its stronger forms, that relational structure may be ontologically prior to the familiar individual objects that appear to participate in it (Ladyman and Ross, 2007; French, 2014). That claim has particular relevance to a framework trying to derive object-like identity. If objects are treated as primitive, relations merely connect already existing things. If relational organization is primary, a different possibility opens: what appears to us as a thing may be the stable persistence of a relational pattern. The series pursues that possibility through equivalence, invariance, boundary, mutual constraint and closure. It nevertheless retains a difficult objection against itself. Calling primitive relata "positions" instead of "objects" would achieve very little if the positions secretly retained all the metaphysical work previously performed by objects. The question is therefore not whether relational vocabulary can replace object vocabulary. It is whether relational structure can do explanatory work that an object-first ontology would otherwise have to assume.

Influence theory: physics from directed relational events. Influence theory, developed by Kevin Knuth and collaborators (Knuth and Bahreyni, 2014), undertakes one of the closest neighboring derivational projects. It begins from entities participating in discrete directed influence events and develops a partially ordered structure from which familiar quantities associated with space, time, energy, momentum and mass can be reconstructed. Its importance for this series is methodological as much as physical: it demonstrates that concepts ordinarily introduced as basic physical quantities can instead be treated as emergent descriptions of a more primitive relational structure. The present series attempts to begin one explanatory move earlier. Directed influence already contains orientation; the participating entities already possess an identity sufficient to take part in influence; the resulting event structure already carries an order relation. Here those structures are separated and interrogated individually. That should not be confused with

superiority. Influence theory chooses primitives suited to the physics it wants to recover. Emergent Existence asks whether some of those primitives can themselves be made provisional.

Causal set theory: order before geometry. Causal set theory proposes that continuum spacetime may not be fundamental (Bombelli, Lee, Meyer and Sorkin, 1987). A discrete partial order can instead serve as the underlying structure, with causal ordering carrying much of the information ordinarily associated with spacetime geometry. This produces one of the clearest conceptual precedents for the transition from order to geometry. The lesson is significant: geometry need not be the stage upon which relations occur, since relational order may participate in generating the stage itself. The series arrives at that possibility by another route. Its early chapters distinguish dependency from orientation, orientation from causality, causality from temporal metric, and temporal metric from the broader relational order from which it might emerge. Where causal sets offer an already disciplined mathematical account of proto-spacetime order, they may ultimately provide a valuable convergence test for whatever order this framework succeeds in deriving.

Quantum graphity: symmetry becoming locality. Quantum graphity (Konopka, Markopoulou and Severini, 2008) explores a striking transformation. A highly connected and highly symmetric quantum graph can pass into a lower-energy regime in which permutation symmetry is reduced and a more ordered, low-dimensional, local structure emerges. The similarities are especially relevant to the physical middle of Volume I. Symmetry need not characterize every effective scale in the same way. Locality may itself be emergent. Dimensional structure can become a property of organization rather than an eternal container in which organization takes place. These ideas resonate with the series' distinction between unresolved variation and effective asymmetry: a structure that appears symmetric at one descriptive level need not exhaust all lower-order distinctions, which is how this book defines Origin (1.3), and perturbations inconsequential at one scale may become collectively decisive at another. Quantum graphity also illustrates how much mathematical machinery becomes available once graph structure, quantum states, energy and Hamiltonian dynamics are granted. Those tools may later prove indispensable. The question here is simply when their use becomes justified.

Computational universe models: simple rules, unexpected worlds. Hypergraph rewriting and related computational-universe approaches (Wolfram, 2020) investigate how simple local update rules can produce structures resembling causal networks, effective spacetime geometry, relativistic behavior and quantum-like phenomena. Their relevance lies in recursive generativity. A rule

need not explicitly contain the macroscopic structure eventually produced by repeated application; rich higher-order behavior can appear through composition, recursion, constraint and coarse-graining. This matters because the series does not seek a foundation containing miniature versions of everything that later emerges. Higher-order structure should not already be written into the primitive vocabulary. Computational models provide an unusually concrete arena in which that requirement can be tested. If geometry appears only when geometric assumptions have been encoded into the update rule, little has been explained. If robust geometric behavior emerges under broad classes of rules that contain no such target specification, something more interesting has occurred. That standard is central to the computational companion's program.

Process philosophy: from becoming to organism and experience. Process philosophy offers perhaps the nearest historical precedent for the breadth of the series. In Alfred North Whitehead's *Process and Reality* (1929), the world is not fundamentally composed of inert substances sitting inside a container. Reality is constituted by processes, events, relations, integration, persistence and the recursive formation of higher-order societies, so that matter, organism, experience and value belong to one continuous ontological story. That continuity is deeply congenial to Emergent Existence. The divergence is equally instructive. In process metaphysics of the Whiteheadian kind, experiential character enters near the foundation: elementary actuality already involves something analogous to prehension, feeling or valuation, even though ordinary consciousness appears much later. The present series places the burden elsewhere. Its earliest relation need not feel anything. It need not value. It need not represent. It need only differentiate and constrain. This changes the explanatory direction. Rather than asking how sophisticated consciousness develops from elementary experience, the later volumes must ask whether experience itself can emerge from organizations initially specified without experiential properties. The two approaches may approach many of the same destinations while traveling from opposite sides of one of philosophy's oldest divides.

Constraint and the emergence of life. Constraint-based accounts of biological organization provide an especially important bridge between physics and life (Montévil and Mossio, 2015; Moreno and Mossio, 2015). In such approaches, organisms are not defined simply by possessing a particular material ingredient. Their organization depends on interlocking constraints that channel otherwise available physical processes, maintain boundaries, reproduce enabling conditions and preserve forms of organization far from equilibrium. The relevance to this series is immediate. Its early notion of relational constraint begins far below biology: one relation can reduce or alter the

possibilities available to another (Relation). That idea becomes progressively richer as organizations acquire boundaries, closure, persistence and the ability to participate in maintaining the very conditions that support them. The biological threshold then ceases to look like the sudden arrival of an entirely new metaphysical substance and may instead represent a qualitative reorganization of constraint. This is also where information changes meaning. A retained difference that merely influences a later physical state is not yet a memory used by a living system to regulate its own future organization. The distinction between retention, path dependence, memory, agency and interpretation becomes increasingly important as the series proceeds.

Markov blankets and nested autonomy. Markov-blanket approaches formalize boundaries separating internal and external states through statistical dependency structure (Pearl, 1988; Friston, 2013). Their extension into nested blankets (Kirchhoff, Parr, Palacios, Friston and Kiverstein, 2018) offers a powerful way of describing organisms and other autonomous systems as layered organizations whose boundaries exist at multiple scales. This provides a mature mathematical analogue for several ideas developed much earlier in this series: boundary, nested identity, higher-order closure, and the possibility that one integrated organization can become a component of another. There is also a useful shift in vocabulary. What begins here as logical and relational separability can later become statistical conditional independence. What begins as closure of constitutive dependency may eventually admit probabilistic characterization. What begins as relationally defined higher-order identity may later become recognizable as an autonomous statistical entity. The progression is valuable precisely because the later language is richer: it tells us what additional structure becomes available once probability, dynamics and physical time have entered the ontology.

Projection, perception and the limits of a reference frame. Theories that treat ordinary perception as an adaptive interface rather than a transparent window onto fundamental reality (Hoffman, Singh and Prakash, 2015) introduce another important distinction: the world as physically organized need not be identical to the world as resolved by an observer. Emergent Existence shares the weaker form of this claim. A reference frame can fail to resolve a distinction without proving that no distinction exists (4.5). Two underlying states may therefore be physically or relationally non-identical while remaining indistinguishable to a particular observer or level of coarse-graining. The series does not infer from this that spacetime is merely perceptual. Instead it separates two projections, from underlying relational structure to effective physical structure, and from effective physical structure to an observer-resolved world. The first belongs primarily to Volume I; the second increasingly to Volume II. Confusing them would make consciousness responsible for

constructing a physical world before consciousness had itself been explained. Keeping them separate lets perception become part of the story without turning it into the foundation of the story.

What These Neighboring Programs Reveal

Taken together, these approaches establish that the individual intuitions explored in this series do not come from an intellectual vacuum. Distinction has been treated as foundational. Information has been proposed as prior to matter. Relations have been placed before objects. Order has been placed before spacetime. Geometry has been modeled as emergent. Simple recursive systems have generated unexpectedly rich macroscopic behavior. Constraint has been used to explain biological organization. Nested boundaries have been used to characterize autonomous systems. Process philosophies have attempted continuous accounts spanning matter, organism, experience and value.

The question is therefore not whether Emergent Existence can claim exclusive ownership of these ideas. It cannot, and need not. Its more interesting possibility lies in their ordering. Concepts that usually belong to separate theories can be arranged into a dependency sequence and subjected to the same test:

What is the minimum previously earned structure from which this next property can follow?

If orientation truly follows from persistent asymmetric constraint, then direction need not be primitive. If metric separation follows from relational organization and scale, distance need not be primitive. The same test runs through the rest of the series. Metric time, objects, memory, agency, consciousness and socially stabilized meaning each need not be primitive if it follows from something earlier: ordered propagation at scale, invariant organization, retained distinctions that become internally consequential to a self-maintaining organization, valuation over possible relational states, a further form of recursive integration, and coordinated interpretation among agents.

But every if matters. A long chain of derivation is only as strong as its weakest bridge. The series therefore makes no promise that the ladder reaches uninterrupted from distinction to meaning. Its commitment is narrower and more demanding:

At each stage, determine what has actually been earned.

Where a neighboring theory begins with a primitive that proves irreducible, that may mark the legitimate stopping point of this reduction. Where a derivation succeeds, the ontology becomes thinner. Where it fails, the failure should remain visible.

The journey of Emergent Existence is therefore not a march toward a conclusion already decided. It is an attempt to discover how far a universe can build upward before reduction reaches a genuine boundary. And when we find that boundary, we should not conceal it behind new terminology or metaphysical excess. It must identify what remains irreducible and say transparently:

“Until there is a deeper explanation, may this serve as our foundation.”

The earned-structure map

what each chapter earns, from Origin down



Origin is the starting point and two rungs are commitments; every other rung is derived from rungs above it.

The ladder is one reading order: its sequence does not by itself imply dependency, which each chapter establishes separately.

The earned-structure map. Each chapter earns one rung from rungs above it, beginning from Origin and two foundational commitments, and Book I hands what it has earned to Book II.

Selected References Cited in the Introduction

- Bombelli, L., Lee, J., Meyer, D., & Sorkin, R. D. (1987). Space-time as a causal set. *Physical Review Letters*, 59(5), 521–524. doi:10.1103/PhysRevLett.59.521.
- French, S. (2014). *The Structure of the World: Metaphysics and Representation*. Oxford: Oxford University Press.
- Friston, K. (2013). Life as we know it. *Journal of the Royal Society Interface*, 10(86), 20130475. doi:10.1098/rsif.2013.0475.
- Hoffman, D. D., Singh, M., & Prakash, C. (2015). The interface theory of perception. *Psychonomic Bulletin & Review*, 22(6), 1480–1506. doi:10.3758/s13423-015-0890-8.
- Kirchhoff, M., Parr, T., Palacios, E., Friston, K., & Kiverstein, J. (2018). The Markov blankets of life: Autonomy, active inference and the free energy principle. *Journal of the Royal Society Interface*, 15(138), 20170792. doi:10.1098/rsif.2017.0792.
- Knuth, K. H., & Bahreyni, N. (2014). A potential foundation for emergent space-time. *Journal of Mathematical Physics*, 55(11), 112501. doi:10.1063/1.4899081. Preprint arXiv:1209.0881.
- Konopka, T., Markopoulou, F., & Severini, S. (2008). Quantum graphity: A model of emergent locality. *Physical Review D*, 77(10), 104029. doi:10.1103/PhysRevD.77.104029.
- Ladyman, J., & Ross, D., with Spurrett, D., & Collier, J. (2007). *Every Thing Must Go: Metaphysics Naturalized*. Oxford: Oxford University Press.
- Montévil, M., & Mossio, M. (2015). Biological organisation as closure of constraints. *Journal of Theoretical Biology*, 372, 179–191. doi:10.1016/j.jtbi.2015.02.029.
- Moreno, A., & Mossio, M. (2015). *Biological Autonomy: A Philosophical and Theoretical Enquiry*. Dordrecht: Springer. doi:10.1007/978-94-017-9837-2.
- Pearl, J. (1988). *Probabilistic Reasoning in Intelligent Systems: Networks of Plausible Inference*. San Mateo, CA: Morgan Kaufmann.
- Spencer-Brown, G. (1969). *Laws of Form*. London: George Allen & Unwin.
- Wheeler, J. A. (1989). Information, physics, quantum: The search for links. Presented at the 3rd International Symposium on Foundations of Quantum Mechanics, Tokyo, 1989; published in W. H. Zurek (ed.), *Complexity, Entropy and the Physics of Information*, Santa Fe Institute Studies in the Sciences of Complexity, vol. VIII, pp. 3–28. Redwood City, CA: Addison-Wesley, 1990. The source of the phrase “it from bit.”
- Whitehead, A. N. (1929). *Process and Reality: An Essay in Cosmology*. Gifford Lectures delivered in the University of Edinburgh during the session 1927–28. New York: Macmillan; Cambridge: Cambridge University Press.
- Wolfram, S. (2020). A class of models with the potential to represent fundamental physics. *Complex Systems*, 29(2), 107–536. doi:10.25088/ComplexSystems.29.2.107. Preprint arXiv:2004.08210.

Note on these references. These works locate the series among neighboring programs; none is evidence for its claims. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Methodology

This project is not an attempt at a Theory of Everything, and it should not be read as working toward one. It is an attempt to build a minimal, recursively generative ontology and to test how far it can be extended without importing higher-order structure too early. Every inferential bridge is stated, every additional assumption is marked where it enters, and every place the argument currently stops is named as an open problem rather than smoothed over.

The umbrella question this book asks is: how much of observable structure can be reconstructed from minimal logical-relational primitives? Framed this way, the ambition stays intact without implying that the series claims exhaustive unification of physics, mathematics, consciousness and meaning. The working form of that question across the volumes is narrower still and stated as a hypothesis to be tested, not assumed: can increasingly rich physical, biological, cognitive and social structures be derived from a parsimonious, recursively generative relational foundation? The chapters ahead do not assume the answer is yes, and a negative answer, a specific point beyond which no further reduction succeeds, would still leave everything established up to that point intact.

The methodological aspiration follows from this: construct the strongest derivational scaffold possible, identify every unresolved bridge explicitly, and leave those bridges in a form that can be mathematically, computationally or empirically extended by later work. A gap explicitly located is worth more than a conclusion reached by hiding an assumption, and the Hypothesis Status Register in the back exists to make that trade visible rather than implicit. Five standards follow:

1. Minimize primitives.
2. Mark every additional assumption where it enters.
3. Separate formal consequence from physical identification.
4. State plainly where derivation ends and analogy begins.
5. Where a claim cannot yet be derived or tested, name it as a research problem rather than assert it.

Three uses of a concept must be kept apart, because the discipline applies to only one of them.

A **constitutive** use does explanatory work inside a derivation. Here the rule is strict: at a given stage, the ontology may not use a property that stage has not earned. Coordinates cannot explain why geometry exists if coordinates arrive later; metric duration cannot be a premise of a chapter that precedes Time.

A **representational** use describes, in a richer formalism, a structure that has already been derived. This is admissible when it is labelled, and the Formal Admissibility Rule states the condition: extra structure in the notation may not be read back into the world it describes.

A **diagnostic** use applies a later or external framework to the output of a derivation, to ask whether that output reproduces a target property. This too is admissible, and it is how the framework becomes testable at all.

■ do not use the destination to build the road; once the road is built, use the destination to check whether it arrived

We are not occupying the ontology at its earlier stages. We are present-day investigators with geometry, clocks, fields, computers and mathematics already to hand, and it would be perverse to refuse those instruments when asking whether a pre-geometric proposal actually yields geometry. A pre-geometric model may not assume Euclidean distance; its emergent separations may certainly be compared against Euclidean geometry afterwards. A pre-temporal model may not assume proper time; its intervals may be checked against proper-time relations. A pre-quantum model may not assume Hilbert space; its effective observables may be tested for quantum-statistical behaviour. Forbidding the mature structure as a target would leave the framework almost impossible to falsify.

■ higher-order structure $\notin$ premises of the derivation; higher-order structure $\in$ diagnostics applied to its outputs

One guard keeps the second use from quietly becoming the first. A diagnostic influences a derivation not by entering its rules but by deciding which model is kept after the result is seen. So the diagnostic, its control and its criterion are declared before the run, and a failed diagnostic is reported rather than retuned away. Where that discipline lapses, the target has been smuggled back in through model selection, which is harder to notice than smuggling it into the premises and does the same damage.

Some claims in what follows are close to definitional. Others are derived within stated assumptions, or demonstrated computationally for a toy model, or conjectural but sharply formulated, or simply markers of where the framework's reach currently ends. That gradient of confidence is not a weakness in the argument; hiding it would be. If later work replaces parts of this formalism, the scaffold will still have done its job.

Chapter 1

Origin: Before Difference Becomes Possible

Claim ~ Origin is the minimally resolved reference condition from which no operative distinction is available at the framework's initial resolution. We approach it by conceptually unbuilding the richly compressed world of ordinary experience.

Chapter discipline. The opening human perspective is a narrative entry point, and the descent sets it aside. The chapter's task is to establish the least committed starting horizon from which Difference can begin the constructive derivation.

1.1 Looking Back from Now

You are reading this book from a world that is apparently navigable. There are objects. Some are near and some are far. Events unfold. Things persist through change. Other people occupy the same surroundings. You remember, anticipate, compare, choose, speak, and ask what any of it means.

From inside that richly organized experience, one question arrives almost effortlessly:

What am I doing here?

It is a small question, but with a great deal to unpack.

"What" assumes that something can be identified. "I" assumes that an organization can distinguish itself from what it is not and persist long enough to refer to itself. "Doing" assumes change. "Here" assumes position, separation, and some structure in which positions can differ. Even the possibility of an answer assumes alternatives: the answer might have been otherwise.

You arrive late to your own question. By the time you can ask about your existence, an immense amount of structure has already been compressed into your perception and your language.

That compression is what makes your lived experience manageable. A map is useful because it leaves out unnecessary details about the land it illustrates, and perception works the same way. Behind a single tree stand more molecular, optical, causal and historical relations than anyone could hold in mind at the same time, yet what reaches you is simply the tree, with a few

verdicts that matter based on your intent. For example, does it offer shade; does it bear fruit; can its wood build a raft?

The same simplicity that makes a map useful makes it a poor place to begin a theory of the land.

If we begin from the world exactly as it appears, then much of what we hope to explain has already entered unnoticed. We would be using objecthood to explain objects, spatial intuition to explain space, temporal intuition to explain time, and agency to explain how agency became possible.

So the first movement of this book is not construction. It is conceptual descent.

experienced world $\mapsto$ hidden commitments $\mapsto$ thinner commitments




Figure 1.1. The descent to origin, which the rest of the book climbs back from.

We begin with the compressed world of experience because that is where you already stand. Then we ask what must be removed before the framework stops borrowing the structures it intends to derive.

Your frame motivates the descent, but that frame can no longer be applied once the descent has begun.

There are two distinct frames in play that should not be confused. Yours is rich: perception, embodiment, memory, language, geometry, temporal experience, social interpretation, self-reference. The framework's initial resolving frame is deliberately poor, the resolving capacity available before any operative distinction has been introduced.

So becomes the prerequisite for reading Emergent Existence:

I ask you to set aside your personal reference frame for a while and take up the framework's resolving frame instead, which begins with nothing resolved and gains only what each chapter earns. In this way we can make the journey unencumbered by the familiar perspectives we have inherited.

1.2 Unbuilding the Familiar

Look up from the page. There are things in places, some near and some far, some changing and some holding still. None of that took effort. The sorting was finished before you looked. The distinctions you make without trying, and the assumptions that let you make them, are your reference frame. This section takes it apart one layer at a time.

Start with place. To say that something is here rather than there already distinguishes positions. Near and far add magnitude to that separation. A path adds ordered connection. Geometry organizes such relations into a coherent form.

Now peel back the place layer.

Without geometric position, an object can still be conceived as something that remains itself while other things differ from it. But that already presupposes boundary and persistence. An object has to be distinguishable from what it is not, and its identity must survive at least some change.

Now peel back the objecthood layer.

What remains might still be an organization: several relations that constrain one another strongly enough to behave as a unit. Yet organization already assumes relations, and relations already assume that something can differ.

Now peel back the organization layer.

Perhaps difference can persist through transformation. If it does, the difference can constrain what follows. That is already close to information in the stronger sense the later chapters will use.

Now peel back the persistence layer.

Look up again. There is nothing left to sort, only the vicinity of difference itself. Now ask one more question:

What must be available before even a difference can become operative?

At that point there is no useful scene left to imagine. A scene would already have parts. A background would already distinguish what lies against it. A point would invite location. A moment would invite time.

The descent therefore does not uncover a hidden picture of the beginning. It removes our entitlement to picture one.

What remains is a conceptual limit: the least resolved condition from which the possibility of distinction can be discussed without first importing the world that distinction will later help to build.

1.3 A Beginning Without a First Moment

The word “beginning” usually carries a clock. In this book it carries a ledger instead: what has been earned, and in what order.

A physical theory may ask whether the universe has a first moment, whether an earlier phase preceded our present spacetime, or whether temporal extension is finite or unbounded. Those questions have to wait. They are asked in Time, and time has not yet been earned. Origin’s question comes before them in a different sense.

If one concept cannot be specified without another, the prerequisite is logically prior even if no physical time separates them. A coordinate system is conceptually downstream of distinguishable positions. Measurement is downstream of something that can be compared. A retained difference is downstream of a difference that can exist at all.

Here we use our ledger to distinguish logical or derivational priority from physical temporal priority.

№ 1.1

derivational priority $\neq$ temporal priority

When a later chapter says one structure comes “before” another, read it from the ledger, not the clock: it records what must be earned first, not what happened first.

This distinction will matter repeatedly. Distinction will use recursion without treating its index as metric time. Boundary will speak of persistence without duration. Orientation will earn asymmetry without spatial direction. Return will earn re-entry without a physical period. Time will eventually ask what more is required before ordered transformation deserves a temporal reading.

For now, “beginning” means the point at which the derivational bookkeeping starts.

1.4 The Limit of Subtraction

Conceptual subtraction can only take us so far.

We can remove assumed objects, locations, durations, observers, causes, laws, and even resolved differences. But subtraction itself does not prove that what remains is literally nothing. It tells us only that the framework has reached the point where it is no longer entitled to specify further structure.

That distinction matters because “nothing” is not a neutral word. Absolute nothing would mean not merely an empty region or an unoccupied state, but the absence of entities, relations, laws, possibilities, locations, times, and any structure by which one condition could differ from another. Once such a condition is assigned a role in an argument, as a state, source, substrate, reference, or cause, it has already been given more structure than absolute nothing permits.

Nor do familiar scientific and mathematical uses of emptiness solve the problem. An empty set belongs to a formal system. A vacuum belongs to a physical theory. A model without classical spacetime may still contain mathematical relations, dynamical constraints, or admissible alternatives. Each can be extremely sparse without being structureless.

The descent therefore reaches neither a hidden primordial object nor a demonstrated metaphysical void.

It reaches a limit on what the framework can resolve.

What the framework can do is choose a starting condition weak enough not to settle that question in advance.

The constructive ascent will begin from there: not from a claim about what ultimate reality must secretly be, but from the least committed condition from which a first Difference can be introduced without borrowing the richer structures the book is trying to derive.

That reference condition is what this book calls Origin, written as Ω .

1.5 Ω : The Minimally Resolved Reference Condition

Origin can now operate as Ω .

The symbol is deliberately spare. It does not name a primordial substance. It does not name a container in which the universe waits. It does not name an instant at the start of a timeline.

It names a role.

Definition. A condition is undifferentiated relative to a resolving frame when no relation available within that frame distinguishes one part, state, or feature from another.

Origin, Ω , is the minimally resolved reference condition: the condition from which no operative distinction is available within the framework's initial resolving frame.

$$\text{Res}_{w_0}(\Omega) = \emptyset$$

This notation should be read cautiously. It does not claim that Ω is literally the empty set. It says that the framework's initial resolution returns no operative distinction.

The word operative matters. A distinction is operative when it is available to constrain the derivation. Origin does not assert that Ω contains hidden structure, and it does not assert that hidden structure is impossible. It refuses to infer ontological absence from a failure of resolution.

failure to resolve a distinction $\neq$ proof that no distinction exists

This is an important commitment for later chapters. Boundary will generalize the idea into frame-relative resolvability. Orientation will rely on it when distinguishing absolute symmetry from symmetry at a given resolution. The framework must therefore preserve the weaker claim made here: Ω is undifferentiated at the starting resolution, not metaphysically guaranteed to be featureless under every possible description.

The initial resolving frame is not an observer. No mind has been introduced. It is simply the framework's declared starting capacity: what the ontology is permitted to resolve before any distinction has been admitted.

If later work shows that Ω can be eliminated as an entity-like term and replaced by the statement "no operative distinction is yet available," the framework becomes cheaper. Origin leaves that reduction open.

The strongest current formulation is therefore not that Ω is the first thing that existed.

It is this:

Ω is the least conceptually committed reference condition from which the framework chooses to begin.

1.6 What Ω Does Not Give Us

A thin starting condition is useful only if we resist enriching it by intuition.

Ω is not a place. A place requires distinguishable positions, and distinguishable positions have not been earned.

Ω is not a moment. Earlier and later require an ordering that has not been given a temporal interpretation.

Ω is not a substance. Nothing is said to be made of Ω , and no internal parts have been specified.

Ω is not a cause. It exerts no force, initiates no mechanism, and supplies no dynamics merely by being named.

Ω is not an observer. “Reference” does not mean a viewpoint possessed by a mind.

Ω is not an anchor. Difference and Distinction preserve exchange symmetry and Boundary constructs identity without a center. A reference role is earned only later, when Closure produces a dynamically persistent higher-order identity whose representative-independent addressability can function as the organizational anchor A_F .

Ω is not a spatial point. A mathematical point can be defined without coordinates in some formalisms, but ordinary language strongly suggests location. This framework therefore avoids treating Ω as a point until a later geometry has earned that interpretation.

$\Omega \neq (x, y, z, t)$

These negatives do not tell us what ultimate reality is. They tell us what we are not yet entitled to use.

That is the discipline of the opening chapters: subtraction first, construction second.

1.7 The Empty Set as an Analogy, Not an Ontology

There is one mathematical image worth retaining because it shows how little can be needed for structure to begin.

Start with the empty set:

$\emptyset$

Now form the set containing it:

$\{\emptyset\}$

The two expressions are not the same. Continue:

$\emptyset \mapsto \{\emptyset\} \mapsto \{\emptyset, \{\emptyset\}\} \mapsto \dots$

The lesson is not that the universe is a set. Set theory already presupposes logic, axioms, and membership. It is therefore far too structured to serve as the literal ontology of Origin.

The lesson is more modest. A formally empty base and an operation that distinguishes can generate a richer structure without requiring a new material substance at every step.

That pattern is why the analogy is useful:

distinguishing $\rightsquigarrow$ new relational structure

Spencer-Brown's instruction to draw a distinction and Bateson's later description of information as a difference that makes a difference belong to the same broad family of intuitions. The framework borrows the narrow insight that differentiation can be structurally generative.

The empty set therefore models one aspect of Ω : a reference from which differentiated construction can be illustrated. It does not prove that Ω exists, that the universe began as $\emptyset$, or that physical reality is set-theoretic.

$\Omega \neq \emptyset$

The distinction matters because later chapters must be able to use Ω without inheriting set membership as a hidden primitive.

1.8 The Inversion

We have now reached the limit of the descent.

You have disappeared from the ontology, along with the objects you perceived, the geometry in which they seemed located, the temporal order through which they seemed to change, and the higher-order categories through which the world became actionable.

We did not prove that reality began in Ω .

We established Ω as the least committed horizon from which this research program will attempt reconstruction.

That distinction changes the burden of the book.

Until this point, our movement was subtractive. We asked what could be bracketed without losing the possibility of asking the next question.

From this point forward, the movement is constructive.

We turn around.

Can the world we just conceptually dismantled be reintegrated through derivation alone, without smuggling back in the structures it took apart?

That is the generative wager of Volume I.

$\Omega \rightsquigarrow$ Difference $\rightsquigarrow$ Distinction $\rightsquigarrow$ Boundary $\rightsquigarrow$ Relation $\rightsquigarrow$ Closure $\rightsquigarrow$ Orientation $\rightsquigarrow$ Return $\rightsquigarrow$ Formalism $\rightsquigarrow$ Scale $\rightsquigarrow$ Distance $\rightsquigarrow$ Geometry $\rightsquigarrow$ Space $\rightsquigarrow$ Time

The arrows are where the book lives.

The ascent is not allowed to inherit the phenomenological richness of the descent. The fact that the reader already knows what space, objects, direction, measurement, and time feel like does not license the ontology to use them.

This gives the volume its governing constraint:

Do not assume at one level what a later level is intended to derive.

A second constraint follows:

Do not promote a computational or representational convenience into ontology when a thinner relation already does the work.

The descent supplies motivation. The ascent must supply justification.

phenomenological deconstruction suggests a dependency $\neq$ derivational proof of that dependency

If a later chapter shows that the order proposed here is wrong, the architecture must change. Narrative elegance does not get to settle ontology.

1.9 The Starting Claim and the Two Commitments

Everything later in the book rests on two propositions stated here: a claim about what any observable reality requires, and the two working commitments from which the construction begins.

The first is the starting claim, and it concerns persistence.

Proposition 1A - retained distinction. An observable relational difference must be able to survive transformation long enough to constrain later states.

distinction $\rightsquigarrow$ persistence $\rightsquigarrow$ retained distinction $\rightsquigarrow$ information

This separation is essential. Difference is not automatically information. The later concept of a relational bit, r_{ij} , depends on a distinction becoming persistent enough to remain resolvable and consequential.

The second names the commitments themselves.

Proposition 1B - two working commitments. The framework provisionally treats difference, a bare non-equivalence prior to measure, direction or observer, as the first commitment from which relational differentiation begins, and admissible transformation, a constraint on what may follow what, as the second. Distinction is the later achievement by which difference becomes operative in that succession.

This proposition remains provisional because Origin does not explain why difference is admitted at all.

The open problem should remain visible:

Why does differentiation occur at all?

Several possibilities may later compete: differentiation could be logically unavoidable, dynamically favored, unstable to suppress, or simply the primitive fact from which explanation begins. The current framework has not earned a verdict among them.

Without an alternative precursor, we accept difference as a possible foundational premise, given a world in which innumerable distinctions arguably exist. For now, the working strategy is empirical in the broad methodological sense: accept the minimum primitive provisionally, then test how much structure can be built before additional primitives become necessary.

1.10 Origin as a Role That Can Reappear

Treating Ω as a reference role rather than a first physical object has an important downstream consequence.

An origin need not occur only once.

Later, a relational organization may become sufficiently closed and stable that it can function as a new unit for higher-order construction. Closure asks whether completion can therefore supply a new origin at a higher organizational level.

■ relational organization at level n $\rightsquigarrow$ closed identity O_F at level $n+1$ $\rightsquigarrow$ organizational anchor A_F $\rightsquigarrow$ higher-order relational construction

Level indices mark organizational level, not physical time. Ω remains the initial minimally resolved reference condition; it is not copied upward as a privileged pole. Higher-order originhood is re-instantiated by Closure.

This matters again in Return. A higher-order identity may depart from its organizational anchor A_F , the reference earned in Closure, transform, and later re-enter the identity class associated with that anchor without reproducing the same lower-order state. Return is re-entry relative to that earned reference, not recurrence to Ω .

The possibility of return depends on a distinction first made here: a reference role can remain meaningful even when its later realizations are not identical in every detail.

So Origin must preserve two ideas at once:

Ω is minimal at the initial resolution.

Originhood is a role that may later be re-instantiated by higher-order organization.

Those claims are compatible because the later origin is not primitive in the same sense. It is earned by closure, persistence, and addressability.

This recursive reuse of reference will later support comparison and, eventually, endogenous standards of scale.

1.11 Relation Before Geometry

The ascent will fail immediately if the first relation already smuggles in space.

So one further constraint belongs in the opening chapter.

A relation can be formally specified without assigning coordinates, lengths, angles, or a spatial embedding. That mathematical fact does not prove that physical reality is relational at bottom, but it shows that relation does not logically require geometry.

This volume therefore treats geometry as a target rather than a background.

Any primitive relation introduced in Difference must avoid silently meaning near, far, inside, outside, earlier, later, toward, away, or adjacent in physical space.

Likewise, recursion may establish an order of derivation without yet establishing duration. Orientation may later distinguish relational roles without becoming a spatial axis. Return may later re-establish identity without becoming a geometric loop.

These separations are not semantic fussiness. They are what make the volume's final question non-circular:

Can a sufficiently organized relational system earn geometry without geometry having been assumed in the relations used to construct it?

Book I carries the relational derivation through Time. Book II begins where the separately earned structures of Space and Time must be shown to support a physically instantiated spacetime and the dynamics associated with it. Geometry, Space and Time are therefore targets of the prephysical derivation rather than evidence that physical spacetime has already been obtained.

Whether an earned geometry can acquire the dynamical structure of physical spacetime belongs on the far side of the volume. That later test remains essential, but it is no longer a promise Origin needs to front-load.

1.12 Competing Readings of Origin

Ω is a methodological starting condition, not a declaration that every other account of beginnings is false. Several readings remain available.

A physical initial state. Reality may have possessed some earliest or boundary physical condition. If so, that condition belongs to a theory with physical structure. It may later realize part of the framework, but it cannot define the minimal pre-geometric starting point without importing what Volume I is trying to earn.

Absolute nothing. One may hold that there was literally nothing and that something arose, against Parmenides' maxim that nothing comes from nothing. The present framework does not adopt that claim, because absolute nothing cannot function as a structured reference condition without ceasing to be absolute nothing.

Perfect uniformity. One may instead imagine an origin in which something exists but every available feature is exactly homogeneous. That possibility is compatible with the framework only as one interpretation among others. Origin

does not assert that Ω is absolutely uniform; it says only that no operative distinction is available at the framework's initial resolution.

Unresolved variation. A different possibility is that variation exists but cannot yet be resolved by the starting frame. The framework permits this reading but does not posit it. Failure to resolve a distinction does not establish either that no distinction exists or that hidden structure must exist.

No temporal beginning. Reality may have no first physical instant. That possibility is compatible with this framework because Ω is defined by derivational role, not by temporal location.

An external ground. A creator, necessary principle, mathematical structure, or metaphysical ground may ultimately explain why there is anything to describe. Origin neither proves nor disproves such proposals. It asks whether the internal derivational program requires them before it can begin.

These possibilities should not be collapsed into one another. Absolute nothing, perfect uniformity, and unresolved variation are different ontological claims. Ω commits to none of them. It names only the least resolved reference condition from which the framework begins.

The reference-state reading is chosen for one reason: it is the least committal starting condition that keeps the book's constructive question open.

1.13 Objections and Replies

Objection 1: Ω is merely “nothing” renamed.

Reply: The definitions differ. Absolute nothing is an ontological claim of absence. Ω is a resolution-relative reference condition: no operative distinction is available at the initial frame. It says less, not more.

— — — —

Objection 2: Any “condition” presupposes a space of possible conditions.

Reply: The language risks exactly that implication. The framework should therefore prefer the relational content over the noun. If Ω can ultimately be reduced to “no operative distinction is yet available,” the ontology becomes cheaper. Until then, Ω is a working term whose entity-like reading remains provisional.

— — — —

Objection 3: The conceptual descent proves nothing about the universe.

Reply: Correct. Its role is foundational orientation, not proof. It exposes how much ordinary experience presupposes and motivates the decision to begin from a thinner reference condition. The ascent must justify every constructive step independently.

Objection 4: If Ω is unresolved, what produces the first difference?

Reply: Origin does not solve that problem. It deliberately withholds a verdict on whether Ω is absolutely uniform or only unresolved at the initial frame. In either case, the framework still owes an account of why Difference becomes available and why admissible transformation later makes it operative. That burden is not discharged by appealing to hidden variation.

○ SPECULATIVE Ω is unresolved rather than uniform: it holds variation below what the initial frame can resolve. The first operative distinction arises when one such variation, amplified under admissible transformation, crosses that threshold, and the rest of this book follows as a cascade: retention, relation, closure, orientation, return, each building on what the last made available. Physically, that variation is energy, and the crossing is the first asymmetry in its distribution.

Objection 5: If unresolved variation is allowed, hidden structure can be invented to explain anything.

Reply: The framework does not posit hidden structure. It only refuses the inference from non-resolution to absolute absence or perfect uniformity. Any specific hidden variation introduced later would require independent justification and would count as an added commitment.

Objection 6: Then the framework has not explained why differentiation occurs at all.

Reply: Correct. Origin defines the starting horizon; it does not derive Difference from Ω . Difference remains the first constructive commitment beyond Origin. A future reduction would have to show how non-equivalence arises from weaker structure without already containing dyadicity, orientation, succession, or another equivalent primitive.

Objection 7: The historical parallels make Ω a version of the *apeiron* or Peircean indeterminacy.

Reply: They do not. Those comparisons identify neighboring questions, not inherited ontology. Anaximander's *apeiron* functions as a cosmogonic source, and Peirce's cosmology attributes genuine roles to chance, continuity, habit, and the development of law. Ω carries none of those commitments. It is defined only by the absence of an operative distinction at the starting resolution.

Objection 8: The empty-set analogy imports set theory.

Reply: Only as an analogy. It demonstrates a formal pattern in which differentiation generates structure. Membership, axioms, and set-theoretic ontology are not inherited by the model.

Objection 9: Starting with the reader makes the theory anthropocentric.

Reply: You supply the entry point, not the framework's primitive. The chapter immediately dismantles the conditions that make a questioner possible. A later volume must derive agency rather than assume it.

Objection 10: The descent assumes the very dependency order the book later claims to derive.

Reply: The descent proposes a conceptual map. It does not certify the arrows. Later chapters are free to alter the order if their formal analysis requires it. Derivational success, not literary sequence, determines what survives.

Objection 11: If Ω cannot be observed directly, it is insulated from evidence.

Reply: Ω is not offered as a directly observable physical state. It is constrained downstream. If the framework cannot construct the structures it claims from the commitments attached to Ω , or if the construction requires hidden geometry, time, objecthood, or other undeclared primitives, the starting proposal loses explanatory value.

1.14 Ontological Defensibility Pulse: Origin

Pulse question	Applied to Origin
Entities required	Ideally none beyond the possibility of operative distinction; provisionally represented by Ω .
Ontological level	Minimal pre-geometric reference condition.
Lower-order dependencies	None physical. The concept depends only on the possibility of resolving or failing to resolve difference.
New emergent property	None yet. Origin establishes a starting horizon, not a dynamical result.
Claim type	Interpretive and definitional, with a minimal formal notation for resolution.

Pulse question	Applied to Origin
New primitive required	Provisionally Ω . Stronger if reducible to the statement that no operative distinction is yet available.
Can fewer assumptions do the work?	Possibly. Eliminating entity-like language for Ω remains an explicit open route.
Observational constraint	Indirect. Downstream derivations must succeed without importing undeclared structure; failure constrains the starting proposal.

The Pulse gives Origin a deliberately modest result. We have not derived existence. We have not explained why there is something rather than nothing. We have not identified a physical first moment.

We have established a candidate starting horizon whose commitments are thin enough for the rest of the volume to be audited against them.

1.15 What Origin Has Not Earned

A physical first moment or temporal beginning.

A spatial location, metric, coordinate system, topology, or geometry.

Matter, fields, energy, action, entropy, or thermodynamic dynamics.

Objects, observers, agents, consciousness, or meaning as primitives.

Causation or a physical law of evolution.

Information in the stronger retained and consequential sense used in Boundary.

A mechanism explaining why the first distinction occurs.

A proof that Ω is an entity rather than a definitional role.

A claim that Ω contains hidden structure.

A claim that Ω is absolutely featureless.

A proof that relational ontology is physically instantiated.

Physical spacetime. Book I ends at earned Time; physically instantiated spacetime is Book II's frontier.

The refusal to claim these results is part of the method. Origin succeeds only if it leaves the framework poorer than ordinary intuition and makes the next constructive burden unmistakable.

1.16 Turning Toward Difference

We began with you asking what you were doing here.

At first the question seemed to point outward, toward the universe.

Instead we followed its assumptions inward.

The familiar world thinned. Location gave way to the requirement for distinguishable positions. Objecthood gave way to boundary and persistence. Persistence gave way to retained difference. Retained difference gave way to difference itself.

At the limit, even difference was withheld.

We did not discover a primordial landscape underneath experience. We reached the point at which the framework had no further structure it was entitled to name.

We call that limit Ω .

Now the direction changes.

The next chapter does not ask what else can be removed. It asks what the smallest constructive addition must be.

What is the minimum relational scaffold required for one condition to become distinguishable from another?

That is the first step of the ascent.

If it succeeds, difference becomes available.

If difference can persist, information becomes possible.

If retained relations constrain one another, organization becomes possible.

If organization can close, higher-order identity becomes possible.

And only much later, after scale, distance, and ordered measure have been earned, may geometry become available as more than an intuition we started with.

We began inside a world already given form.

We have now removed our right to assume that form.

Difference begins the attempt to earn it back.

1.17 Precursors and Departures

The possibility that an origin may remain unresolved without being equivalent to either absolute nothing or perfect uniformity has historical precedents.

Precursors. Anaximander's *apeiron* was described as a boundless or indefinite source from which differentiated opposites emerge. The important precursor here is not the claim that Ω is an *apeiron*, but the older idea that determinacy need not be fully present at the beginning.

Charles Sanders Peirce later developed an evolutionary cosmology in which determinacy and law are not simply treated as eternally fixed features of reality. His writings on chance, continuity, and habit explore the possibility that regularity itself can emerge from a more indeterminate condition.

These two traditions approach the problem from very different directions, but together they bracket a question Origin deliberately leaves open: whether the absence of resolved distinction reflects genuine uniformity, or whether variation may exist below the level at which anything has yet become stably distinguishable.

Departure. The framework makes a thinner claim than either precursor. Ω is not asserted to be an indefinite substance, a reservoir of latent opposites, a field of chance, or a productive cause. Nor is it assigned any tendency to generate order. Origin assumes no physical time in which a process of differentiation, habit formation, or cosmogenesis could unfold.

Ω is only the minimally resolved reference condition from which no operative distinction is available within the framework's initial resolving frame.

The framework therefore leaves both possibilities open:

- no lower-order variation exists
- lower-order variation exists but remains unresolved

Neither possibility is currently earned.

What matters at Origin is not what Ω secretly contains, but what the framework is entitled to resolve from it. Later chapters must earn persistence, organization, closure, orientation, return, and the regularities that make stable structure possible rather than placing them into the starting condition.

In that sense, Anaximander and Peirce are precursors to the question, not premises of the answer.

Questions Opened by This Framework

Is Ω unresolved because no lower-order variation exists, or because variation exists below the framework's initial resolving capacity?

Can Ω ultimately be eliminated as an entity-like term and replaced entirely by the condition that no operative distinction is resolved?

Does the conceptual descent identify genuine ontological dependencies, or only the order in which human cognition finds them easiest to remove?

Is distinction genuinely primitive, or can a still weaker relation generate it?

Why does differentiation become operative at all?

Can later origin roles be earned from closure and higher-order addressability without copying Ω forward as a privileged anchor?

Can relation be specified without importing ordering, metric, locality, topology, or geometry?

Can an origin role be re-instantiated at higher organizational levels without smuggling in a hierarchy as a primitive?

What would falsify the claim that the later geometric structure has been earned rather than encoded in the starting relations?

Where does derivational necessity end and contingent structural selection begin?

If Volume I reaches geometry, what additional structures are required before that geometry deserves a physical spacetime interpretation?

Selected References Cited in Origin

Anaximander of Miletus (c. 550 BCE). Fragment DK 12 B1, preserved by Simplicius, numbered as in Diels and Kranz, *Die Fragmente der Vorsokratiker*; texts and translation in Kirk, G. S., Raven, J. E., & Schofield, M. (1983). *The Presocratic Philosophers: A Critical History with a Selection of Texts* (2nd ed.). Cambridge: Cambridge University Press. For the boundless or indefinite source from which opposites are separated.

Bateson, G. (1972). *Steps to an Ecology of Mind: Collected Essays in Anthropology, Psychiatry, Evolution, and Epistemology*. San Francisco: Chandler Publishing. Widely reprinted, most accessibly by University of Chicago Press (2000) with a foreword by Mary Catherine Bateson; pagination differs across printings. For information as a difference that makes a difference, cited here for the family of intuitions rather than for the later formal account.

Leibniz, G. W. (1714). *Principles of Nature and Grace, Based on Reason*, §7. Written in French for Prince Eugene of Savoy; English translation by Jonathan Bennett freely available at earlymoderntexts.com. For the question why there is something rather than nothing.

von Neumann, J. (1923). Zur Einführung der transfiniten Zahlen. *Acta Litterarum ac Scientiarum Regiae Universitatis Hungaricae Francisco-Josephinae, Sectio Scientiarum Mathematicarum* (Szeged), 1, 199–208. For the construction of the natural numbers from the empty set, used here only as a logical analogy.

Parmenides of Elea (c. 475 BCE). *On Nature*, fragments B2 and B6, numbered as in Diels and Kranz, *Die Fragmente der Vorsokratiker*. Burnet's English translation of the fragments is in the public domain, in *Early Greek Philosophy* (A. & C. Black, 1908; Project Gutenberg ebook 67097), and is also available arranged by Diels-Kranz number at lexundria.com. For the maxim that nothing comes from nothing.

Peirce, C. S. (1891). The architecture of theories. *The Monist*, 1(2), 161–176. And (1892). The doctrine of necessity examined. *The Monist*, 2(3), 321–337. Both reprinted in *The Essential Peirce*, vol. 1 (Indiana University Press, 1992). For an evolutionary cosmology in which law and regularity emerge from chance and habit.

Spencer-Brown, G. (1969). *Laws of Form*. London: George Allen & Unwin. Reissued by Julian Press (New York, 1972) and in several later editions with added prefaces; the pagination differs between them. For the instruction to draw a distinction as the minimal generative act.

Note on these references. None of these works supports the ontology proposed here; they mark the problem the chapter inherits. Bibliographic details were verified against primary or authoritative sources on 25 and 28 September 2026.

Chapter 2

Difference: The First Non-Equivalence

Claim ~ Difference is the minimum dyadic structure of relational non-equivalence. Its two poles are co-constituted within that structure and stand symmetrically, each only as the other's counterpart. Difference is therefore the first constructive commitment beyond Origin.

Chapter discipline. This chapter adds only the least structure needed for non-identity to become available after Origin. The chapter describes what Difference minimally is; Chapter 3 will ask what additional commitment lets that Difference become operative.

This chapter therefore separates four ideas that are easily compressed into one:

■ Difference $\neq$ Distinction $\neq$ Retained distinction $\neq$ Information

2.1 Where Origin Leaves Us

Origin supplies the least-resolved reference condition the framework can name without treating that condition as a place, moment, substance, or cause. Its formal statement is a claim about the initial resolution available to the framework, not about an absolute metaphysical void.

■ $\text{Res}_{w_0}(\Omega) = \emptyset$

Nothing in that expression says that reality is absolutely featureless. It says only that no operative distinction is available at the initial declared resolution. The next step must therefore be constructive without pretending that a physical event has occurred. Time has not been earned, so “next” means derivationally next.

Foundational question. What is the minimum structure required for non-equivalence to be available without already presupposing objects, properties, measurement, orientation, or succession?

2.2 Why Difference Must Precede Distinction

To distinguish is already to do more than state that two terms are non-equivalent. Distinction implies that the non-equivalence can enter an operative contrast, a test, an update, or some other internally consequential structure. If the framework begins with Distinction as the primitive, it risks hiding that extra burden inside the verb “distinguish.”

This order refuses that compression. Difference names the austere structural fact of non-equivalence. Distinction, reserved for Chapter 3, will require an additional commitment that makes the non-equivalence usable in succession.

■ non-equivalence $\rightsquigarrow$ admissible succession $\rightsquigarrow$ retention $\rightsquigarrow$ consequence

The squiggle arrow $\rightsquigarrow$ is derivational only (A.2).

2.3 Proposition 2A: Primitive Difference

Proposition 2A - primitive difference. The least constructive structure beyond the unresolved Origin is a symmetric dyad whose two poles are numerically two as a primitive cost and are related by a symmetric, irreflexive relation of non-equivalence. Difference and its poles are co-constitutive: neither independently constituted relata nor a relation existing prior to all relata is asserted.

■ $\mathfrak{D} = \langle a, b ; \emptyset \rangle$

Here $\mathfrak{D}$ names the whole primitive dyad. The symbols a and b are metalanguage labels used so the structure can be discussed. They do not yet name objects with intrinsic properties or states carrying histories.

■ $a \emptyset b \iff b \emptyset a$

■ $\neg(a \emptyset a)$ and $\neg(b \emptyset b)$

Symmetry preserves exchange equivalence. Irreflexivity prevents the non-equivalence relation from applying to a pole with itself. Neither condition introduces a metric or a magnitude of difference.

■ The proposition states its primitive cost rather than deriving multiplicity from weak discernibility.

Why any dyadic Difference exists at all remains outside what this chapter can derive.

2.4 Dyadicity Is a Primitive Cost

The framework cannot honestly claim to derive numerical two-ness from the irreflexive relation. The two-pole character is already part of Proposition 2A. This is not a defect if the project states the cost explicitly; it would be a defect only if the text pretended that $\emptyset$ somehow manufactured multiplicity from a prior numerical one.

The primitive cost is therefore not “two fully formed things.” It is weaker: a minimal dyadic structure whose poles are jointly admitted and whose only declared internal fact is their non-equivalence.

This distinction matters because a foundational ontology is not improved by hiding cardinal commitments in relational notation. The project’s parsimony test counts the dyad as a commitment and later asks whether anything weaker can do the same explanatory work.

2.5 Co-Constitution Rather Than Priority

Two familiar metaphysical pictures are deliberately avoided. The first says that two independently constituted entities exist first and then acquire a relation. The second says that a free-standing relation exists first and somehow generates its relata. Both impose an order that Proposition 2A does not need.

The weaker claim is co-constitution: the dyadic whole, its poles, and their non-self relation are introduced together as one minimal structure. The framework therefore does not answer the general metaphysical question of whether relations or relata are absolutely prior. It chooses only the least structure needed for this derivation.




Figure 2.1. Neither the difference nor its poles comes first. A difference with nothing to differ is empty, and two things that exist before their difference would make difference a later addition. The dyad is one structured fact, like a stick and its two ends: break the stick and you get two sticks with two ends each, never a lone end. The image of a stick that cannot have only one end is an old one.

2.6 Weak Discernibility Is Diagnostic, Not Generative

The literature on weak discernibility is useful here only if its role is kept narrow. A symmetric irreflexive relation can make two already-admitted poles relationally discernible without assigning either one a distinct intrinsic qualitative property. That is exactly the modest job needed here.

It does not generate numerical diversity. Hawley's objection (Hawley, 2006) and the circularity concerns discussed by Ladyman, Linnebo and Pettigrew (2012) therefore land if weak discernibility is asked to explain why there are two poles. This framework does not ask it to do so. Numerical dyadicity has already been paid for in Proposition 2A.

Muller's discussion (2015) of "relationals" provides a useful comparison class: entities may be structurally discernible through relations rather than intrinsic qualitative features. The comparison supports conceptual possibility, not the truth of this ontology.




Figure 2.2. Three ways two things can be told apart. A property can differ, as with coins of different dates; a relation can hold one way only, as when one coin rests on the other; or a relation can hold only both ways, as between two identical coins, which swapping leaves exactly as they were. The primitive dyad is discernible only in this last, weakest sense.


2.7 Exchange Symmetry Is Descriptive

At the Difference level, exchanging the external labels a and b leaves the dyad unchanged. The swap is therefore an automorphism of the described structure.

■ $\sigma(a) = b, \sigma(b) = a, \sigma(\mathbb{D}) = \mathbb{D}$

This statement belongs to the theorist's description. It says that the primitive structure has no fact corresponding to "which pole is really a." It does not yet say that the modeled structure can perform, instantiate, or propagate the exchange. That difference will become the entire burden of Chapter 3.

primitive difference: symmetric, irreflexive non-equivalence



exchanging the labels a and b leaves the dyad unchanged
no update, direction, metric or reference pole

Figure 2.3. Primitive Difference is symmetric non-equivalence. Exchanging the metalanguage labels leaves the dyad unchanged. The figure deliberately contains no update arrow, privileged pole, metric, or temporal order.

2.8 Difference Is Not Yet a Configuration Space

The labels a and b should not yet be read as fully typed configurations. Doing so would silently introduce a state space and make transitions among its members look available before any transition relation has been admitted. Chapter 2 therefore stops one step earlier.

The poles are positions in the primitive dyadic structure. Chapter 3 will make an explicit type promotion by collecting them into the minimal configuration carrier $\mathcal{C}_2 = \{a, b\}$. That promotion is not free: it is part of what becomes necessary once admissible succession enters the framework.

2.9 Difference Is Not Change, Magnitude, or an Event

Difference is not written as Δ because Δ is reserved elsewhere in the manuscript for change in a quantity or structure. Nor is the relation written as a non-zero magnitude. Expressions such as $\Delta(a, b) \neq 0$ would smuggle in both a measure and a distinguished zero before either has been earned.

Likewise, Difference is not an event. No pole "appears after" the other. No object splits. No duration elapses. Proposition 2A states a logical-structural commitment, not a cosmological episode occurring inside already existing time.

2.10 Difference Is Not Yet Distinction

The chapter's most important stopping point is negative. A structure can be non-equivalent without containing any internally admissible operation that makes use of that non-equivalence. The theorist can describe $a \not\sim b$ and can notice the swap symmetry, but the dyad itself has not yet been given a rule of succession.

Accordingly, this chapter introduces no resolving condition F . Asking resolution to do that work here would blur the joint with Distinction.

Difference = non-equivalence; Distinction = non-equivalence made operative

2.11 Minimal Contrast Is Not Yet Relational Organization

The primitive dyad is relational in the minimal sense that its poles are characterized together. It is not yet what the later Relation chapter means by relational organization.

This distinction prevents a vocabulary trap. "Relation" in ordinary metaphysics can name any connection between terms; "Relation" as a later chapter title names the emergence of mutually constraining organization among multiple retained relations.

2.12 Could Difference Be Reduced Further?

One speculative possibility is that the dyad might eventually be reconstructed from recursive self-differentiation of a more primitive condition. That possibility is retained as a reduction hypothesis, not as part of the present derivation. The current architecture does not depend on its success.

A successful reduction would have to do more than rename the dyad. It would have to show how numerical two-ness and non-self relation arise without inserting them in equivalent form. Until such a construction exists, Proposition 2A should remain explicit about its primitive cost.

2.13 What Difference Earns

A minimal dyadic carrier $\mathfrak{D}$ with two jointly admitted poles.

Symmetric, irreflexive non-equivalence $\not\sim$.

Weak relational discernibility without intrinsic qualitative asymmetry.

Exchange symmetry under relabeling in the theory's metalanguage.

A clean separation between numerical dyadicity and later operational Distinction.

2.14 What Difference Does Not Earn

No update relation, succession, transformation history, or admissible operation.

No reference pole, anchor, source, target, orientation, or direction.

No magnitude, metric, probability, information measure, or spatial separation.

No persistence, retained distinction, boundary, information, or memory.

No claim that a and b are physical objects, events, or configurations in time.

2.15 Objections and Replies

Objection 1: The chapter simply assumes two things. **Reply:** It assumes primitive dyadicity, and it says so. The claim is not that two fully individuated substances are primitive, but that the least constructive structure currently available contains two co-constituted poles. If a genuinely weaker construction later reproduces that work, Proposition 2A should be reduced.

— — — —

Objection 2: The relation $\emptyset$ already presupposes its relata. **Reply:** The chapter does not claim metaphysical priority of relation over relata. It introduces the dyadic whole, poles, and relation together. Co-constitution avoids both an object-first and a relation-first sequence.

— — — —

Objection 3: Weak discernibility is too weak. **Reply:** Agreed if it is asked to generate numerical multiplicity. It is used only to characterize how little qualitative individuation is required once dyadicity has been admitted.

— — — —

Objection 4: Exchange symmetry already gives an operation. **Reply:** No. An automorphism visible in a representation is not yet an operation admitted by the modeled structure. Treating those as equivalent would collapse Chapter 3 into vocabulary.

— — — —

Objection 5: Why should Difference exist at all? **Reply:** This chapter does not answer that ultimate question. It identifies the minimum constructive commitment from which the remainder of the program will attempt to proceed.

Objection 6: If Origin has no resolvable distinction, how can Difference follow it?

Reply: The order is derivational, not temporal. Origin states the least-resolved starting condition; Difference is the first additional structure the framework admits. No physical production event is implied.

2.16 What Would Count Against the Claim

A coherent weaker structure that performs every downstream role currently assigned to primitive dyadic Difference without presupposing an equivalent two-pole commitment.

A proof that symmetric irreflexive non-equivalence necessarily imports orientation, metric, or independently individuated objects.

A downstream derivation that repeatedly requires hidden intrinsic properties of a and b, showing that the claimed austerity of Proposition 2A was illusory.

Failure to formulate Distinction without simply renaming the descriptive automorphism already available here.

2.17 Ontological Defensibility Pulse: Difference

Pulse question	Applied to Difference
1. Entities required	One primitive dyadic structure $\mathfrak{D}$ with two co-constituted poles and relation $\emptyset$.
2. Ontological level	Pre-operational structural level; no state dynamics or physical realization is claimed.
3. Lower-order dependencies	Only the minimally resolved Origin as derivational background.
4. New emergent properties	None. Causation and even succession are unavailable.
5. Claim types	Structural and relational, not yet dynamical or metaphysical closure.
6. New primitives	Numerical dyadicity plus symmetric irreflexive non-equivalence.
7. Fewer assumptions?	Open. Any proposed reduction must derive rather than rename dyadicity.
8. Observational constraints	Primarily downstream coherence and parsimony at this stage; physical realization remains unearned.

2.18 Implications and Handoff

Difference has earned the first non-equivalence but has earned no activity. The dyad can be described, but it cannot yet succeed itself, preserve itself, branch, or constrain a later configuration. That stopping point is intentional.

The next chapter therefore asks a sharper question than the older “what resolves the pair?” formulation: what additional commitment makes the primitive non-equivalence enter the structure’s own admissible succession without privileging either pole?

■ $\mathcal{D} \rightsquigarrow$ admissible transformation $\rightsquigarrow$ reciprocal Distinction

Handoff to Distinction. If Difference is static non-equivalence, what is the weakest non-circular transformation structure under which that non-equivalence becomes operational while preserving exchange symmetry?

2.19 Precursors and Departures

The ingredients of this book are not new. Non-equivalence, transition relations, automorphisms, retention tests and information-theoretic comparisons are established ideas, and later chapters do not repeat the point. What the book proposes is architectural: placing them in one inheritance-tracked derivation, making each assumption cost explicit, and refusing later structure until earlier chapters have earned it.

Precursors. Spencer-Brown’s *Laws of Form* (1969) and Isaacson and Kauffman’s recursive distinctioning (2016) are close neighbors for the idea that distinctions, and recursive operations on them, can generate structured patterns. “Weakly discernible” is used only in its established philosophical sense: items discerned by an irreflexive symmetric relation without differing in intrinsic properties, as discussed by Saunders, Hawley, Ladyman, Linnebo and Pettigrew, and Muller.

What is new here. The chapter isolates symmetric dyadic non-equivalence as the least constructive stage in the sequence, withholds operative transformation from it, and records dyadicity as a primitive cost rather than pretending that weak discernibility generates multiplicity. The claim under test is whether this ordering can support the later derivation without importing succession, orientation, information, geometry or objects too early.

Questions Opened by This Framework

Can primitive dyadicity be reduced to a weaker recursive structure without importing numerical multiplicity in disguise?

Is symmetric irreflexive non-equivalence the weakest relation sufficient for the later architecture?

Can a physical theory ever distinguish co-constituted poles without eventually introducing intrinsic qualitative properties?

What is the exact boundary between a symmetry visible in a model and an operation available to the modeled system?

Does any candidate pre-spacetime physics supply evidence for dyadic non-equivalence at its foundation, or is the present proposal purely reconstructive?

Selected References Cited in Difference

Hawley, K. (2006). Weak discernibility. *Analysis*, 66(4), 300–303. For the objection that weak discernibility does not by itself secure numerical diversity (Objection 3).

Isaacson, J. D., & Kauffman, L. H. (2016). Recursive distinctioning. Preprint arXiv:1606.06965.

Ladyman, J., Linnebo, Ø., & Pettigrew, R. (2012). Identity and discernibility in philosophy and logic. *The Review of Symbolic Logic*, 5(1), 162–186. For the formal grades of discernibility and the circularity objection (Objection 2).

Muller, F. A. (2015). The rise of relationals. *Mind*, 124, 201–237. Relationals: objects discernible by relations rather than intrinsic properties, used as a comparison class.

Saunders, S. (2003). Physics and Leibniz's principles. In K. Brading & E. Castellani (eds.), *Symmetries in Physics: Philosophical Reflections*, chapter 16. Cambridge: Cambridge University Press. For weak discernibility by an irreflexive symmetric relation, used as a comparison class rather than a derivation of numerical diversity.

Spencer-Brown, G. (1969). *Laws of Form*. London: George Allen & Unwin.

Note on these references. These works are comparison classes, not evidence that the ontology proposed here is correct. Bibliographic details were verified against primary or authoritative sources on 26 September 2026.

Chapter 3

Distinction: When Difference Enters Succession

Claim ~ Difference becomes an operative Distinction when a second foundational commitment is introduced: an admissible transition relation $\mathcal{U}$ on the minimal configuration carrier. If $\mathcal{U}$ is nontrivial and covariant under the symmetries of the primitive dyad, it induces reciprocal exchange. Distinction is therefore the point at which non-equivalence first becomes usable in the structure's own succession.

Chapter discipline. This chapter pays openly for admissible transformation, the second foundational commitment. The order supplied by $\mathcal{U}$ is an order of admissible succession; whether it later becomes temporal is a question for Time.

The framework therefore has two foundational commitments so far, not necessarily two forever:

primitive Difference + admissible transformation

Boundary will test whether a third ontological commitment is required for retention or whether retention can be defined with diagnostic structure in the metalanguage alone.

3.1 Where Difference Leaves Us

Chapter 2 leaves the primitive dyad $\mathfrak{D} = \langle a, b; \emptyset \rangle$. Its poles are non-equivalent but exchange-symmetric. The theory can describe the swap $a \leftrightarrow b$, yet nothing in Difference says that one pole may succeed the other. The structure is static in precisely that limited sense.

Foundational question. What is the weakest non-circular additional structure under which primitive non-equivalence becomes internally operative rather than merely analyst-visible?

3.2 A Second Commitment Is Unavoidable Unless Derived

A static relation does not by itself generate succession. If the book wants later chapters to speak of updates, histories, retention, branching, closure, or return, something must constrain what configurations may follow what. It is easy to use $\mathcal{U}$ without recognizing it as a foundational cost. This chapter makes that cost explicit.

The commitment is not that physical time already flows. It is only that there exists an admissibility relation over configurations. Removing that relation leaves Difference intact but eliminates every downstream concept that depends on transformation.

- The framework should count $\mathcal{U}$ as a primitive commitment unless an earlier or deeper construction later derives it.

Whether Difference and admissible transformation can ultimately be reduced to a single weaker principle remains a research question.

3.3 Type Promotion: From Poles to Minimal Configurations

Introducing $\mathcal{U}$ changes the type of the objects it relates. Chapter 2 deliberately did not treat a and b as configurations. Chapter 3 now collects them into the least carrier on which a transition relation can be defined:

- $\mathcal{C}_2 = \{a, b\}$

The move is explicit. The primitive poles now function as the minimal configurations available to the emerging update structure. This is not a claim that they are physical states in spacetime; it is a formal role required by succession.

The update relation is typed as:

- $\mathcal{U} \subseteq \mathcal{C}_2 \times \mathcal{C}_2$

This keeps the later Formalism chapter's ontology honest from the start: $\mathcal{U}$ is fundamentally a relation on configurations. Functional notation becomes available only where the relation happens to assign a unique successor.

3.4 Admissibility Must Not Be Defined Through Distinction

The word “admissible” is the chapter's most dangerous word. If a transition is called admissible because some resolver can already distinguish it, Distinction has been presupposed in the definition that is supposed to earn it. The chapter therefore refuses any definition of $\mathcal{U}$ in terms of Res_F , observation, measurement, or represented difference.

At this level, admissibility is a primitive structural constraint on succession. Its content is restricted by what Difference already supplies, and no hidden label may determine which transition is allowed.

3.5 Symmetry Covariance: No Hidden Labels

Let $\text{Aut}(\mathfrak{D})$ denote the automorphisms of the primitive dyad. At the two-pole minimum, the nontrivial automorphism exchanges a and b. Primitive admissibility must respect that symmetry:

$$\blacksquare (x, y) \in \mathcal{U} \iff (\sigma x, \sigma y) \in \mathcal{U} \text{ for every } \sigma \in \text{Aut}(\mathfrak{D})$$

This is the precise form of the “no analyst-imposed labels” rule. An admissibility fact cannot depend on which pole the theorist happens to call a. If the structure licenses a nontrivial transition from one pole to the other, symmetry covariance licenses its exchanged counterpart as well.

Nontriviality requires at least one transition between non-identical configurations:

$$\blacksquare \exists x, y \in \mathcal{C}_{\mathfrak{D}} : x \neq y \text{ and } (x, y) \in \mathcal{U}$$

For the symmetric dyad, one such transition plus covariance forces reciprocity.

3.6 Proposition 3A: Reciprocal Distinction

Proposition 3A - reciprocal distinction. A primitive Difference becomes an operative Distinction when the dyad’s poles are promoted to a minimal configuration carrier and a nontrivial admissible transition relation $\mathcal{U}$, invariant under $\text{Aut}(\mathfrak{D})$, licenses succession between them. At the two-pole minimum, covariance forces reciprocal exchange without privileging either pole.

In plain terms: once one pole may be followed by the other at all, and no rule may favor either pole, each must be able to follow the other.

$$\blacksquare \mathcal{U}_{\min} = \{(a, b), (b, a)\}$$

The relation is deterministic at this minimum: each configuration has one admissible successor. It contains no primitive self-transition. Reciprocity is therefore a consequence of nontriviality plus symmetry, not an independently stipulated operation.




Figure 3.1. The same pairs, two different claims. A register of differences and a timetable can list the very same ordered pairs, but only the timetable says what may follow what, so only it lets a journey be strung together. A timetable that may not favor either town must also pair every service with its return: one non-trivial transition, plus symmetry, forces reciprocal exchange. $\emptyset$ constrains what differs; $\mathcal{U}$ constrains what may follow.

3.7 Why $\emptyset$ and $\mathcal{U}$ Are Not the Same Thing

A referee can immediately notice that, extensionally, $\emptyset$ and $\mathcal{U}_{\min}$ may contain the same ordered pairs. In the minimal two-pole case both can be represented by $\{(a,b),(b,a)\}$. If the chapter relies on extension alone, it has renamed Difference rather than derived Distinction.

The distinction is instead one of type and inferential role:

■ $\emptyset$ constrains what differs; $\mathcal{U}$ constrains what may follow

From $\emptyset$ alone, nothing follows about successors, composition, branching, determinism, or histories. From $\mathcal{U}$, those questions become well-typed. Two relations can therefore share an extension while making different assertions because they occupy different formal roles in the structure.

This claim is load-bearing. If no downstream formal consequence distinguishes the role of $\mathcal{U}$ from the role of $\emptyset$, Chapter 3 collapses back into Chapter 2.

3.8 The Reciprocal Map Is Derived

Because $\mathcal{U}_{\min}$ assigns each configuration a unique successor, the relation can be represented by a map induced from $\mathcal{U}$. Write that map as $J_{\mathcal{U}}$:

$$\blacksquare J_{\mathcal{U}}(a) = b$$

$$\blacksquare J_{\mathcal{U}}(b) = a$$

The notation $J_{\mathcal{U}}$ is secondary. The ontological commitment is $\mathcal{U}$; $J_{\mathcal{U}}$ is the functional representation available because the minimal relation happens to be single-valued and total on $\mathcal{C}_{\mathfrak{D}}$.

The order matters. The chapter does not admit a swap operation J and then ask whether it is internal. We admit a symmetry-respecting update relation and derive the reciprocal map from it.

3.9 Identity Comes From Composition, Not Primitive Stasis


Applying the derived reciprocal map twice returns the same configuration:

$$\blacksquare J_{\mathcal{U}}^2 = \text{id}$$

The identity map id is therefore generated by composition. It is not a primitive self-loop in $\mathcal{U}_{\min}$. The update relation itself contains neither (a,a) nor (b,b) . This matters because adding those pairs would introduce optional stasis and branching at the minimum without any derivational need.

The algebra generated by $J_{\mathcal{U}}$ contains $\{\text{id}, J_{\mathcal{U}}\}$, but that closure is derived bookkeeping over compositions of the primitive update.

Identity from composition: a switch that can only toggle



The set $\{\text{id}, J\}$ is bookkeeping about compositions of the one update, not a second rule added alongside it.

Figure 3.2. Identity from composition. A switch with a single control, flip, returns to where it started after two flips, though it has no “stay” setting. The minimal update likewise contains exchange and nothing else; identity arises from composing it twice. Adding a “stay” transition would give every state two possible futures, which the derivation does not need.

3.10 Formal Recurrence Is Not Return and Not a Clock

The expression $J_{\mathcal{U}}^2 = \text{id}$ can look like an oscillator, and mathematically it is a two-step recurrence. Two warnings are therefore necessary.

First, exact state repetition is not the later Return predicate. Return concerns a higher-order identity that departs from and re-enters an independently specified identity class. Here the same minimal configuration is recovered by composing a reciprocal update twice.

Second, the exponent 2 counts formal composition in the analyst’s notation. It does not yet supply physical duration or a calibrated period. Formal recurrence is weaker than clockhood.

■ formal recurrence $\neq$ higher-order Return $\neq$ physical clock

3.11 Succession Is Not Yet Time or Orientation

Each ordered pair in $\mathcal{U}$ says that one configuration may be followed by another. This is genuine step order, and the book should not hide it. What it does not supply is a physical temporal interval or a globally oriented relation.

The relation as a whole remains exchange-symmetric: whenever (a,b) is admissible, (b,a) is admissible. Orientation later requires persistent non-equivalence between relational roles under exchange. That condition is absent here.

Likewise, an index used to display repeated application of $\mathcal{U}$ records derivational or compositional order only. Time must still earn when such ordered dependence deserves a physical temporal interpretation.

3.12 Distinction Without an Observer or Resolver

The construction needs no generic resolving frame F to make Difference operative. Distinction is grounded in admissible succession rather than in observation. A conscious observer, sensor, or representational frame can later exploit distinctions, but none is constitutive here.

Resolution language returns only when there is a concrete criterion or frame whose discriminatory capacity is actually at issue.

3.13 Distinction Is Not Yet Retention

A distinction may be operative in succession and still fail to survive a transformation of the larger structure that supports it. Under $\mathcal{U}_{\min}$, reciprocal exchange preserves the dyad by construction; testing only $J_{\mathcal{U}}$ would therefore make retention trivial.

Boundary must ask a stronger question: what happens when the update structure is perturbed, embedded, projected, or otherwise compared across a declared transformation family? That problem is deliberately deferred.

3.14 Distinction Is Not Yet Information

Information requires more than an admissible difference. At minimum, some distinction must remain available so that later structural possibilities depend on it. Chapter 3 supplies an operative contrast but has not yet shown that the contrast survives any nontrivial transformation of the structure itself.

The sequence therefore remains:

■ Difference $\rightsquigarrow$ Distinction $\rightsquigarrow$ retained distinction $\rightsquigarrow$ information

3.15 What Distinction Earns

The minimal configuration carrier $\mathcal{C}_{\mathfrak{D}} = \{a, b\}$.

A second foundational commitment so far: admissible transition relation $\mathcal{U}$.

Nontrivial succession constrained by covariance under $\text{Aut}(\mathfrak{D})$.

Derived reciprocal map $J_{\mathcal{U}}$ and derived identity under composition.

A formal distinction between static non-equivalence and operational succession.

3.16 What Distinction Does Not Earn

No physical time, duration, causal order, or propagation speed.

No orientation, source/target privilege, reference pole, anchor, or Ω designation.

No primitive stasis, branching, probability, metric, or information quantity.

No retained distinction, boundary, memory, or higher-order identity.

No explanation yet of why admissible transformation exists at all.

3.17 Objections and Replies

Objection 1: $\mathcal{U}$ is simply another primitive. **Reply:** Yes, unless it is later derived. The chapter counts it openly because a static Difference cannot by itself license succession. “Fewest possible assumptions” requires minimizing commitments, not pretending that an indispensable commitment was derived when it was not.

— — — —

Objection 2: $\mathcal{U}_{\min}$ and $\emptyset$ have the same extension. **Reply:** At the minimal dyad they can. Their type and inferential roles differ: one states non-equivalence; the other licenses successor structure. The chapter fails if that difference never matters downstream.

— — — —

Objection 3: Ordered pairs already introduce orientation. **Reply:** An ordered pair represents a succession relation locally, but the full update relation is invariant under exchanging the poles. Orientation requires a persistent asymmetry between exchangeable roles, which is absent.

— — — —

Objection 4: Why is (a,b) admissible in the first place? **Reply:** Nontrivial admissibility is primitive here. Symmetry determines its reciprocal partner once one nontrivial transition is admitted, but the existence of transformation itself remains an explicit unexplained commitment.

— — — —

Objection 5: A two-state oscillator is already a clock. **Reply:** It exhibits formal recurrence, and an analyst can count compositions, but Time requires four criteria for clockhood: recurrence, countability, stability, and couplability. Here recurrence is formal; the composition count is still analyst bookkeeping rather than an earned physical measure; stability under perturbation has not yet been shown; and no coupling to an independent recurrent process exists. $J_{\mathcal{U}}^2 = \text{id}$ is therefore recurrence without yet being a physical clock.

— — — —

Objection 6: Excluding self-loops is arbitrary. **Reply:** The exclusion follows the minimality rule. Primitive self-loops add stasis and, when combined with cross-transitions, branching. Neither is required to make Difference operative. They may be admitted later if a downstream construction needs them.

— — — —

Objection 7: $J_{\mathcal{U}}$ is still an analyst's function. **Reply:** Correct as notation. What grounds it is not the analyst's ability to write a swap but the antecedent internal transition relation $\mathcal{U}$. $J_{\mathcal{U}}$ is only the functional representation of a relation already admitted in the model.

3.18 What Would Count Against the Claim

A demonstration that $\mathcal{U}$ cannot be specified without already using the Distinction it is supposed to ground.

A demonstration that the role difference between $\emptyset$ and $\mathcal{U}$ has no formal consequence in any downstream construction.

A weaker structure than admissible transition that makes Difference operative without equivalent dynamical commitment.

A proof that symmetry covariance plus nontriviality cannot yield the claimed reciprocal minimum without importing hidden labels or orientation.

A later requirement for primitive stasis at this level showing that $\mathcal{U}_{\min}$ was too restrictive.

3.19 Research Frontier

Open module	Question to be earned
Origin of $\mathcal{U}$	Can admissible transformation itself be derived from a still weaker structural principle?
Admissibility semantics	What physical or mathematical fact eventually distinguishes actually admissible transitions from merely conceivable ones?
Generalization	How should $\mathcal{U}$ be extended when more than two configurations become available without presupposing Relation?
Branching	When does more than one admissible successor become necessary, and what new commitment does branching represent?
Temporal interpretation	Under what conditions does compositional succession become physical temporal order?
Operational realization	What candidate physical substrate could instantiate $\mathcal{U}$ without assuming spacetime in advance?

3.20 Ontological Defensibility Pulse: Distinction

Pulse question	Applied to Distinction
1. Entities required	Primitive dyad plus minimal configuration carrier and admissible transition relation $\mathcal{U}$.
2. Ontological level	Pre-temporal dynamical/operational level.
3. Lower-order dependencies	Difference supplies only dyadic non-equivalence and its automorphisms.
4. New emergent properties	None yet. $\mathcal{U}$ gives succession, not causation.
5. Claim types	Functional/structural: what transitions are admissible.
6. New primitives	Admissible transformation, counted explicitly as the second foundational commitment so far.
7. Fewer assumptions?	Open. A reduction of $\mathcal{U}$ would strengthen the theory; hiding it would weaken it.
8. Observational constraints	Non-circular typing, symmetry covariance, downstream usefulness, and eventual physical realization.

3.21 Implications and Handoff

Distinction has transformed the project's foundation in a precise sense. Difference could only be described. Distinction can now participate in admissible succession. Yet nothing has persisted except what is guaranteed by the minimal reciprocal update itself.

The next chapter therefore must not test retention merely by applying $J_{\mathcal{U}}$ again. That would return the result built into Proposition 3A. Boundary instead asks whether the distinction survives transformations of the structure that are not themselves the primitive internal update.

Handoff to Boundary. Given an operative reciprocal distinction, what does it mean for that distinction to survive perturbation, embedding, projection, or collapse without adding a hidden third primitive to the ontology?

3.22 Precursors and Departures

Precursors. Relations on configuration sets, successor relations, composition, identity maps, automorphisms and covariance are standard mathematical machinery. Recursive and rewriting approaches, including Isaacson and Kauffman (2016) and the broader Wolfram-model family (Wolfram, 2020), show that simple update rules can generate rich higher-order structure.

What is new here. The chapter separates primitive non-equivalence from admissible transformation by type and role: one states static non-equivalence, the other constrains succession. It makes admissible transformation an explicit assumption cost, forbids defining admissibility through prior resolution, and requires covariance under the dyad's automorphisms, so that reciprocal exchange follows from symmetry rather than from labels. The claim under test is that this yields an internally operative Distinction while withholding time, orientation, retention and observer-relative resolution.

Questions Opened by This Framework

Can the existence of admissible transformation be derived from Difference itself without circularity?

Is $\text{Aut}(\mathfrak{D})$ -covariance sufficient to capture the full content of “no hidden labels”?

When does a relation with a unique successor deserve functional representation, and when must the relational form remain primary?

What minimal extension of $\mathcal{W}$ supports branching without introducing probability?

Can a model of pre-spacetime physics realize reciprocal update without already assuming temporal dynamics?

Selected References Cited in Distinction

Isaacson, J. D., & Kauffman, L. H. (2016). Recursive distinctioning. Preprint arXiv:1606.06965.

Wolfram, S. (2020). A class of models with the potential to represent fundamental physics. *Complex Systems*, 29(2), 107–536. doi:10.25088/ComplexSystems.29.2.107. Preprint arXiv:2004.08210.

Note on these references. These works are comparison classes, not evidence that the ontology proposed here is correct. Bibliographic details were verified against primary or authoritative sources on 26 September 2026.

Chapter 4

Boundary: When Distinction Survives Transformation

Claim ~ An operative Distinction becomes retained when its non-equivalence remains recoverable under declared structural variation and can constrain what remains admissible downstream. Boundary is the criterion under which that recoverability is preserved. The chapter earns frame-relative resolvability, admissible possibility, retained-dependency precedence, and criterion-based identity, all from retained distinction.

Chapter discipline. This chapter inherits $\mathfrak{D}$, $\mathcal{C}_{\mathfrak{D}}$, $\mathcal{U}_{\min}$ and $J_{\mathcal{U}}$. Because $J_{\mathcal{U}}$ preserves the reciprocal dyad by construction, retention cannot be tested only against $J_{\mathcal{U}}$. Boundary therefore distinguishes the internal update law $\mathcal{U}$ from a declared diagnostic family $\mathfrak{T}_{\text{test}}$ used to ask what survives structural change.

■ $\mathcal{U}$ = internal admissible succession $\mathfrak{T}_{\text{test}}$ = diagnostic transformation family

The distinction between those two types is load-bearing. Chapter 3 required internality because it made a constitutive claim: Difference becomes operative only if succession belongs to the modeled structure rather than to an analyst's description. Boundary asks a different, modal question: would an already-internal distinction remain recoverable under specified variation? A counterfactual robustness test may therefore be stated in the metalanguage without being promoted to a third internal law. If later physics requires a privileged, physically realized transformation family that cannot be derived, the primitive count must increase.

Information-literature discipline. Retention, counterfactual preservation, erasure, possible/impossible transformations, and identity under change have established literatures. This chapter therefore treats retained distinction as a deliberately weak structural precursor, not as a replacement for Shannon information, thermodynamic information, constructor-theoretic information, or a mature theory of identity.

4.1 Where Distinction Leaves Us

Chapter 3 gives an operationally nontrivial dyad. Every application of $\mathcal{U}_{\min}$ exchanges the active configuration, and the induced map satisfies $J_{\mathcal{U}}^2 = \text{id}$. Nothing stands still, yet reciprocal non-equivalence is never lost under that update because the update is generated from the same exchange-symmetric structure.

Boundary begins where that guarantee ends. The relevant question is not whether a differs from b under $J_{\mathcal{U}}$. It is whether the operative distinction remains recoverable when its realization, carrier, or surrounding structure is varied, and whether retaining it can make a difference to what follows.

4.2 Persistence Is Not Stasis

With no self-loop in $\mathcal{U}_{\min}$, no primitive configuration persists by remaining unchanged. Persistence at this stage can only mean persistence of a structural distinction. This aligns with Proposition 1A: what matters is distinguishability surviving transformation, not a token remaining frozen through duration.

The chapter therefore avoids saying that a or b persists. A realization may be replaced completely while a distinction it instantiates remains recoverable.

■ state invariance $\neq$ retained distinction

4.3 Why Boundary Needs a Stronger Test

On the carrier $\{a,b\}$, the endomaps are id , the swap $J_{\mathcal{U}}$, and two constant maps that collapse both inputs onto one image. id and $J_{\mathcal{U}}$ preserve dyadic separation. Constant maps erase it. If Boundary considered only $\mathcal{U}_{\min}$, retention would be automatic; if it promoted every conceivable map into a physical update, it would add ontology without warrant.

The chapter therefore separates constitutive succession from diagnostic variation. The latter asks a robustness question about a structure already earned; it does not tell the primitive system what it may internally do.

4.4 The Diagnostic Transformation Family $\mathfrak{T}_{\text{test}}$

Let $\mathfrak{T}_{\text{test}}$ denote a declared family of transformations used in the theory's metalanguage to test preservation. A member T may alter the carrier, the realization of the poles, the relation that instantiates non-equivalence, or the embedding of the dyad, provided its source and target types are explicit.

Because $\mathfrak{T}_{\text{test}}$ is diagnostic, it may include collapse maps without reintroducing primitive stasis into $\mathcal{U}_{\min}$. A constant structural test and an internal successor pair are different types of object. The no-stasis decision in Chapter 3 remains intact.

4.5 Frame-Relative Resolvability Returns Here

Chapter 3 deliberately removed a generic resolver from the constitution of Distinction. Boundary is the first place a resolving frame is again needed, because retention is now a question about whether a distinction remains accessible after transformation. The frame does not create the underlying Difference or make succession internal; it evaluates recoverability in a transformed structure.

Let W denote a resolving frame: a structural criterion or map that determines which distinctions are accessible at a declared organizational level. W need not be a conscious observer, sensor, coordinate chart, spatial frame, or reference pole. It is a criterion of discriminatory access.

Keep Origin's Res notation set-valued. For any configuration Σ ,

■ $\text{Res}_W(\Sigma)$ = the set of distinctions resolvable from Σ under W

Origin's $\text{Res}_{W_0}(\Omega) = \emptyset$ is therefore a special case of the same type: at the least-resolving initial frame, no operative distinction is available. Boundary does not redefine Res as a number, truth value, or operation set.

Frame equivalence is then written $\sim_W$. Two configurations are frame-equivalent when W cannot resolve them apart. This relation is epistemic/structural in the minimal sense of accessibility; it does not imply subjective observation.

4.6 A Preservation Predicate

Return later reserves $\text{Ret}(A_F; \cdot)$ for re-entry into the identity class of an organizational anchor A_F . Boundary therefore uses a different predicate. For $T \in \mathfrak{T}_{\text{test}}$, define $\text{Pres}_W(a, b; T)$ by the condition that the images of the two poles remain non-equivalent as resolved by W :

■ $\text{Pres}_W(a, b; T)$ iff $T(a) \not\sim_W T(b)$

Equivalently, the transformed a/b distinction remains represented in Res_W of the target structure. Pres_W is truth-valued. It is not an information quantity.

The definition is deliberately frame-relative. A transformation can preserve a distinction for one resolving frame and erase it for another.

4.7 Collapse Is Loss of Distinction, Not Return to Ω

Suppose a diagnostic map T_c sends both poles to one effective image q :

$$T_c(a) = q \quad T_c(b) = q$$

Then $\text{Pres}_W(a,b;T_c)$ fails for any frame that resolves only the target structure presented. Nothing has returned to Ω . No privileged origin was assigned. Loss is simply collapse of the previously recoverable non-equivalence.

This makes no appeal to a marked pole such as $S_0 = \Omega$, and lets the negative case be stated symmetrically.

4.8 Preservation Can Change the Realization

Retention does not require $T(a)=a$ or $T(b)=b$. Let T_p carry the poles to new realizations a' and b' . If W can still resolve their non-equivalence, $\text{Pres}_W(a,b;T_p)$ holds:

$$\blacksquare T_p(a)=a' \ T_p(b)=b' \ a' \not\sim_W b'$$

The retained content is therefore relational rather than token-identical. Realizations may change while a criterion of distinction remains recoverable.




Figure 4.1. What survives a transformation, and what does not. The internal update belongs to the structure; diagnostic tests belong to the robustness test. A preserving test carries the poles to new realizations that remain distinguishable; a collapsing test sends both to one image. Two signatures behave the same way: a clean photocopy changes the ink and paper but keeps them distinguishable, while a

blurred fax removes the fine detail that told them apart and reduces both to the same smudge. Whether a copy preserves the difference depends on who is checking.

4.9 From Preservation to the Retained Distinction r_{ab}

When the reciprocal distinction remains recoverable under the declared relevant transformation regime, write r_{ab} for that retained distinction. The notation does not introduce a binary digit, an orientation, or a numerical amount of information.

r_{ab} = retained reciprocal non-equivalence of a and b

At this level $r_{ab}=r_{ba}$ in content: the indices identify the participating roles but do not order them. A later oriented relation may distinguish those orderings, but Boundary does not.

“Relational bit” may remain editorial shorthand only if Appendix A states clearly that r_{ab} is not a computational bit $b \in \{0,1\}$. “Retained distinction” is the ontologically safer term.

4.10 The Admissible-Possibility Set $\mathcal{P}$

Retention becomes consequential only if it can restrict what remains structurally admissible. Boundary therefore restores the possibility function needed throughout Relation and later Time. For a configuration Σ , let $\mathcal{P}(\Sigma)$ denote the set of configurations reachable from Σ through the admissible succession structure available at that stage.

$\mathcal{P}(\Sigma) = \{\Sigma' : \Sigma' \text{ is reachable from } \Sigma \text{ under admissible succession}\}$

$\mathcal{P}$ is a set-valued possibility function, not a probability distribution. It assigns no likelihoods and assumes no measure. Where a relation r is embedded in a larger domain, $\mathcal{P}(\Sigma, r)$ may be used schematically to denote the admissible set conditional on retaining that relation.

At the primitive two-state level the set is nearly trivial. Its importance is type-theoretic: the framework now has a place to state whether retaining a distinction changes what can follow once larger structures exist.

4.11 Retained-Dependency Precedence $\prec$

The conjunction of admissible succession and retention now yields something bare Difference cannot provide: dependency. Write

■ $\Sigma_a \prec \Sigma_b$

when Σ_b contains, or its admissibility depends on, a retained consequence inherited from Σ_a such that removing the relevant retained contribution changes Σ_b or changes the admissible possibility set leading to it. This is retained-dependency precedence.

The criterion is counterfactual rather than temporal. A useful schematic test is: if deleting the retained contribution from Σ_a changes $\mathcal{P}(\Sigma_b)$ or the admissibility of Σ_b , then the dependency is structurally consequential.

This directly discharges Chapter 3's demand that $\mathcal{U}$ do work that $\emptyset$ alone cannot do. Static non-equivalence cannot generate a successor possibility set or a retained-dependency relation. Admissible succession plus retained consequence can.

The symbol $<$ does not yet mean “earlier in physical time,” causal influence, or orientational direction. It is a generative/dependency ordering between configurations. Transitivity, acyclicity, and totality are not assumed here.




Figure 4.2. *Precedence is dependence, not earliness.* Σ_a precedes Σ_b when removing what Σ_a contributed would change Σ_b or what is admissible for it. The stock and the garnish were both prepared before the sauce, but leaving out the stock changes the sauce while leaving out the garnish does not, so only the stock precedes it.

4.12 Boundary as a Preserved Criterion of Non-Collapse

Boundary enters when preservation is treated as a criterion rather than a single successful case. A primitive Boundary is the relational condition under which a distinction remains recoverable across the transformation regime relevant to the identity under consideration.

For a declared frame W and diagnostic family $\mathfrak{T}^*$, define the preservation class:

$$\blacksquare B_{ab}(W, \mathfrak{T}^*) = \{T \in \mathfrak{T}^* : \text{Pres}_W(a, b; T)\}$$

This set is bookkeeping for the boundary condition, not a spatial region. It separates preserving transformations from collapsing transformations. There is still no inside, outside, surface, distance, or enclosure.

4.13 Which Transformation Family Counts?

Retention is relative to a regime of variation. A distinction robust under one family may collapse under another. The chapter exposes this relativity rather than treating it as an embarrassment.

At this stage $\mathfrak{T}^*$ is selected by the diagnostic question. Later physics must earn a principled transformation family from dynamics, coupling, coarse-graining, symmetry, or empirical constraint. If the mature theory requires an irreducibly primitive physical transformation class in addition to Difference and $\mathcal{U}$, then “two foundational commitments so far” must be revised upward.

This is also why the internality standard differs between Chapters 3 and 4 without inconsistency. $\mathcal{U}$ is constitutive of Distinction and therefore must belong to the modeled structure. $\mathfrak{T}_{\text{test}}$ is a modal probe of robustness and therefore may remain metalanguage until a later physical theory identifies which probes correspond to realized transformations.

4.14 Identity Criteria Without an Anchor

The rest of the book also requires a way to say that two changing configurations instantiate the same higher-order identity. That scaffold can be introduced without privileging Ω or introducing a central anchor.

Let F be an identity criterion: a declared structural condition specifying which features are constitutive of the higher-order identity under consideration. Define identity equivalence by

$$\Sigma \sim_F \Sigma' \text{ iff } \Sigma \text{ and } \Sigma' \text{ satisfy the same criterion } F$$

The corresponding candidate identity is the equivalence class

$$O = [\Sigma]_{\sim_F}$$

This is a minimal identity scaffold, not yet a fully integrated object. At the primitive pair the construction is thin; Relation will give it substantive content by supplying several retained relations whose organization can jointly satisfy F. What Boundary earns is the grammar of identity through change: token variation can occur while an identity criterion remains satisfied.

No anchor is required by this definition. A later closed organization may earn an endogenous reference role, but reference is not constitutive of $\sim_F$ itself.

4.15 Resolving Frames and Identity Criteria Must Stay Distinct

W and F answer different questions. W asks what distinctions a frame can resolve. F asks which features must be preserved for two configurations to count as realizations of the same higher-order identity.

$$\sim_W = \text{frame equivalence} \quad \sim_F = \text{identity equivalence}$$

Two configurations may be indistinguishable to a coarse resolving frame yet fail the identity criterion, or be distinguishable in many details while still satisfying the same F. Conflating the relations would make observation constitutive of identity, which the framework does not assume.

4.16 Embedding, Projection, and Coarse Loss

A useful nontrivial test can embed the dyad into a larger carrier X without yet claiming that X is an integrated relational domain:

$$\blacksquare e : \mathcal{C}_2 \rightarrow X$$

If $e(a)$ and $e(b)$ remain resolvable as non-equivalent under W, the distinction survives enlargement. X is only a target of the robustness test.

A many-to-one projection can do the opposite. It may preserve some distinctions while collapsing others. Boundary needs only the formal possibility of such maps; Scale will later earn physically grounded coarse-graining criteria. The present chapter must not smuggle metric smallness or resolution scale into the projection.

4.17 Retained Distinction as Minimal Information

A retained distinction becomes informational in the weakest functional sense when its presence changes admissible possibilities. The relevant condition is not merely that r_{ab} exists, but that retaining or removing it changes $\mathcal{P}$ for some downstream configuration or domain.

$$\blacksquare \mathcal{P}(\Sigma, r_{ab}) \neq \mathcal{P}(\Sigma, \emptyset)$$

This is conceptual information before probability, coding, entropy, or energetic cost. It captures the minimum idea that a preserved difference can make a structural difference to what follows. Later information theories must either recover this case as a limit/precursor or show that the proposal is too weak to support the intended bridge.

4.18 Boundary Is Not Yet an Anchor

Neither W , F , B_{ab} nor r_{ab} selects one pole as a privileged reference. A resolving frame discriminates; an identity criterion classifies; a boundary preserves non-collapse. None of those operations by itself produces a center or origin.

The current candidate is that Closure may later earn endogenous reference: a sufficiently closed organization can become a stable reference condition for subsequent organization. That proposal reverses the old assumption that the anchor was inherited from $S_0 = \Omega$ and must be tested explicitly when Closure is revised.

4.19 Boundary Is Not Yet Orientation

The retained distinction remains exchange-symmetric. Dependency precedence $<$ is a relation between configurations connected by retained consequence; it does not assign source/target roles inside the primitive dyad or establish the orientational non-equivalence later written $<_o$.

Orientation must still earn persistent consequential non-equivalence between otherwise exchangeable roles. Boundary gives it retained structure to work with, not the result in advance.

4.20 Boundary Is Not Yet Physical Time

$\mathcal{U}$ supplies admissible succession, and $<$ supplies retained-dependency precedence. Neither is yet elapsed duration. The formal sequence of applications can be indexed or counted in the analyst's mathematics without

thereby yielding seconds, rates, simultaneity, proper time, or an invariant causal cone.

Time will later ask whether stable dependency precedence can support temporal order and whether recurrent, countable, stable, couplable subsystems can become endogenous clocks. Boundary supplies prerequisites, not the temporal interpretation.

4.21 Minimal Worked Example

Start with the reciprocal Distinction from Chapter 3. Let T_p map $a \mapsto a'$ and $b \mapsto b'$, and let W resolve a' from b' . Then $\text{Pres}_W(a,b;T_p)$ holds, so the distinction has a retained realization r_{ab} . Let T_c send both a and b to q . Then $\text{Pres}_W(a,b;T_c)$ fails.

Now suppose a later configuration Σ_b is admissible only when the retained difference represented by r_{ab} is present. Removing that retained consequence changes $\mathcal{P}(\Sigma_b)$. The framework may then write $\Sigma_a < \Sigma_b$ without saying that Σ_a occurred earlier in physical time.

If multiple later configurations satisfy the same structural criterion F despite token changes, they may be grouped as $O=[\Sigma]_{\sim F}$. None of these moves requires Ω as an anchor. The example therefore displays the complete Boundary inheritance needed downstream: resolution, retention, possibility, dependency, and criterion-based identity.

4.22 What Boundary Earns

Frame-relative resolvability through a structural resolving frame W , with Res_W remaining set-valued.

A preservation predicate Pres_W distinct from Return's $\text{Ret}(A_F; \cdot)$.

The retained distinction r_{ab} without Ω , primitive orientation, or binary value.

The admissible-possibility set $\mathcal{P}$ as a set of reachable configurations, not a probability distribution.

Retained-dependency precedence $<$ as a non-temporal precursor of later causal/temporal order.

Boundary as a preserved criterion of non-collapse rather than a spatial surface.

A minimal identity criterion F , identity equivalence $\sim_F$, and candidate identity class $O=[\Sigma]_{\sim F}$ without an anchor.

A weak functional bridge from retained distinction to information through changed admissible possibilities.

A principled separation between constitutive internality in Chapter 3 and diagnostic robustness testing in Chapter 4.

4.23 What Boundary Does Not Earn

No privileged physical transformation family; $\mathfrak{T}_{\text{test}}$ remains diagnostic until later theory identifies realized transformations.

No Ω -designated pole, anchor, higher-order origin, or intrinsic center.

No orientation, orientational dependency $\prec_{\circ}$, spatial geometry, distance, inside/outside, or enclosure.

No physical time, causal cone, duration, clock, entropy, Shannon measure, thermodynamic erasure cost, or material carrier.

No claim that $\sim_F$ already describes a mature object; Relation and Closure must supply integrated organization and, if possible, endogenous reference.

No assumption that $<$ is transitive, acyclic, total, causal, or temporal.

4.24 Objections and Replies

Objection 1: $\mathfrak{T}_{\text{test}}$ is a third primitive disguised as methodology. **Reply:** Not at this stage. It is the metalanguage domain over which robustness is quantified, analogous to perturbation or quotient analysis. A third ontological commitment appears only if later physics requires an irreducibly primitive family of actually realized transformations.

— — —

Objection 2: Chapter 3 rejected analyst-visible structure, while Chapter 4 relies on analyst-declared transformations. **Reply:** The standards differ because the claims differ. Chapter 3 is constitutive: succession must be internal for Difference to become operative. Chapter 4 is counterfactual: retention is a modal robustness property of an already-operative distinction. A test transformation need not itself be a constituent of the tested system.

— — —

Objection 3: Constant maps reintroduce stasis. **Reply:** No. A constant T_c is a diagnostic transformation of the representation/structure, not an internal successor pair in $\mathcal{U}_{\text{min}}$. The absence of primitive self-transitions remains intact.

— — —

Objection 4: Frame-relative retention makes information observer-dependent. **Reply:** W is a structural resolving criterion, not necessarily an observer. The framework exposes resolution dependence without identifying it with subjectivity. Later physical frames must be earned as realized structures.

— — — —

Objection 5: r_{ab} is just $\emptyset$ with a new name. **Reply:** r_{ab} carries an additional modal and historical fact: operative non-equivalence has remained recoverable across the declared variation regime. Bare $\emptyset$ states only the static relation in the primitive dyad.

— — — —

Objection 6: $<$ smuggles Orientation or Time into Boundary. **Reply:** $<$ records retained dependency between configurations: removing an inherited consequence changes admissibility. It does not orient the internal roles of a relation, measure duration, or imply a temporal partial order. Orientation and Time must add further constraints.

— — — —

Objection 7: $\sim_F$ requires an anchor. **Reply:** An identity criterion can classify configurations without privileging a center. An anchor may later be useful or emergent, but it is not logically constitutive of criterion-based equivalence.

— — — —

Objection 8: Information has been defined too weakly. **Reply:** Deliberately. Retained consequence is proposed as a minimum functional precursor. Quantitative information theories remain later specializations with stronger assumptions.

4.25 What Would Count Against the Claim

A proof that retention cannot be defined without making a privileged physical transformation family an additional primitive constituent.

A demonstration that frame-relative resolvability necessarily requires a conscious observer or spatial coordinate frame.

A downstream proof that every coherent identity criterion requires a primitive anchor or center.

A demonstration that retained-dependency precedence adds no structural content beyond bare succession or static non-equivalence.

A mature physical account of information in which no preserved distinguishability or consequential retained difference is required at any level.

Failure to connect $\mathcal{P}$, $<$, $\sim_F$, and r_{ab} coherently to their later uses in Relation, Return, Formalism, and Time.

Failure to identify any physically meaningful transformation regime in which the diagnostic notion of retention has explanatory value.

4.26 Research Frontier

Transformation selection. What later physical principle selects the transformation family under which a distinction should count as robust or retained?

Frame realization. When does an abstract resolving frame W become a physically instantiated frame rather than a criterion in the metalanguage?

Partial retention. Can recoverability be graded without importing probability, metric distance, or information measure too early?

Dependency structure. Under what additional conditions does $<$ become transitive, acyclic, or sufficiently stable to support temporal interpretation?

Identity. What conditions make $\sim_F$ more than a classification rule and yield autonomous higher-order organization?

Anchor emergence. Can Closure earn a stable endogenous reference role without contradicting the symmetric inheritance established here?

Information. Can familiar quantitative information measures be recovered as coarse-grained or specialized cases of consequential retained distinction?

4.27 Ontological Defensibility Pulse: Boundary

Pulse question	Applied to Boundary
1. Entities required	No new modeled substance is introduced. The chapter adds structural predicates and relations over already earned configurations: W , Pres_W , $\mathcal{P}$, $<$, F and the equivalence relations they induce. $\mathfrak{I}_{\text{test}}$ remains diagnostic unless later physics reifies it.
2. Ontological level	The chapter operates between internal succession and multi-relation organization. Its subject is robustness, dependency, and identity criteria, not geometry or physical dynamics in spacetime.
3. Lower-order dependencies	Every result depends on primitive Difference plus admissible succession from Chapters 2–3. Without $\mathcal{U}$, $\mathcal{P}$ and $<$ have no basis; without non-equivalence, there is nothing to retain.

Pulse question	Applied to Boundary
4. New emergent properties	Retained distinctions can constrain admissible successor structure. This is causal only in a precursor/counterfactual sense; physical causation is not yet claimed.
5. Claim types	The chapter is primarily relational and functional. It states what retention, dependency, and identity criteria would have to do, not what physical substrate realizes them.
6. New primitives	None is claimed beyond the two commitments so far. This remains conditional on later success in deriving physically relevant transformation families and frames rather than stipulating them.
7. Fewer assumptions?	W and F are kept distinct because collapsing resolution and identity into one structure would smuggle observation into identity. Pres_W is kept distinct from $\text{Ret}(A_F; \cdot)$ to avoid semantic collision with Return.
8. Observational constraints	The construction must reproduce downstream uses of frame-relative resolution, $\mathcal{P}$, $<$ and $\sim_F$ without reintroducing Ω -as-anchor, physical time, or orientation prematurely.

4.28 Precursors and Departures

Precursors. Shannon information (Shannon, 1948) supplies a quantitative theory of communication under probabilistic and coding assumptions not available here, and Landauer (1961) a later physical relation between logical erasure and energetic cost; neither is re-derived in Boundary. Constructor theory (Deutsch, 2013; Deutsch and Marletto, 2015) characterizes physical information through possible and impossible tasks on substrates. Its counterfactual orientation is a close neighbor to preservation under declared transformations, but it is a law-level physical framework, whereas Boundary is still pre-geometric and substrate-neutral.

What is new here. The chapter places frame-relative recoverability, retention, possibility, dependency precedence and criterion-based identity in one stage, between internally admissible succession and multi-relation organization, while withholding an anchor, orientation, metric time and physical measures of information. The claim under test is whether this placement and separation of roles can support the later chapters without circular inheritance.

4.29 Implications and Handoff to Relation

Relation now inherits substantially more than a retained pair, but less than an Ω -centered architecture would assume. It receives symmetric retained

distinctions r_{ij} ; resolving frames W ; admissible possibility sets $\mathcal{P}$; retained-dependency precedence $<$; and the identity-equivalence scaffold $\sim_F$. It does not receive a privileged anchor.

The derivational chain is now:

■ Difference $\rightsquigarrow$ admissible succession $\rightsquigarrow$ reciprocal Distinction $\rightsquigarrow$ retention $\rightsquigarrow$ dependency $\rightsquigarrow$ mutual constraint

Relation must show how several retained distinctions cease to vary independently and become an integrated organization. It may use W , $\mathcal{P}$, $<$ and $\sim_F$ because Boundary has now introduced them. If Relation still requires Ω as an anchor, that requirement must be removed, reformulated as a criterion, or explicitly deferred until Closure can attempt to earn endogenous reference.

Handoff to Relation. When several retained distinctions coexist and constrain one another's admissible possibilities, what additional condition turns them from a collection into a persistent relational organization?

A distinction can now survive change, and what survives can constrain what follows.

Questions Opened by This Framework

What physically selects the transformation family under which a distinction should count as retained?

Can frame-relative resolvability be physically instantiated without an observer and without a metric?

Which properties of retained-dependency precedence are necessary before causal or temporal interpretation becomes warranted?

Can higher-order identity be built from $\sim_F$ and mutual constraint without any privileged anchor?

Can Closure subsequently earn an endogenous reference condition without undoing exchange symmetry at the foundation?

Can quantitative information theory be recovered from consequential retained distinctions rather than imported as a separate primitive?

What computational test would show that the sequence $\mathcal{U} \rightsquigarrow$ retention $\rightsquigarrow \mathcal{P} \rightsquigarrow <$ fails to add explanatory content beyond an ordinary transition system?

Selected References Cited in Boundary

Deutsch, D. (2013). Constructor theory. *Synthese*, 190(18), 4331–4359. doi:10.1007/s11229-013-0279-z.

Deutsch, D., & Marletto, C. (2015). Constructor theory of information. *Proceedings of the Royal Society A*, 471(2174), 20140540. doi:10.1098/rspa.2014.0540.

Landauer, R. (1961). Irreversibility and heat generation in the computing process. *IBM Journal of Research and Development*, 5(3), 183–191.

Shannon, C. E. (1948). A mathematical theory of communication. *Bell System Technical Journal*, 27(3), 379–423, and 27(4), 623–656. doi:10.1002/j.1538-7305.1948.tb01338.x.

Note on these references. These works are comparison classes, not evidence that the ontology proposed here is correct. Bibliographic details were verified against primary or authoritative sources on 26 September 2026.

Chapter 5

Relation: When Difference Becomes Structure

Claim ~ Structure begins when retained distinctions cease to vary independently and become mutually constraining parts of a persistent relational organization.

Chapter discipline. This chapter inherits symmetric retained distinctions r_{ij} , frame-relative resolvability through W , admissible possibility sets $\mathcal{P}$, retained-dependency precedence $<$, and criterion-based identity through F and $\sim_F$. Its task is to show how more than one retained distinction can become an organized whole using that inheritance alone. If that transition cannot be stated from the inherited machinery, the chapter fails its own derivational burden.

retained distinction $\rightsquigarrow$ mutual constraint $\rightsquigarrow$ invariant organization $\rightsquigarrow$ structure

Inheritance note. Boundary hands Relation retained distinctions, resolving criteria, admissible possibilities, dependency precedence, and an identity-equivalence scaffold. It does not hand forward an anchor. Relation therefore treats every reference center as unearned. If a stable reference role becomes necessary downstream, Closure must derive it from organization already available here rather than inherit it from Ω or designate one member by stipulation.

5.1 Where Boundary Leaves Us

A single retained distinction is still too small to look like a world. Relation widens the frame until several retained relations are visible at once.

At first they may be only a collection. Then one relation begins to limit what another can be. The scene changes: we are no longer cataloguing differences; we are watching organization appear among them.

Our task is to locate that transition precisely.

The question mark is the burden of this chapter. Relation becomes structure only if the multiplication of relations produces organization that is not exhausted by listing them separately.

■ Boundary supplies retained distinction and non-spatial boundary. Open question: whether several retained relations can generate integrated organization without a new primitive.

5.2 From Retained Distinction to the Relational Domain

Let r_{ij} be a retained distinction between two relational positions q_i and q_j , in the sense earned by Boundary. At this stage $r_{ij} = r_{ji}$ in content unless a later chapter earns an asymmetry. A relational domain $\mathcal{R}$ collects several such retained distinctions into one jointly describable organization. The matrix R is bookkeeping over those inherited relations, not a new ontological layer.

$$\blacksquare R = [r_{ij}], \mathcal{R} = \{q_i, r_{ij}\}$$

The entries of R are the already-retained relations of Boundary, not a new kind of relation. Capital R names the matrix, not a promotion of its entries. The matrix notation is bookkeeping and must not be mistaken for a spatial grid. Rows and columns are not directions, coordinates or locations. If the labels of the state-positions are permuted while every relation is preserved, the represented organization should remain the same. A relabeling changes the description without changing the structure.

$$\blacksquare R \mapsto R^\pi, \text{ with } (R^\pi)_{ij} = r_{\pi(i)\pi(j)}$$

Here π is a relabeling, a permutation of the relational positions. The plain predicate M used later for membership is kept distinct from the calligraphic possibility function $\mathcal{P}$ inherited from Boundary. The requirement is not that this matrix form be fundamental. It is that the ontology remain invariant under mere renaming. If changing q_i to q_k changed the theory while preserving every relation, the labels would be carrying unexplained intrinsic content. Klein's Erlangen programme (1872) provides a precise mathematical ancestor for invariance under transformation; here the same discipline is applied one level below geometry. The hole-argument literature in the philosophy of relativity (Earman and Norton, 1987) poses a closely related question about what survives descriptive relabeling.

The symmetry inherited from Boundary is preserved: r_{ij} and r_{ji} carry the same retained content. Retained-dependency precedence $<$ may order configurations by inherited consequence, but it does not by itself orient the internal roles of r_{ij} . Directed relational roles are reserved for Orientation unless an asymmetry is derived rather than stipulated.

■ Multiple retained distinctions can be represented jointly without assigning them spatial positions, distances or directions. Open question: how networks of retained-dependency precedence $<$ constrain a domain while the retained relations themselves remain unoriented.




Figure 5.1. The same structure drawn twice. Four members and five relations, laid out once in one arrangement and once in another, with the adjacency matrix printed beneath each. The matrices are identical. The everyday counterpart is a league table sorted alphabetically and then by the year each club joined: the same league, rearranged. The insight is what the figure quietly withholds — nothing about the structure changed between the panels, so whatever differs between them is something the drawing supplied rather than something the relations contain. That is the invariance the chapter requires before relations can be called structure.

5.3 Relation Before Object

An object-first description begins with things and asks how they relate. This framework attempts the reverse. It asks whether a state-position can become identifiable because of the organization of relations it participates in, before any rich intrinsic object has been assumed.

Define the relational profile of q_i as the ordered collection of the relations it participates in:

$$\blacksquare \lambda_i = (\Gamma_{i1}, \Gamma_{i2}, \dots, \Gamma_{in})$$

If two state-positions have different relational profiles, $\lambda_i \neq \lambda_j$, they are structurally distinguishable even though we have assigned neither an intrinsic property. our proposal is not that every object is nothing but a row of a matrix. It is that individuation need not begin with intrinsic substance. A stable relational position can do some of the work ordinarily assigned to intrinsic identity.

This is a higher-order recurrence of the weak-discernibility problem isolated in Difference. At the primitive level, numerical dyadicity is admitted explicitly while symmetric irreflexive non-equivalence supplies relational discernibility.

At the present level, a relational position becomes distinguishable by the pattern of retained relations connecting it to the rest of an organized domain. Ontic structural realism makes a related move for physical objects (Ladyman and Ross, 2007; French, 2014). The difference here is that the framework is attempting to earn object-like identity from a thinner inherited scaffold rather than assume it about mature physics.

An object's primitive identity may be its stable position within a relational organization rather than an intrinsic property carried independently of that organization.

5.4 A Collection of Relations Is Not Yet a Structure

The existence of several relations is insufficient. Two unrelated retained distinctions can coexist without forming one integrated structure. Even connectivity is too weak: two relations may share a state-position while remaining freely variable with respect to each other. A stronger threshold is needed.

Boundary (4.10) introduced $\mathcal{P}$ for the set of relational states reachable from a configuration. Let $\mathcal{P}(r_{ij})$ be the admissible states of a relation considered by itself, and $\mathcal{P}(r_{ij} | \mathcal{R})$ the admissible states of the same relation embedded in the wider domain. If the surrounding organization restricts what r_{ij} can be, then:

$$\blacksquare \mathcal{P}(r_{ij} | \mathcal{R}) \neq \mathcal{P}(r_{ij})$$

The difference between these two possibility sets is the first formal sign that the relation participates in an integrated structure. The larger domain now matters to the local relation. This yields the chapter's working definition.

A relational structure is a set of retained relations whose admissible states are constrained by the organization of other relations in the set.

Constraint here is deliberately broader than causation. It may be logical, combinatorial, algebraic, dependency-based or eventually dynamical. We do not need physical causation to say that one relational configuration excludes another. Causal interpretation is a later achievement. Nor must every relation constrain every other. Structure may be modular: one subset tightly integrated, another only weakly coupled. That possibility matters once object-like substructures are introduced.

■ Mutual constraint, defined as a difference between $\mathcal{P}(r_{ij})$ and $\mathcal{P}(r_{ij} | \mathcal{R})$, separates structure from mere connectivity without invoking causation. Open question: whether the constraint relation can be formalized without probabilistic or metric language (Question 1).

5.5 Constraint Propagation and Recursive Incorporation

A retained distinction becomes more structurally consequential when its consequences propagate through the domain. Because $\mathcal{U}$ is fundamentally an admissible transition relation rather than a generally available function, write two successive admissible configurations as:

$$\blacksquare (\Sigma_n, \Sigma_{n+1}) \in \mathcal{U}, (\Sigma_{n+1}, \Sigma_{n+2}) \in \mathcal{U}$$

Suppose Σ_n carries a retained contribution associated with r_a and removing that contribution changes the admissible possibilities available to r_b in a later configuration. Then r_a has not merely persisted as a stored mark. Its retained consequence participates in the dependency structure of the domain. Boundary already supplies the schematic relation $\Sigma_n < \Sigma_{n+2}$ when such removal changes what remains admissible.

$$\blacksquare \text{retained } r_a \Rightarrow \Delta \mathcal{P}(r_b \mid \mathcal{R})$$

This permits a stronger interpretation of retention than pairwise preservation alone requires. Persistence need not mean that an earlier realization remains unchanged. A relation can disappear in its original carrier while its retained consequence remains encoded in later admissibility. Repeated succession can be represented by relational composition $\mathcal{U}^k$ in the analyst's formalism, but that notation does not turn $\mathcal{U}$ into a primitive function or introduce physical duration. What matters here is whether some organization remains identifiable across the admitted succession and declared tests. That question leads directly to invariance.

○ INTERPRETIVE Constraint propagation allows a retained distinction to persist through consequences rather than through literal preservation of its original carrier.

5.6 Relational Invariance and Structural Persistence

Suppose an identity-relevant criterion F of the relational organization remains satisfied across a declared organization-level diagnostic family $\mathfrak{I}\mathcal{R}$, a specialization of Boundary's diagnostic transformation family rather than an additional internal update law. Then:

$$\blacksquare F(T(\Sigma)) = F(\Sigma) \text{ for every } T \in \mathfrak{I}\mathcal{R}$$

We do not yet specify what F must be. It might concern connectivity, a pattern of participation, an algebraic constraint, or a more sophisticated invariant introduced later. The point is methodological: structural persistence requires stating both what is identity-relevant and under which declared variation it is

tested. The diagnostic family does not tell the system how to update; it asks whether already-earned organization survives variation. This immediately separates two notions often conflated:

■ state persistence $\neq$ structural persistence

A state persists when some particular configuration remains. A structure persists when identity-relevant organization survives even though constituents or local values change. A whirlpool is not offered as proof of our ontology, only as the logical form. The pattern persists while the material occupying it changes. Section 5.7 makes the same point without a fluid. An invariant with no specified transformation class is rhetorically impressive and formally empty. Weyl's treatment of symmetry (1952), which makes invariance under a stated group the content of objectivity, is the nearest classical statement of the same discipline.

■ Structural persistence is preservation of identity-relevant relational organization through an explicitly stated diagnostic transformation family. Open question: what the weakest sufficient criterion is, and which later physical dynamics, if any, select a privileged realized transformation regime rather than leaving $\mathfrak{R}$ purely diagnostic.

5.7 Carrier Persistence Is Not Structural Persistence

Once structural persistence is separated from state persistence, a further distinction follows. A relational pattern can remain identifiable even when its physical or representational carrier changes. Engineered information systems demonstrate the logical form without establishing anything about fundamental physics.

Consider an encoded work stored in one hardware state, decoded into a media encoding, transmitted. Reconstructed as an audiovisual pattern available to a human. The successive realizations are not physically identical; their microscopic states can differ radically. Yet selected relations are preserved well enough that the later realization is recognized as an instance of the same organized content.

■ $H \mapsto D \mapsto M \mapsto P$, with $H \neq D \neq M \neq P$ and $H \sim_F D \sim_F M \sim_F P$

Here H is a hardware realization, D an encoded organization, M a decoded media structure, P a perceptually accessible realization. $\sim_F$ denotes equivalence with respect to the selected relational invariant F , not physical identity. This motivates a term used later in the series.

Relational re-instantiation is the production of a new state or realization whose organization preserves selected relational invariants of an earlier structured state.

The example establishes only logical coherence. Human-made encodings are designed to preserve specified relations; they do not show that nature works the same way. Their narrower value is to show that persistence of organization does not require persistence of carrier. A theory of object-like identity need not equate sameness with material identity. The philosophy of mind reached the same conclusion under the name multiple realizability (Putnam, 1967; Fodor, 1974). A functional organization can be realized by physically different substrates. This section borrows the form of that argument without its psychological content.

■ Persistence of organization does not require persistence of carrier. Open question: whether re-instantiation supplies a generalizable invariant criterion or remains an analogy (Question 3; 5.19, item 4).

5.8 Underlying State, Identity Equivalence and Frame-Resolved State

The preceding example exposes another ambiguity. Two configurations can be non-identical while satisfying the same identity criterion, and a resolving frame can in turn fail to discriminate configurations that differ in identity-relevant ways. Three relations must stay separate:

■ underlying non-identity $\neq$ identity equivalence $\sim_F \neq$ frame equivalence $\sim_W$

Let W be a resolving frame in Boundary's sense. Two underlying configurations may be distinct, $Xa \neq Xb$, while W fails to resolve them apart, $Xa \sim_W Xb$.

Separately, an identity criterion F may classify two configurations as realizations of the same higher-order identity, $Xa \sim_F Xb$, even when W resolves many differences between them. Neither equivalence entails the other. This is Boundary's explicit separation of discriminatory access from identity carried into structured domains.

A thermal example is useful only as an illustration of effective description. A temperature reading or thermal sensation can integrate several lower-order physical relations into one effective state without implying that those lower-order states are identical. At the present ontological level the narrower lesson is simply that a resolving criterion may coarse-grain distinctions while an identity criterion tracks a different set of preserved features.

■ $Xa \sim_W Xb$ does not imply $Xa \sim_F Xb$

Both equivalences are indexed and criterion-relative. There is no license to infer identity simpliciter from either one, and no license to make observation constitutive of object-like identity.

○ INTERPRETIVE Sameness at an emergent level may consist in preservation of identity-relevant organization under F even while a resolving frame W continues to discriminate lower-order differences.

5.9 When Structure Becomes Object-Like

We can now state a candidate for object-like identity without assuming primitive substance. Let Σ range over relational configurations and let $\sim_F$ identify configurations that preserve the organization judged identity-relevant by criterion F . An object-like identity is then, provisionally, an equivalence class:

$$\blacksquare O = [\Sigma]_{\sim_F}$$

This is a model of persistence, not a completed ontology of objects. Several lower-order configurations may count as the same higher-order object if they preserve the relations that constitute the object's continuity within the domain. Benacerraf (1965) argued that numbers are positions in a structure rather than intrinsically propertied objects. The building here makes the same wager for persistent physical organization, one level up from the relational positions of 5.3.

An object-like cluster C should also display constitutive asymmetry between relations that participate in its identity and relations that do not. No metric of coupling strength has yet been earned, so the diagnostic must remain counterfactual rather than quantitative:

$$\blacksquare \exists r \in C \text{ such that removing } r \text{ changes } F(C), \text{ while not every } r' \notin C \text{ does}$$

The condition does not define a complete boundary; it marks the minimal fact that some relations matter constitutively to F while arbitrary external relations do not. If a declared diagnostic transformation T maps C to C' while $C' \sim_F C$, then C exhibits structural persistence under that test. The language of an object becomes useful only when the criterion survives nontrivial tests specified independently of the desired grouping.

Object-like persistence is preserving identity-relevant relational organization across admissible transformation.

○ SPECULATIVE This is a candidate route from relation to objecthood. It has not shown that all physical objects are equivalence classes of relational

configurations, and it earns nothing if any grouping can be made persistent by choosing F after the fact (5.19, item 5).

5.10 Two Internally Equivalent Objects and Higher-Order Discernibility

Object-like persistence produces a new version of the problem that began the book. Suppose two persistent organizations OA and OB satisfy the same internal identity criterion. Can a larger resolving frame still preserve them as two distinct members of one domain rather than collapse them into one effective class?

The question must be stated carefully. Numerical distinctness and frame-resolved discernibility are not the same claim. It is logically possible to posit two numerically distinct but perfectly exchangeable organizations. What must be explained is how a larger frame W preserves their non-equivalence as two resolvable members of one domain. If every relation available under W is invariant under exchanging OA and OB, then W contains no criterion that tells their relational positions apart. To preserve two distinguishable positions at the higher level, the larger domain must retain some difference in their relational profiles.

Let $\lambda_W(O)$ be the relational profile of organization O as resolved within the larger frame W. Higher-order discernibility requires at least:

■ $\lambda_W(OA) \neq \lambda_W(OB)$

This does not require the organizations to possess different intrinsic properties. It requires the larger domain to retain a difference in how they participate relationally. The same architecture is thereby reused at a higher organizational level: distinction, retention, identity, then higher-order distinction. The nearby technical literature includes debates over permutation symmetry and the identity of indiscernibles for quanta (French and Redhead, 1988), which ask related questions about entities sharing intrinsic properties.

■ If two internally equivalent persistent objects coexist observably, some relation in the larger frame must preserve their non-equivalence. Open question: what minimum reference structure suffices to break exchange symmetry (Question 6).

5.11 Relational Position Without Space

The previous section yields a concept that resembles position without being spatial. OA and OB can satisfy the same internal identity criterion while

occupying different relational conditions with respect to a larger resolving frame. Define:

$$\blacksquare p_A = \lambda_W(O_A), p_B = \lambda_W(O_B), p_A \neq p_B$$

The symbols p_A and p_B are not coordinates. They are relational positions: distinctive profiles by which the larger frame resolves each object relative to the rest of the domain.

Relational position is the distinctive relational profile an organization occupies within a larger resolving domain.

No anchor is required for this definition. A relational position may be fixed by a distributed profile across the larger domain rather than by relation to one privileged member. If two organizations have the same relation to one candidate reference but differ elsewhere in the domain, the richer profile can still distinguish them. Position is therefore a pattern of relations sufficient for frame-relative discernibility, not an intrinsic tag.

Relational position is not yet spatial: it has no line, interval or metric until Orientation and Distance.

Spatial position may eventually emerge from persistent non-equivalent relational positions, but Relation earns only the latter.

5.12 Higher-Order Membership in a Multi-Relation Domain

Boundary supplied a non-spatial preservation criterion and an identity scaffold, but it did not supply a primitive multi-relation aggregation operator. Relation therefore asks a narrower question: when should a retained relation count as participating in the organization $\mathcal{R}$? The answer should be stated from mutual constraint already earned here rather than by adding a new $\mathcal{A}$.

$$\blacksquare M_{\mathcal{R}}(r) \text{ holds when participation of } r \text{ changes the admissible organization of } \mathcal{R}$$

The worked example of 5.16 supplies a non-agential case. A relation participates in the integrated structure when embedding it in $\mathcal{R}$ changes admissible possibilities relative to considering it independently. A simple structural membership predicate is therefore $M_{\mathcal{R}}(r)$ iff $\mathcal{P}(r \mid \mathcal{R}) \neq \mathcal{P}(r)$. No observer or privileged center decides membership. The predicate is fixed by the same mutual-constraint criterion used to distinguish structure from mere collection.

$$\blacksquare M_{\mathcal{R}}(r) \iff \mathcal{P}(r \mid \mathcal{R}) \neq \mathcal{P}(r)$$

A higher-order domain can then be described extensionally as the relations satisfying $M_{\mathcal{R}}$, while its identity criterion F specifies which pattern of such participation is constitutive. Existential or universal statements about membership require only ordinary quantification in the metalanguage; they do not require a new modeled operator. Cardinal, majority, weighted, or threshold rules would require additional structure not yet earned.


Result. No independent aggregation primitive is required to state higher-order membership under one shared structural criterion. Membership is participation in mutual constraint; quantification over members remains metalanguage. This keeps $\mathcal{U}$ typed as admissible succession rather than silently turning it into a Boolean accumulator or verdict-combining operation.

Cases in which different resolving frames classify the same organization differently are a separate problem. They concern reconciliation among frame-relative descriptions, not the constitutive membership criterion of $\mathcal{R}$. Relation therefore keeps W and F distinct: a frame may fail to resolve a constitutive difference, and a frame may resolve differences that do not matter to identity.

■ Higher-order membership can be stated through mutual constraint and ordinary quantification without a new aggregation primitive. Cardinal, weighted, and threshold membership remain deferred until the required magnitude or valuation structure is earned.


Membership is participation in mutual constraint

r considered alone



its possibilities $\mathcal{P}(r)$

r embedded in the organization




fewer possibilities $\mathcal{P}(r \mid \mathcal{R})$

the membership test

$$M_{\mathcal{R}}(r) \Leftrightarrow \mathcal{P}(r \mid \mathcal{R}) \neq \mathcal{P}(r)$$

r belongs when belonging changes what r can do

An everyday counterpart: stones and an arch



Touching the arch does not make the pebble part of it. What decides membership is whether belonging changes what a thing can do.

*Figure 5.2. Membership is participation in mutual constraint. A relation belongs to an organization when being embedded in it changes the relation's admissible possibilities. A stone set in an arch can only be where it is, held by its neighbors; the same stone on the ground could lie any way at all. A pebble resting on the arch touches it but can be lifted off without changing anything, so it is not a member. The picture recalls Marco Polo's answer to Kublai Khan in Calvino's *Invisible Cities** (1974): the bridge is held up not by any one stone, but by the line of the arch the stones form.**

5.13 Flexible Boundaries, Transitional Cases and Structural History

A higher-order boundary need not preserve exactly the same membership across every admissible configuration. What can persist is the criterion F together with a pattern of constitutive participation, while individual relations enter, leave, or change realization. The appropriate precursor to history here is retained-dependency precedence, not an assumed interval of duration.

- $\Sigma a < \Sigma b$ when retained contribution from Σa changes the admissibility of Σb

Along an admissible succession, the relations constitutive of F may change while the higher-order criterion remains satisfied. A transitional case is simply one in which the current organization does not yet satisfy the same participation pattern as either of two nearby identity-relevant regimes.

- boundary stability $\neq$ boundary rigidity

The criterion by which membership is resolved can persist while particular members enter, leave or remain ambiguous. Higher-order identity is therefore compatible with change in composition.

A stronger case occurs when two configurations that are equivalent under the present coarse description nevertheless have different admissible futures because their retained-dependency histories differ. That is path dependence without requiring metric thresholds or elapsed time. It is not yet memory: memory in the stronger biological sense waits until retained change becomes internally consequential to a self-maintaining system. Relation earns only the possibility that retained history can constrain present organization.

- Persistence of an identity criterion does not require invariant membership. Retained-dependency path dependence is a structural precursor to stronger notions of history and memory without yet supplying physical time.

5.14 Independence Before Dimensionality

Once a domain contains several relations, it is tempting to count independent variations and call the result dimensionality. That would be premature twice

over: cardinal magnitude has not yet been earned internally, and independence need not yet have a vector-space form. Relation can nevertheless ask a weaker structural question: which admissible variations are fixed by the organization of others, and which remain non-redundant under the current constraints?

relation count $\neq$ independence structure $\neq$ physical dimension

The present chapter therefore earns an independence problem, not a numerical relational dimension d_R . A set of variations is structurally non-redundant when no member is fixed by the admissible constraints imposed by the others, under a definition Formalism must make precise. Rank remains only an analogy until appropriate algebra is earned. Matroid theory (Whitney, 1935), which axiomatizes independence without presupposing a vector space, is a natural candidate formalism for later development.

A regulatory network or game-playing agent can contain several non-redundant relational variables without those variables being spatial axes. The later physical question is stronger: do generic recursive relational dynamics select stable collective modes that decouple sufficiently to support effective dimensional geometry? In particular, no orthogonality is assumed. If effective orthogonality appears, it must be earned from stability-selected decoupling or a comparably justified relation among modes.

Independence of relational variation must also remain distinct from the dimensionality of any later embedding space. A system could possess many non-redundant relational modes without each mode becoming a spatial axis. Relation therefore withholds comparisons such as $d_R \leq d_P$ or $d_R > d_P$ until both quantities and their relevant notion of magnitude have actually been earned.

Open question: how should relational independence be defined before vector-space structure is available, and do stable relational dynamics generate persistent approximately decoupled modes without dimensionality being written into the update rules?

5.15 Reference Structure Has Not Yet Been Earned

An integrated relational organization can contain distinctive positions without yet containing an anchor. A distinctive profile says that one position differs from another; it does not establish that any member functions as a reference for the organization as a whole. Relation therefore withholds reference architecture rather than selecting one by convenience.

A later closed organization might support a localized structural reference, a distributed reference carried by several relations, or no privileged internal

reference at all. All three remain downstream possibilities; none is inherited from Ω .

The methodological constraint is stricter than mere usefulness: a reference role may be admitted only if the organization itself makes that role stable and consequential under admissible succession and declared variation. Choosing the member that makes a diagram or coordinate description easiest would add analyst-imposed asymmetry.

Closure is the first chapter capable of testing this stronger possibility because closure can convert an integrated pattern into a persistent higher-order unit. Relation therefore hands forward the problem rather than an answer.

Open question: can internal sufficiency, identity preservation, dependency structure, or representative-independent higher-order addressability make a reference role endogenous rather than stipulated?

Handoff within the derivation. Relation earns integrated organization but no anchor. Closure must determine whether completion can supply an endogenous reference role without undoing the symmetry inherited from Difference through Boundary.

5.16 Worked Example: Three Relational Regimes

A minimal example separates coexistence, connectivity and structure. It is non-geometric; the indices are labels only.

Regime	Relations	Key condition	Interpretation
A. Coexistence	r_{01}, r_{23}	No shared relata; no mutual constraint	Two retained relations coexist but do not form one integrated structure
B. Connectivity	r_{01}, r_{12}	Shared q_1 , but $\mathcal{P}(r_{01} \text{ given } r_{12}) = \mathcal{P}(r_{01})$	A network exists, but shared participation alone does not make the relations mutually constraining
C. Structure	r_{01}, r_{12}, r_{20}	$r_{20} = f(r_{01}, r_{12})$	At least one relation is restricted by the organization of the others; the domain is integrated

Now perturb one relation in Regime C, $r_{01} \mapsto r'_{01}$. Several outcomes are possible. The structure may collapse, revealing that its organization was fragile. It may reorganize into a new structure with a different invariant. Or it may absorb the perturbation while preserving the same identity-relevant invariant, $F(\mathcal{R}') = F(\mathcal{R})$. The third case is the strongest candidate for object-like persistence.

It also supplies an obvious candidate for the computational companion. Construct weighted relational networks, perturb edges or constraints, identify candidate clusters, and measure whether identity-relevant organization survives. The network-robustness literature (Albert, Jeong and Barabási, 2000) and community-detection methods (Newman and Girvan, 2004) offer ready-made instruments, with the usual guardrail. The simulation cannot prove that physical objects arise this way. It can test whether the proposed criterion distinguishes persistent integrated structures from arbitrary collections of relations.

5.17 What Relation Has Not Yet Earned

The discipline of the chapter lies as much in what it refuses to add as in what it adds. Several concepts are near enough to be tempting and still too expensive.

Spatial direction. Different relational positions do not yet define left, right, inward, outward or any directed axis.

Linear order. Two positions can differ without admitting a unique ordering $p_i < p_j$.

Metric distance. No quantity yet measures how far apart two relational positions are.

Orthogonality. Independent relational modes do not yet possess an inner product, and orthogonality must not be assumed as a capacity of the domain.

Physical dimensionality. Relational degrees of freedom are not spatial dimensions.

Metric time. Admissible succession and retained-dependency precedence are not seconds, durations or proper time.

Physical instantiation. The chapter has not shown why stable relational organization acquires the dynamical properties associated with physics.

These deferrals are not omissions to be hidden. They are the boundary conditions that make later claims testable. our framework is stronger if the reader can point to the exact chapter where each additional structure becomes necessary.

5.18 Objections and Replies

Objection 1: Relations require relata, so relation-before-object is incoherent. **Reply:** The objection succeeds if the framework claims that relations exist with literally nothing to occupy a relational position. It does not succeed against the weaker

proposal made here. The q_i are positions sufficient for relational differentiation, not fully formed substances with intrinsic properties. Difference and Distinction already make the primitive carrier and type-promotion costs explicit; the burden here is to show that the relational description does explanatory work beyond renaming a stock of primitive objects. If later chapters require unexplained intrinsic properties for the q_i , relation-before-object will have failed its own test.

Objection 2: A matrix already imports geometry. **Reply:** A matrix imports indexing, not physical geometry. The safeguard is permutation invariance under relabeling (5.2). No row or column is a coordinate direction merely because the relation is written in rectangular notation. The objection would become decisive if later arguments inferred neighborhood, distance, orientation or dimension from matrix position rather than from relational invariants.

Objection 3: Mutual constraint already assumes causation. **Reply:** The chapter uses constraint in a modal sense: the state of the larger organization restricts the admissible possibilities of a local relation. A triangle inequality constrains lengths without causing them; an algebraic relation constrains values without temporal influence. Physical causation is not required for the working definition of structure.

Objection 4: The object-equivalence construction merely redescribes ordinary objects. **Reply:** That risk is real. The construction earns explanatory value only if it generates nontrivial criteria for persistence, predicts when object-like identity fails, or supports computational tests that distinguish stable integrated clusters from arbitrary groupings. If every pre-existing object can simply be relabeled as an equivalence class after the fact, the proposal is decorative rather than explanatory.

Objection 5: Frame-relative equivalence makes reality observer-dependent. **Reply:** No. The framework distinguishes underlying non-identity, identity equivalence $\sim_F$, and frame equivalence $\sim_W$. A resolving frame is a structural criterion of discriminatory access, not necessarily a conscious observer. Failure of W to resolve a distinction is not evidence that the distinction does not exist.

Objection 6: Relational dimensionality is vector-space language in disguise. **Reply:** The objection is correct against any premature use of rank, basis, orthogonality or span as literal ontology. This chapter uses the weaker concept of independent degrees of variation and points at matroid independence as a formalism that does not presuppose a vector space (5.14). Formalism must earn whatever algebra is needed to make the independence structure precise before any numerical dimension is assigned.

Objection 7: Higher-order discernibility assumes a background space in which two objects coexist. **Reply:** It requires only a larger relational frame capable of preserving two non-equivalent profiles. “Coexist” means membership in the same organized domain, not simultaneous occupation of a pre-existing space. Spatial coexistence is one later realization of the more primitive relational condition.

— — — —

Objection 8: Structural persistence presupposes time. **Reply:** The chapter uses preservation across admissible succession and declared diagnostic transformation, not elapsed duration. An index used by the analyst records compositional or derivational order without becoming a clock. If persistence required physical duration at this stage, the project would be circular; the present formulation is designed to avoid that implication.

5.19 What Would Count Against the Chapter

Mutual constraint cannot be defined without presupposing intrinsic objects whose properties do all the explanatory work.

The distinction between a collection of relations and an integrated structure collapses under formalization, so that the proposed criterion adds nothing beyond connectivity.

Structural persistence cannot be specified without a hidden temporal metric or a pre-existing physical substrate.

Relational re-instantiation reduces to an analogy that supplies no generalizable invariant criterion.

Object-like identity requires choices of F and diagnostic variation so free that any grouping can be made persistent by stipulation.

Higher-order discernibility cannot distinguish two internally equivalent structures without importing coordinates or primitive labels.

Multi-relation boundary aggregation requires an uncontrolled new primitive that cannot be reduced to, or constrained by, previously earned operations.

Relational degrees of freedom cannot be defined before metric or vector-space structure without becoming merely verbal.

Computational models show no robust difference between mutually constraining persistent clusters and generic network artifacts under perturbation.

The strongest single failure condition: if integrated structure cannot be specified without importing intrinsic objects, geometry, metric, orientation or an uncontrolled proliferation of new primitives, Relation has not completed its derivation.

5.20 Ontological Defensibility Pulse: Relation and Structure

Pulse question	Applied to Relation
1. Entities required	Retained relational positions q_i and symmetric retained distinctions r_{ij} inherited from Boundary; R is bookkeeping over them. No new substance or reference center.
2. Ontological level	Pre-geometric multi-relation organization, still below physical metric structure and orientation.
3. Lower-order dependencies	Difference and admissible succession; Boundary's retained distinctions, W , $\mathcal{P}$, $<$, F and $\sim_F$. No anchor is inherited.
4. New emergent properties	Relational profile, mutual constraint, structural invariance, object-like identity, higher-order discernibility, relational position and constitutive membership.
5. Claim types	Primarily relational and formal, with interpretive examples and marked provisional extensions.
6. New primitives	None claimed. Membership uses mutual constraint plus metalanguage quantification; diagnostic transformation families remain tests rather than internal laws.
7. Fewer assumptions?	Strongest if integrated structure follows from already-earned retained relations and $\mathcal{P}$ without a center, metric strength, cardinality, or new aggregation operator.
8. Observational constraints	Perturb candidate organizations under preregistered diagnostic families; test whether mutual constraint and identity persistence distinguish them from matched collections without hard-coding the target grouping.

Relation tightens our ontology only if structure can be derived from retained relations and their recursive constraints rather than declared as a new primitive.

5.21 Implications and Handoff

We leave Relation with the first genuinely organized relational field. Its parts can constrain one another, preserve invariants, and support object-like identity without requiring primitive objects.

Yet the organization can still depend on conditions supplied from outside itself. It has structure, but not necessarily self-sufficiency.

Closure changes the perspective from pattern to whole. We ask when the dependencies that keep an organization recognizable become internal enough that the organization can function as one new relatum.

That opens the next questions. Can a structured relational domain close into a higher-order identity? Can that identity retain history? Can distinct relational positions acquire orientation without importing a spatial axis? Can independent relational modes later become metrically resolvable? Can stable dynamics select approximately decoupled modes so that effective orthogonality is earned rather than assumed? Those belong to later chapters. The present chapter stops one step earlier.

A persistent relational structure has now been earned. Geometry has not.

Handoff to Closure. Under what conditions does a structured relational domain become sufficiently complete that its organization can function as a new higher-order identity or origin?

Questions Opened by This Framework

Can mutual constraint be formalized without causal, metric, probabilistic or geometric language?

What is the weakest invariant sufficient for structural persistence under nontrivial transformation?

Can object-like identity be operationalized so that persistence criteria are not chosen after the fact?

What diagnostic transformation families are appropriate at different ontological levels, and what later physical structure, if any, turns a diagnostic regime into a realized one?

Can two internally equivalent object-like structures remain resolvably distinct using only relational profiles to a larger frame?

What minimum reference structure suffices to break exchange symmetry between otherwise equivalent persistent objects?

Can relational position be defined so that it later supports spatial order without presupposing it?

Can cardinal or weighted membership be earned later, and what is the least magnitude structure the framework would need for it?

When does retained-dependency path dependence remain merely structural, and what additional organization would make retained history function as memory?

How should relational independence be defined before vector-space structure has been earned, and does matroid-style independence provide an adequate later formalization?

Do generic recursive relational dynamics generate stable collective modes whose effective cross-coupling decreases under coarse-graining, without those modes being encoded in advance?

If such modes emerge, under what later conditions can their effective independence be represented as orthogonality rather than merely low coupling?

Can a computational perturbation test distinguish integrated relational objects from arbitrary dense subgraphs?

Can Closure earn an endogenous reference role from closed organization without privileging a primitive pole, and under what conditions would that reference be localized or distributed?

What result would show that relation-before-object is explanatory rather than a redescription of an object-first ontology?

Selected References Cited in Relation

Albert, R., Jeong, H., & Barabási, A.-L. (2000). Error and attack tolerance of complex networks. *Nature*, 406, 378–382.

Barbour, J., & Bertotti, B. (1982). Mach's principle and the structure of dynamical theories. *Proceedings of the Royal Society A*, 382(1783), 295–306. doi:10.1098/rspa.1982.0102. A relational dynamics in which position is defined only against other bodies.

Benacerraf, P. (1965). What numbers could not be. *The Philosophical Review*, 74(1), 47–73.

Calvino, I. (1974). *Invisible Cities* (W. Weaver, Trans.). New York: Harcourt Brace Jovanovich. Originally published in 1972 as *Le città invisibili* (Turin: Einaudi). The parable of the bridge and its arch, recalled in Figure 5.2.

Earman, J., & Norton, J. (1987). What price spacetime substantivalism? The hole story. *The British Journal for the Philosophy of Science*, 38(4), 515–525. doi:10.1093/bjps/38.4.515.

Fodor, J. A. (1974). Special sciences (or: The disunity of science as a working hypothesis). *Synthese*, 28(2), 97–115. doi:10.1007/BF00485230.

French, S., & Redhead, M. (1988). Quantum physics and the identity of indiscernibles. *The British Journal for the Philosophy of Science*, 39(2), 233–246.

French, S. (2014). *The Structure of the World: Metaphysics and Representation*. Oxford: Oxford University Press.

Klein, F. (1872). *Vergleichende Betrachtungen über neuere geometrische Forschungen*. Erlangen: Andreas Deichert. Reprinted in *Mathematische Annalen*, 43 (1893), 63–100, doi:10.1007/BF01446615; English translation by M. W. Haskell, “A comparative review of recent researches in geometry,” *Bulletin of the New York Mathematical Society*, 2 (1892–93), 215–249.

Ladyman, J., & Ross, D., with Spurrett, D., & Collier, J. (2007). *Every Thing Must Go: Metaphysics Naturalized*. Oxford: Oxford University Press. Chapter 4, Ontic Structural Realism and the Philosophy of Physics, is the nearest neighbor to this chapter’s account of objecthood.

Newman, M. E. J., & Girvan, M. (2004). Finding and evaluating community structure in networks. *Physical Review E*, 69(2), 026113.

Putnam, H. (1967). Psychological predicates. In W. H. Capitan & D. D. Merrill (eds.), *Art, Mind, and Religion*, pp. 37–48. Pittsburgh: University of Pittsburgh Press.

Rovelli, C. (1996). Relational quantum mechanics. *International Journal of Theoretical Physics*, 35(8), 1637–1678. doi:10.1007/BF02302261. For states defined relative to other systems rather than absolutely.

Weyl, H. (1952). *Symmetry*. Princeton: Princeton University Press.

Whitney, H. (1935). On the abstract properties of linear dependence. *American Journal of Mathematics*, 57(3), 509–533. doi:10.2307/2371182.

Note on these references. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 6

Closure: When Completion Becomes a New Origin

Claim ~ Closure occurs when the relations required to preserve a higher-order organization become internally sufficient as a domain, and that sufficiency remains available across the transformations by which the organization persists. A closed organization can then become a new relatum for higher-order relational construction.

Chapter discipline. This chapter inherits what Relation earned: mutual constraint, structural invariance, criterion-based identity $\sim_F$, $\mathcal{P}$ and $\prec$, and the separation of resolving frames W from identity criteria F . Its burden is to show what completion can mean with that inheritance alone, and whether closure itself can earn the first endogenous reference role.

■ retained distinction $\rightsquigarrow$ mutual constraint $\rightsquigarrow$ invariant organization $\rightsquigarrow$ closure $\rightsquigarrow$ higher-order addressability

6.1 Where Relation Leaves Us

Relation gave us patterns that can persist. Closure asks us to change scale of view. Instead of inspecting each dependency separately, we ask when the network of dependencies becomes sufficient to hold a higher-order identity together.

The visual temptation is immediate: a loop, shell, or enclosed region. We cannot use that picture yet. Nothing spatial has been earned.

So we look for a non-geometric threshold. When do the relations required to preserve an organization come from within that organization itself?

The chapter's foundational question is therefore not "what shape closes?" but:

When do the dependencies required for a persistent relational organization become sufficiently internal to that organization that the organization can function as a higher-order relatum?

This phrasing changes the burden. We do not begin from a triangle, simplex, tetrahedron, K4, or a target dimensionality. Those may become useful later mathematical realizations. They cannot define primitive closure without inserting geometric structure the book is trying to earn.

6.2 What Closure Can Mean Before Geometry

Ordinary language makes closure sound spatial. A door closes, a curve closes, a membrane encloses, a surface separates an interior from an exterior. None of those senses is primitive here. No coordinate chart, metric, adjacency relation, angle, volume, or spatial side has yet been derived.

The first definition must therefore be relational. Let $\mathcal{R}$ be a relational domain whose constituent relations mutually constrain one another. Let F denote an organization-level invariant of the kind introduced in 5.6. F need not yet be a number. It is whatever relational organization must survive for the domain to remain the same higher-order structure under the transformations presently admitted.

Working definition. A relational domain $\mathcal{R}$ is structurally closed with respect to F when every dependency constitutively required to maintain F is supplied within $\mathcal{R}$, except for inputs explicitly classified as non-constitutive conditions rather than parts of F itself.

The qualification matters. Closure is not absolute independence. A later physical or biological system can exchange material, energy or information with an environment while retaining an internally organized identity. Theoretical biology makes this distinction explicitly: Montévil and Mossio characterize biological organization through mutually dependent constraints while simultaneously treating organisms as thermodynamically open systems (Montévil and Mossio, 2015). Their proposal operates at a much richer physical and biological level than this chapter. It supplies a useful warning: organizational closure and environmental isolation are not the same claim.

■ closure with respect to $F \neq$ isolation from all external relation

At this stage, “internal” and “external” are not spatial words. A dependency is internal when it belongs to the relational organization whose persistence constitutes F . A dependency is external when the organization requires it but it does not participate in that organization. Spatial interior and exterior remain unearned.

6.3 Closure Is a Predicate, Not a New Primitive Operation

The project’s parsimony rule forbids solving the closure problem by introducing an unexplained operator whose output is simply “closed.” The cleanest notation is therefore predicative rather than generative:

■ $\text{Closed}_F(\mathcal{R}) = \text{true or false}$

This notation says that $\mathcal{R}$ satisfies a stated closure criterion relative to F . It does not add a process called Closed_F to our ontology. In particular, it must not be confused with the mathematical notion of a closure operator. In standard mathematics, closure operators are typically extensive, monotone and idempotent. Closed elements are fixed points of the relevant operator. That formal family is useful as an analogy for completion. Closure needs no new operator C with $C(\mathcal{R})=\mathcal{R}$.

The same discipline applies to $\mathcal{U}$. Distinction typed $\mathcal{U}$ fundamentally as an admissible transition relation on configurations. Later domains may admit branching, so Closure must not silently replace that relation by a globally single-valued update map:

$$\blacksquare (\Sigma_n, \Sigma_{n+1}) \in \mathcal{U}$$

Closure may be preserved or destroyed along admissible succession under $\mathcal{U}$, but closure is not another meaning of $\mathcal{U}$. Nor should $\mathcal{U}$ be stretched into a Boolean, membership verdict, or aggregation operation. The transition relation constrains what may succeed what; the closure predicate describes a property some configurations and admissible trajectories possess.

$$\blacksquare \text{admissible succession under } \mathcal{U} \neq \text{logical verdict} \neq \text{closure predicate}$$

This distinction becomes important again when boundary aggregation is revisited in 6.9.

6.4 The Minimal Closure Test

A usable definition needs to distinguish genuine closure from connectivity, cycles and arbitrary observer-selected groupings. The test proposed here for structural closure has three parts. None is introduced as an independent primitive; each is a condition imposed on structures and machinery already available.

Internal sufficiency. Every dependency constitutively required to maintain F is supplied within the candidate domain, or else the domain is not closed with respect to F .

Constraint participation. The relations classified as constitutive of F must actually participate in the organization that maintains F . Merely listing unrelated retained relations inside the same set is insufficient. Participation is always judged at a declared resolution: a relation whose removal changes nothing a frame W can resolve has not thereby been shown to be idle, since its contribution may be derived through other relations or may lie below what W resolves.

Consistent realizability. The mutually constraining requirements must admit at least one relational configuration. Circular equations with no jointly admissible state do not constitute closure.

■ $\text{Closed}_F(\mathcal{R}) \Rightarrow \text{Sufficiency}_F \wedge \text{Participation}_F \wedge \text{Realizability}_F$

These three are conditions on a relational state. They define structural closure, which is a snapshot property. Persistence across change is a further and separate requirement. It is what distinguishes dynamic closure (6.7) and robust closure (6.8) from structural closure. It is the property the higher-order work of 6.12 actually needs. An instantaneous coincidence can be structurally closed without being able to do that work. The worked example of 6.18 keeps the two apart for that reason.

The implication is deliberately one-way. Formalism may later discover that some conditions are redundant, or that stronger necessary-and-sufficient conditions can replace them. Closure's task is to expose the burden, not pretend the final theorem already exists.

■ Connectivity and circularity are insufficient for closure. Open question: whether the three-part test can be reduced further, and whether each clause can be expressed using one common formal object in Formalism.




Figure 6.1. Connected is not closed. Closure depends on where dependencies end, not on how the members are linked.

6.5 Internal Sufficiency Without Absolute Self-Sufficiency

The most dangerous phrase in our definition is “internally sufficient.” Taken too strongly, it would exclude every system that depends on an environment. Taken too weakly, it would permit any externally scaffolded collection to call itself closed.

The distinction should therefore be made at the level of constitutive dependency. Suppose $\mathcal{R}$ requires an input x from outside the candidate domain. Two cases differ.

If x supplies a condition under which the organization operates but does not itself determine the organization that constitutes F , x may be an environmental input without defeating closure with respect to F .

If x supplies one of the dependencies without which the identity-relevant organization F is not specified or maintained, the candidate domain is not closed with respect to F unless x is included in the domain.

This is analogous, but not identical, to the distinction made in the theory of reflexively autocatalytic and food-generated (RAF) sets (Hordijk, Steel and Kauffman, 2019). An RAF set can be self-sustaining with respect to its internal catalytic organization while still depending on an ambient food set. RAF theory therefore supplies a useful counterexample to the idea that closure means total external independence. It also supplies a second warning: RAF closure does not automatically include a boundary. Hordijk and Steel explicitly note that boundary is not part of the basic RAF formalism and must be added or modeled separately (Hordijk and Steel, 2015).

The lesson for this framework is precise: internal organizational sufficiency does not entail environmental isolation. Network self-support does not by itself entail boundary.

6.6 Dependency Closure and Consistent Realizability

A simple cycle is not enough. Let three relations be represented as r_{ab} , r_{bc} and r_{ca} . A graph can contain the cycle

$$\blacksquare r_{ab} < r_{bc} < r_{ca} < r_{ab}$$

Here $<$ is the retained-dependency relation inherited from Boundary, applied to constitutive dependencies among retained relations; the cycle is not orientational and therefore does not use $<_{\circ}$. While one of the relations still depends constitutively on an unspecified external condition x :

$$\blacksquare r_{ca} = f(r_{ab}, r_{bc}, x), x \notin \mathcal{R}$$

The representational graph closes, but the identity-relevant dependency does not. Conversely, three mutually specified equations can be syntactically circular yet inconsistent. If no relational configuration satisfies them simultaneously, no realized organization exists to be closed.

Let $\mathcal{S}_F(\mathcal{R})$ denote the set of configurations of $\mathcal{R}$ that satisfy the constraints constitutive of F . A necessary realizability condition is simply:

$$\blacksquare \mathcal{S}_F(\mathcal{R}) \neq \emptyset$$

This notation carries no metric, probability measure or state-space geometry. It means only that the stated constraints are jointly satisfiable. For a configuration that actually obtains, the condition is met automatically. It has force when a proposed specification of F , or a model of it, is being tested, since a specification that no configuration can satisfy describes no organization at all.

Robert Rosen's work on closure to efficient causation provides a useful higher-level analogue (Rosen, 1991). In the biological setting, closure concerns whether the productive causes required by the organization are themselves entailed within the organization rather than supplied indefinitely from outside. Later formal work has sought computable realizations of this idea (Cárdenas et al., 2010). The present chapter does not import Rosen's causal vocabulary into the prephysical ontology. It borrows only the structural question: where do the dependencies required by the organization come from?

6.7 Structural Closure and Dynamic Closure

The distinction between structural and dynamic closure separates a snapshot property from a trajectory property. A configuration can be structurally closed at one derivational state and fail immediately under the next update. That is too weak to ground persistent higher-order identity.

Let $\mathcal{C}F$ denote the class of relational configurations satisfying the structural closure conditions for F . Admissible succession under $\mathcal{U}$ then permits a stronger question along a realized or selected trajectory:

$$\blacksquare \Sigma_n \in \mathcal{C}F \text{ and } (\Sigma_n, \Sigma_{n+1}) \in \mathcal{U} \Rightarrow \Sigma_{n+1} \in \mathcal{C}F$$

When the implication holds across the relevant admissible succession, closure is dynamically preserved along that trajectory. Dynamic closure therefore does not redefine $\mathcal{U}$. It is a property of a sequence of configurations licensed by $\mathcal{U}$. A

stronger requirement over every admissible successor would be a robustness or invariant-set condition and should be stated separately.

This is where the persistence requirement belongs. A structurally closed state that fails at the next update has satisfied the three conditions of 6.4 and no more. Persistence is preserving those three under $\mathcal{U}$.

Working distinction. Structural closure is internal sufficiency of an identity-relevant organization at a relational state. Dynamic closure is the preservation or recurrent recovery of that sufficiency under the system's endogenous state-to-state updates.

■ structural closure + preservation under $\mathcal{U} \rightsquigarrow$ dynamic closure

This brings the chapter close to dynamical-systems language without yet importing its full apparatus. Fixed points, invariant sets, limit cycles, basins and stability spectra belong in Formalism. Here the important idea is more primitive. A closure that performs ontological work must survive some transformation rather than exist only as a static coincidence.

■ Closure can be tested against $\mathcal{U}$ without making closure another operation of $\mathcal{U}$. Open question: whether dynamically persistent closures arise generically under admissible update rules or only under rules designed to produce them.

6.8 Perturbation and the Admissible Transformation Class

Endogenous persistence is not the same as robustness. A structure may remain closed along the one trajectory it happens to follow while collapsing under the slightest alternative perturbation. Boundary introduced a diagnostic transformation family distinct from internal succession, and Relation specialized it for organization-level invariance. Closure can now sharpen that same methodological role rather than introduce another transformation primitive.

$\mathcal{U}$ and the diagnostic family $\mathfrak{IC}$ should remain distinct. $\mathcal{U}$ belongs to the modeled succession structure. $\mathfrak{IC}$ is a declared robustness test, chosen before the closure result is inspected. A candidate transformation belongs to $\mathfrak{IC}$ only if it can be described using structures already earned at this ontological level and does not insert the very property being tested.

At minimum, a defensible perturbation class should satisfy four constraints:

Type preservation. The transformation maps admissible relational configurations to admissible relational configurations. It does not add coordinates, metric, physical time or other later structure.

Nontriviality. $\mathfrak{I}C$ contains at least one transformation other than identity or pure relabeling.

Pre-specification. The class is stated before the closure result is inspected, preventing F and $\mathfrak{I}C$ from being tuned after the fact to protect any desired grouping.

Relevance. The transformations challenge relations that plausibly matter to the candidate organization rather than only changing inert labels.

Examples at the present level include permutation of labels, deletion or substitution of a retained relation, replacement of one lower-order realization by another relation-preserving realization. Alternative state updates that remain within the permitted relational formalism.

A closure robust across $\mathfrak{I}C$ is stronger than one preserved only by its actual admissible trajectory. Dynamic persistence asks what occurs along succession; robustness asks which declared variations preserve the organization.

6.9 Higher-Order Membership Without a New Primitive

Relation (5.12) already showed that higher-order membership can be stated through a shared structural participation criterion without a primitive aggregation operator. Closure does not reopen that question. What it adds is a stronger source for membership: participation in the dependency structure constitutive of F .

- No independent aggregation primitive is required for closure membership. Cardinal and weighted membership await machinery that can justify magnitude or valuation over relations.

6.10 Closure and Boundary Become Reciprocal

Boundary introduced boundary as preserved non-equivalence before there was an inside or outside. Relation generalized membership to multi-relation domains. Closure now gives higher-order membership a stronger basis.

A relation belongs to a closed organization when it participates in the dependency structure constitutive of F . The boundary can therefore be read as the distinction between relations whose participation is required for that closure and relations that are not constitutive of it.

- inside_F = participation in the F -maintaining closure
- outside_F = non-participation in that closure

Our result is nevertheless stronger than Boundary's pairwise separability. A higher-order organization can now carry an internally defined membership structure.

Closure and boundary therefore constrain one another. Boundary states which relations count as participating in the organization. Closure states why those relations count together as one organization. Neither needs to be primitive if both can be recovered from the same persistent constraint organization.

The biological closure-of-constraints literature again provides a useful analogue rather than evidence. Montévil and Mossio argue that organizational closure can help mark boundaries between interacting biological systems. Hordijk and Steel show the complementary point that a self-sustaining network formalism need not contain a boundary unless boundary relations are represented. Together, those cases warn against assuming either direction of implication without specifying the mechanism.

6.11 Overlapping Closure and Non-Exclusive Membership

Closure does not require reality to partition into mutually exclusive containers. A retained relation can participate in more than one persistent organization if it contributes to distinct identity-relevant invariants.

■ $r_i \in \mathcal{R}_A$ and $r_i \in \mathcal{R}_B$

provided the two closures are defined by different but compatible relational organizations F_A and F_B . Nothing in the pre-geometric ontology requires $\mathcal{R}_A \cap \mathcal{R}_B = \emptyset$.

This matters because recursive emergence is more likely to be heterarchical than a perfectly nested tree. Later biological and social systems plainly exhibit overlapping organization. The present result is structural rather than empirical: the closure definition itself contains no exclusivity axiom.

Overlap raises a real pressure point. If two closures demand incompatible states of the same relation, the relation cannot satisfy both simultaneously without additional machinery. Such conflict may require retained-dependency precedence, alternation, contextual resolution or a later reconciliation formalism. Closure should not solve that problem by assuming a global arbitration rule.

■ Closure need not imply exclusive membership. Open question: what formal conditions permit compatible overlap, and what happens when two candidate closures impose contradictory constraints on a shared relation.

6.12 How Closure Creates Higher-Order Relational Addressability

The chapter's most consequential claim is not merely that a network becomes self-contained. It is that a sufficiently stable closure can become a new relatum at a higher organizational level. That transition requires more than naming a cluster. It requires external relations to act consistently on the organization despite variation among its lower-order realizations.

Relation represented an object-like identity as an equivalence class of configurations that preserve an invariant F :

$$\blacksquare O_F = [\Sigma]_{\sim_F}$$

Let E denote some relation or transformation coupling this organization to a larger relational domain. E is well-defined at the higher-order level only if its result does not depend on which lower-order representative of O_F happens to realize the organization. Formally, if

$$\blacksquare \Sigma_a \sim_F \Sigma_b$$

then the higher-order action is well-defined when

$$\blacksquare E(\Sigma_a) \sim_{F'} E(\Sigma_b)$$

for the equivalence relevant to the resulting organization. When this condition holds, the larger domain can relate to O_F without tracking every microconfiguration separately. We can define the higher-order action by representative:

$$\blacksquare \tilde{E}([\Sigma]_{\sim_F}) = [E(\Sigma)]_{\sim_{F'}}$$

because every representative yields the same higher-order result class.

This is the exact mechanism by which closure can grant higher-order addressability. The lower-order multiplicity does not disappear. It becomes irrelevant to a specified class of external relations because those relations factor through the invariant organization.

$$\blacksquare \text{many lower-order realizations} \rightsquigarrow \text{one stable higher-order relational address}$$

The construction is analogous to a standard quotient construction in mathematics. An operation descends to equivalence classes only when it respects the equivalence relation. Here the analogy earns a precise criterion rather than merely a metaphor. The closest precedent in the study of dynamics is lumpability. A Markov chain is lumpable with respect to a partition of its states exactly when the coarse-grained process is itself well defined, whichever member of a block the system occupies (Kemeny and Snell, 1960). The

condition above is the same demand made of a relation rather than a stochastic process.

At this prephysical stage it is safer to call this relational addressability rather than causal addressability. If later chapters derive physical causal structure, the same criterion may support a stronger causal reading.




Figure 6.2. Addressable as one. A closed organization can be treated as a single thing by a relation whose result does not depend on which lower-order realization is present. A concert contract with an orchestra is fulfilled whether Ana or Ben plays first violin, so it addresses the orchestra; a recording deal for Ana's sound is not, so it addresses Ana. Addressability is always relative to the relation.

6.13 When Closure Earns Endogenous Reference

Boundary withheld an anchor because no privileged pole had been earned, and Relation produced integrated organization without selecting a center. Closure now supplies the first structure capable of functioning as a reference without importing one from Origin. A dynamically persistent closed identity $O_F = [\Sigma] \sim_F$ becomes reference-capable when a declared class of higher-order relations acts consistently on O_F across its lower-order realizations, as established by the addressability criterion of 6.12.

■ $\text{Closed}_F(\mathcal{R}) + \text{dynamic persistence} + \text{representative-independent addressability} \rightsquigarrow \text{endogenous reference}$

Definition — organizational anchor. Write A_F for a closed identity O_F when it is functioning in this earned reference role: subsequent higher-order distinctions can be specified relative to O_F without selecting an arbitrary lower-order representative. A_F is therefore not an additional entity and not a privileged internal member. It names a role of the already-earned closed equivalence class.

This earns a minimal endogenous reference while preserving foundational symmetry. The reference belongs first to the organization as a whole. Some later structures may localize that role in a distinctive constituent; others may distribute it across several relations. Closure does not need to decide that stronger question in order to earn the weaker organizational anchor required downstream.

A new origin is therefore a re-instantiated reference role, not a transmitted primitive center. Once A_F can enter further relational construction as one addressable relatum, a new organizational level may begin: $\mathcal{R}^{(n)} \rightsquigarrow O_F^{(n+1)} \equiv A_F^{(n+1)} \rightsquigarrow \mathcal{R}^{(n+1)}$. The superscripts mark organizational level, not spatial scale or elapsed time.

■ Closure plus dynamically preserved identity and representative-independent higher-order addressability is sufficient to earn an organizational reference role without privileging a primitive pole. Whether every closed organization yields a unique anchor, and what additional conditions localize or distribute that reference architecture, remains a problem for later formal development.




Figure 6.3. The first reference point is a role of the whole. A closed identity that persists, and can be addressed whichever realization is present, can serve as the reference for what comes next. "20 km from Paris" refers to the city as a whole, not to any building, and stays true while buildings change; only later did a convention pin French road distances to Point zéro, a plaque in front of Notre-Dame.

6.14 Ontic Closure and Frame-Mediated Identification

A further distinction is required because any closure we describe is accessed through some resolving or analytic procedure. That epistemic fact must not be mistaken for the ontological claim that a conscious observer creates the closure.

Let F_{dyn} denote the organization actually preserved by the relational succession, insofar as such an invariant can be derived. Let W be an external resolving frame in Boundary's sense. The frame has access only to the distinctions its criterion preserves, from which an investigator may construct or infer a candidate identity criterion F_{obs} . In general:

■ F_{obs} need not equal F_{dyn}

A resolving procedure or investigator can miss a real closure, merge distinct closures, or treat an accidental regularity as identity-relevant. We therefore need a way to constrain F_{dyn} independently of retrospective description.

A candidate invariant should earn ontic status only if it does explanatory work under intervention or continuation. Perturbing relations constitutive of the candidate changes whether the organization persists. At the same time, changes outside that constitutive set do not have the same consequence. In computational work this can be tested by preregistered ablations and perturbations rather than by choosing F after our result is known.

■ ontic closure $\neq$ frame-mediated identification of closure

This distinction lets Volume I remain pre-conscious. Objects and closed structures need not wait for a mind to recognize them. What is frame-mediated is our access to, and encoding of, their closure; W does not become constitutive of F merely because an investigator uses it to detect F .

6.15 When Identification Becomes Internal

There is nevertheless a later transition in which the distinction between ontic closure and identified closure becomes internal to a system. A system may first preserve its organization without representing that organization. Later, a sufficiently complex system may contain a resolving process that maps aspects of its own state into an internal model:

■ $W_s(\mathcal{R}_s) \mapsto \sigma_s$

where σ_s is a self-model, the symbol the notation table reserves for it. If σ_s represents conditions relevant to the persistence of the same system, closure has become internally represented rather than merely externally identified. That is a qualitatively new level, but it should not be equated immediately with self-consciousness.

■ self-maintenance $\neq$ self-discrimination $\neq$ self-model $\neq$ recursive self-consciousness

Volume II will ask what additional organization is required for retained distinctions to become distinctions for a system, and later, when a system can represent itself as the bearer of those encodings. Closure needs only the negative boundary condition: no self-model is required for ontic closure.

(forward pointer to Volume II) Closure can exist before it is represented. Its identification is initially external to the closed domain; reflexive cognition begins only when the domain can internally represent and evaluate conditions of its own persistence. Whether that is sufficient for phenomenal self-consciousness remains open.

6.16 Stability Without Rigidity

A closed organization that cannot vary would be a poor precursor to memory, orientation, return or dynamics. Closure must therefore preserve identity without requiring every constitutive relation to remain fixed.

Let V_F denote the set of admissible variations that preserve F . A dynamically useful closure requires:

■ $V_F \neq \emptyset$

and should include at least one non-identity transformation. At the same time, not every variation can be admitted, or F ceases to distinguish the organization from arbitrary alternatives. The resulting principle is qualitative but important: persistent higher-order identity requires constrained freedom, not maximal constraint.

Montévil and Mossio's closure-of-constraints framework reaches a related conclusion in a biological context by treating stability and variation as complementary rather than opposed. The present framework borrows only that structural lesson. It does not import biological function, metabolism or thermodynamic timescales into Closure.

The computational question is sharper: across candidate update rules, do organizations with internally completed dependencies occupy more robust regions of relational state space than equally connected but externally dependent controls? That is a testable claim about our model, not yet a claim about nature.

6.17 Computational Diagnostics of Closure

A conceptual definition becomes more useful when it can constrain a computational test. The computational companion can operationalize closure without promoting its readouts into ontology. This distinction is essential: an external simulation may count nodes, edges, failures and trials even when cardinality has not yet been derived as an internal primitive of the modeled world.

Four diagnostics are natural.

Diagnostic	Computational readout	What it tests	What it does not establish
Dependency leakage	Number or fraction of F-maintaining dependencies that terminate outside the candidate domain	Internal sufficiency	That numerical ratio is fundamental ontology
Constraint participation	Ablation sensitivity of candidate constitutive relations compared with non-constitutive controls	Whether listed relations actually matter to persistence	That all causal structure has been derived
Closure robustness	Fraction of preregistered perturbations in $\mathfrak{I}C$ after which Closed_F remains true	Persistence beyond one trajectory	That nature selects the tested rule
Higher-order addressability	Agreement of macro-outcomes across distinct microstates in the same F-equivalence class under the same external coupling	Whether an external relation descends consistently to the higher-order unit	That the higher-order relation is yet physical causation

A fifth diagnostic can compare candidate closures against matched random, merely connected, or equally dense control subgraphs. The key question is whether the closure criterion identifies a nontrivial class whose persistence and higher-order addressability exceed those controls without having the target grouping supplied in advance. The strongest simulation guardrail remains the same as elsewhere in the project. If closure appears only because the target boundary or topology is hard-coded, closure has not been generated.

6.18 Worked Example: Four Relational Regimes

A minimal example separates connectivity, circularity, structural closure and robust dynamic closure without introducing geometry.

Regime	Relational condition	Interpretation
A. Connectivity	r_{ab} and r_{bc} share a relatum, but each remains independently admissible	A network exists; no integrated closure
B. Circular dependence	r_{ab} , r_{bc} , r_{ca} form a cycle, but r_{ca} also requires external x constitutively	The graph cycles; dependency closure fails
C. Structural closure	All F-maintaining dependencies are internal and jointly realizable	Closed at the current relational state
D. Robust dynamic closure	Regime C persists or recovers F under $\mathcal{W}$ and across a preregistered nontrivial subset of $\mathfrak{I}C$	Strong candidate for a higher-order persistent identity

Now suppose Regime D contains two lower-order configurations Σ_a and Σ_b satisfying $\Sigma_a \sim_F \Sigma_b$. A larger-domain relation E acts on each. If

■ $E(\Sigma_a) \sim_{F'} E(\Sigma_b)$

then the larger domain can treat both as one higher-order O_F for purposes of E. If the results fall into different higher-order classes, the proposed macro-object is not addressable under that coupling. The grouping must be refined or abandoned.

This example supplies an explicit failure mode. Higher-order unity is earned relation by relation. It is not guaranteed merely because an analyst can draw a boundary around a cluster.

6.19 Objections and Replies

Objection 1: Closure is circular by definition. **Reply:** Only if the definition says that a system is closed when it is closed. The proposed test instead decomposes structural closure into internal sufficiency, participation and realizability, and adds persistence under update for dynamic closure. Circular dependency may occur inside that test, but a syntactic cycle alone does not satisfy it.

— — — — —

Objection 2: “Internal sufficiency” makes every open system fail. **Reply:** No. Closure is indexed to the organization F. External inputs are compatible with closure when they are enabling conditions rather than constitutive dependencies of F. If an allegedly external input is necessary to specify the identity-maintaining organization itself, the candidate boundary was drawn too narrowly.

— — — — —

Objection 3: The invariant F is chosen by the analyst, so objecthood remains arbitrary. **Reply:** That is a real risk, not a solved problem. The chapter constrains F by requiring preregistered perturbation and continuation tests. F_{obs} is an external representation; F_{dyn} is the candidate organization whose disruption actually changes persistence and higher-order addressability. If no structure-independent-of-description can constrain F, the ontology reduces to descriptive coarse-graining.

— — — — —

Objection 4: Dynamic closure smuggles closure into $\mathcal{U}$. **Reply:** No. $\mathcal{U}$ retains its state-to-state type. Dynamic closure is a predicate on trajectories generated by $\mathcal{U}$. The distinction is exactly parallel to saying that a dynamical map generates trajectories while stability is a property of some trajectories.

— — — — —

Objection 5: Higher-order membership still needs a new aggregation primitive.

Reply: It does not at the level earned here. Section 5.12 defines participation through mutual constraint, and ordinary quantification over participating relations remains metalanguage. Threshold, majority and weighted membership remain deferred because they require additional magnitude or valuation structure.

Objection 6: Closure has already become memory. **Reply:** Not yet. A closure can preserve the same organization under update while erasing the particular path by which it arrived there. Memory begins when retained history changes present or future relational possibilities in a way not reducible to current closure alone. That is path dependence; memory in the full sense waits for Memory, once retained change can matter to a self-maintaining system.

Objection 7: Higher-order addressability is only an analyst's convenience. **Reply:** It is merely convenient if external relations do not respect the proposed equivalence class. It becomes formally non-arbitrary when the same higher-order relation is well-defined across distinct lower-order realizations. The quotient criterion in 6.12 states exactly what must hold.

Objection 8: Overlapping closures make identity indeterminate. **Reply:** Overlap makes identity relational and level-relative, not automatically indeterminate. A relation can participate in more than one compatible organization. Incompatible demands on shared relations are a separate open problem and cannot be solved by assuming exclusive partition.

Objection 9: Calling a closure a new origin quietly replaces Ω . **Reply:** No. Ω is not inherited as an anchor in this derivation. Higher-order originhood means that a closed identity has earned a new organizational reference role through persistent addressability. That role is re-instantiated at a higher level; it is not a relocated primitive center.

Objection 10: Frame-mediated identification reintroduces consciousness into Volume I. **Reply:** No. W is a structural resolving criterion, not necessarily a conscious observer. Separating ontic closure from its external identification prevents consciousness from doing ontological work here. Internal self-representation remains deferred to Volume II.

6.20 What Closure Has Not Yet Earned

Spatial enclosure. Relational inside and outside are membership in closure, not a geometric interior or exterior.

Metric distance. Closure supplies no interval, norm, separation magnitude or nearest-neighbor geometry.

Physical dimensionality. Recursive higher-order units do not yet imply spatial axes or a 3+1 regime.

Orientation. A closed organization need not have a directed internal order. Orientation carries that burden.

Metric time. Dynamic closure is preservation across ordered update, not duration in seconds or proper time.

Threshold aggregation. Cardinality-based, majority and weighted membership rules remain Deferred.

Self-consciousness. Ontic closure and even self-maintenance do not entail an internal self-model, much less phenomenal awareness.

Physical causation. Relational addressability may later support causal coarse-graining, but causal structure has not yet been derived.

Physical instantiation. The chapter has not shown why closed relational organization acquires the dynamics identified with physics.

Geometry from closure. The chapter defines closure without geometry; it does not yet show that repeated closure generates geometry.

The refusal to claim these results is part of the derivation. Closure is useful only if it adds one identifiable layer without borrowing from later ones.

6.21 Ontological Defensibility Pulse: Relational Closure

Pulse question	Applied to Closure
1. Entities required	No new substance: retained relations, domains, F and $\sim_F$, $\mathcal{U}$, $\mathcal{P}$, $<$ and diagnostic families are inherited. A_F names a role of an already-earned closed identity, not a new entity.
2. Ontological level	Pre-geometric higher-order organization: the transition from persistent structure to closed, relationally addressable, reference-bearing identity.

Pulse question	Applied to Closure
3. Lower-order dependencies	Retained distinction, mutual constraint, criterion-based identity, admissible succession, structural persistence and higher-order addressability.
4. New emergent properties	Internal dependency sufficiency, dynamic closure, representative-independent addressability, higher-order originhood and endogenous organizational reference.
5. Claim types	Formal and relational, with interpretive analogies and marked open questions about localization or distribution of the earned reference role.
6. New primitives	Ideally none. Closed_F is a predicate, not an operator; $\mathcal{U}$ retains its relational type; A_F labels the reference role of O_F rather than adding a privileged pole.
7. Fewer assumptions?	Strengthens if F is constrained by succession and preregistered tests, closure arises without target topology, and reference follows from addressability rather than stipulated centrality.
8. Observational constraints	Perturb candidate domains; measure dependency leakage and representative-independent addressability against controls; test whether closures and their reference-bearing role persist without being encoded in advance.

Closure tightens the ontology only if closure and the resulting organizational reference role emerge from already-earned relational organization. If we must insert a special closure mechanism, a target topology, a privileged center, or an analyst-selected invariant that cannot be independently constrained, the derivation has not completed its burden.

6.22 Implications and Handoff

Closure changes our ontology's resolution. What appeared as many mutually constraining relations can now be addressed, under the right conditions, as one higher-order identity.

The lower-order structure has not disappeared. We have simply gained a new perspective from which the whole can enter later relations as a unit.

But this new whole still has no intrinsic arrow. Closure has earned a reference-bearing organizational identity, not directional roles within its relations. Orientation asks when persistent consequential asymmetry is sufficient for such roles to cease being exchangeable.

This is the sense in which completion becomes a new origin. The organization does not become ontologically simple; it becomes available as one new starting unit for further relational building.

Three distinctions should carry forward:

Closure itself is not the same thing as an external resolving frame identifying closure.

An organizational anchor is not the same thing as a privileged internal member or geometric center.

Persistence of closure is not yet memory of the path through which the closure was produced.

The last distinction is deliberately left unresolved. Closure does not require a closed organization to encode the sequence by which it was produced. As a result, different generative paths may yield the same higher-order identity. Whether relational dependency later acquires path-sensitive, temporal or memory-like significance is deferred until we have earned the structures needed to tell those apart. Path dependence in the formal chapters, time in Time. Memory in Memory, once a self-maintaining system exists for which retained change can matter.

■ closure ↔ higher-order identity ↔ endogenous reference ↔ orientation

Handoff to Orientation. A closed organization can now function as one reference-bearing relatum, but nothing yet gives its internal relational roles a direction. Under what additional condition can persistent asymmetry become orientational rather than merely a difference in profile or dependency?

A whole organization can now enter later relations as one thing and serve as an earned reference.

Questions Opened by This Framework

Can the three-part Minimal Closure Test be reduced to a smaller necessary-and-sufficient formal criterion?

Can the identity-relevant invariant F be derived from relational succession and constraint rather than selected by an analyst after the fact?

What precise distinction separates a constitutive dependency from a merely enabling environmental input?

Under what update rules does structural closure become dynamically persistent without closure being hard-coded into $\mathcal{U}$?

What is the weakest preregistered diagnostic family $\mathfrak{C}$ that makes robustness nontrivial without importing metric perturbation size?

Can a closure be dynamically persistent but not robust, and if so, what ontological status should such a fragile identity have?

What formal conditions allow two closures to overlap compatibly, and what resolves incompatible constraints on shared relations?

Can higher-order relational addressability be generalized so that multiple external relations descend consistently to the same equivalence class?

When does relational addressability warrant the stronger language of causal autonomy or causal emergence?

Under what additional conditions does the organizational anchor earned by closure become localized in a constituent, distributed across a subset, or remain a property of the whole equivalence class?

How should an external resolving frame W support inference of F_{dyn} without mistaking a coarse-grained regularity for ontic closure?

What additional structure is required for a closed system to form an internal representation of its own persistence conditions?

Can cardinal or weighted membership eventually be derived from earned magnitude and valuation rather than introduced by convention?

Do generic relational update rules spontaneously generate closed organizations more often than matched random controls, or is an explicit stability-selection mechanism required?

Can repeated higher-order closure generate stable relational modes from which position, metric separation and effective dimensionality can later be derived without being inserted?

Selected References Cited in Closure

Cárdenas, M. L., Letelier, J.-C., Gutierrez, C., Cornish-Bowden, A., & Soto-Andrade, J. (2010). Closure to efficient causation, computability and artificial life. *Journal of Theoretical Biology*, 263(1), 79–92. <https://doi.org/10.1016/j.jtbi.2009.11.010>. Published online as an article in press in 2009.

Hordijk, W., & Steel, M. (2015). Autocatalytic sets and boundaries. *Journal of Systems Chemistry*, 6, 1. <https://doi.org/10.1186/s13322-014-0006-2>

Kemeny, J. G., & Snell, J. L. (1960). *Finite Markov Chains*. The University Series in Undergraduate Mathematics. Princeton: D. Van Nostrand. Reissued by Springer (1976) in Undergraduate Texts in Mathematics.

Montévil, M., & Mossio, M. (2015). Biological organisation as closure of constraints. *Journal of Theoretical Biology*, 372, 179–191. <https://doi.org/10.1016/j.jtbi.2015.02.029>

Rosen, R. (1991). *Life Itself: A Comprehensive Inquiry into the Nature, Origin, and Fabrication of Life*. Complexity in Ecological Systems series. New York: Columbia University Press.

Steel, M., Hordijk, W., & Xavier, J. C. (2019). Autocatalytic networks in biology: structural theory and algorithms. *Journal of the Royal Society Interface*, 16(151), 20180808. <https://doi.org/10.1098/rsif.2018.0808>

Note on these references. The sources above are analogues or formal precedents at later ontological levels; none is evidence that the proposed foundational closure exists in nature. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 7

Orientation: When Difference Acquires Direction

Claim ~ Orientation is derived: it arises when an asymmetry in relational constraint becomes internally resolvable and persists long enough to bear on whether a higher-order identity can re-enter the identity class referenced by its Closure-earned organizational anchor A_F .

Chapter discipline. This chapter inherits retained distinctions, admissible possibilities $\mathcal{P}$, retained-dependency precedence $<$, mutually constraining organization, criterion-based identity $\sim_F$, closure, higher-order addressability, and the organizational anchor earned in Closure. Direction is earned here: directed notation appears only after the underlying asymmetry has been established.

■ difference $\rightsquigarrow$ retention $\rightsquigarrow$ mutual constraint $\rightsquigarrow$ closure $\rightsquigarrow$ asymmetric dependency $\rightsquigarrow$ orientation

7.1 Where Closure Leaves Us

Through Closure, we can inspect a rich relational organization without yet finding a justified direction. Closure gives us persistent higher-order identities, retained-dependency structure, and an endogenous organizational anchor A_F when representative-independent addressability is available. It does not tell us that one relational role points toward another.

Now we change the question. Instead of asking whether two roles differ, we ask what happens when exchanging them changes the organization's consequences.

If reversal matters, the relational scene has acquired a bearing. In Orientation, we ask for the weakest form of that bearing before any spatial axis, causal arrow, or metric time is allowed.

A closed organization may remain internally exchange-symmetric. The burden of this chapter is to identify the weakest condition under which exchange symmetry ceases to hold in a way that matters to the organization itself.

■ Difference through Closure supply retained dependency, integrated organization, and endogenous reference without supplying direction. Open question: whether orientation can be derived from that inheritance alone or requires an additional commitment.

7.2 Orientation as a Derived Relational Property

The central proposal is that orientation should not be introduced by stipulating a directed edge. A directed edge is a convenient encoding only after the relevant asymmetry has been earned. The ontology should instead begin from the possibility constraints and dependency relations already available from Boundary through Relation.

Let K_{ij} denote, schematically, the way admissible variation in relational component r_i constrains the admissible variation of r_j . The symbol imposes no metric, probability or causal force. It records a structural dependency, that changing what is admissible for r_i changes what remains admissible for r_j . ■
 $K_{ij} : \Delta r_i \mapsto \Delta \mathcal{P}(r_j)$


If the two roles are exchange-equivalent, reversal changes only labels. If they are not exchange-equivalent, the organization itself distinguishes them:

■ $K_{ij} \not\sim K_{ji}$

Working definition. A relational domain is oriented wherever its internal dependency structure contains persistent, consequential non-equivalence between otherwise exchangeable relational roles.

The local arrow discipline is explicit. Here $\mapsto$ denotes a map or coupling between a variation and a change in admissible possibilities; it is not retained precedence. The inherited symbol $<$ continues to denote retained dependency between configurations. Once asymmetric dependency has been earned, $<_o$ denotes orientational dependency. No additional primitive directed-edge relation is introduced.

■ Directional notation records an established non-equivalence; it does not create one. Open question: the weakest non-circular definition of K_{ij} that avoids presupposing causality, probability, metric, or time (Question 1).



The arrow is not drawn first and justified afterwards. It appears only where exchanging the roles makes a difference.

A mine upstream and a plant downstream: swap them and the river carries the effluent the other way.

Figure 7.1. The exchange test, and where the arrow comes from. In the upper panel the relation between A and B is exchanged and the structure is the same one it was. In the lower panel the same exchange yields a different structure. The everyday counterpart is a mine upstream and a plant downstream: swap them and the river carries the effluent the other way. The insight is the chapter's discipline about its own notation — the arrow is not drawn first and justified afterwards. It is admitted only where exchanging the roles makes a difference, which is what orientation means here and all it means.

7.3 What the Minimally Resolved Origin Gives This Chapter

Origin defines Ω as the minimally resolved reference condition: no operative distinction is available within the framework's initial resolving frame. This is a resolution-relative claim, not an assertion that every possible description of Ω is absolutely featureless. Orientation inherits that restraint; it does not require hidden structure beneath Ω .

■ $\text{Res}_{W_0}(\Omega) = \emptyset$ does not entail that no distinction exists at any deeper resolving level

Here W_0 is the least-resolving frame admitted at Origin. The framework neither asserts nor denies finer unresolved variation. Orientation asks a separate question: when can a non-equivalence already available somewhere in the relational organization become consequential at a higher organizational level?

This framing avoids forcing Orientation to explain how an absolutely structureless state generates asymmetry ex nihilo. The chapter can instead ask which admissible variations become integrated into organizations whose consequences survive higher-order resolution and closure.

■ The resolution-relative definition of Origin is compatible with derived orientation without positing hidden directional structure. Open question: whether unresolved lower-order variation is needed at all, or whether orientation can arise entirely from already-admitted relational organization (Question 5).

7.4 Latent Asymmetry, Effective Asymmetry and Orientation

Three thresholds are worth separating, since ordinary language collapses them into “symmetry breaking”.

Latent asymmetry. A non-equivalence exists at some finer relational description but does not survive the resolving criterion of the higher-order identity under consideration.

Effective asymmetry. The non-equivalence survives the higher-order resolving map and changes the admissible organization at that level.

Orientation. The effective asymmetry becomes organized as a persistent asymmetric dependency whose consequences remain available through enough recursive transformation to affect re-entry relative to the organizational anchor A_F .

Let $W^{(L)}$ be a resolving frame associated with organizational level L , in the sense introduced in Boundary. A lower-order difference may be unresolved at L :

$$■ W^{(L)}(\Sigma) = W^{(L)}(g\Sigma)$$

for a relevant exchange or reversal transformation g . Recursive interaction can nevertheless amplify or integrate lower-order differences into an organization for which:

$$■ W^{(L)}(\Sigma) \neq W^{(L)}(g\Sigma)$$

The difference has crossed the resolution threshold of the higher-order organization. The transition is not merely observational if the resolved difference changes the system’s admissible relational transformations. That is the point at which asymmetry becomes dynamically effective.

Renormalization-group and critical-phenomena research supplies an established analogue for the general idea that effective descriptions and symmetries can depend on scale, and that collective behavior can acquire properties not transparent in microscopic variables (Fisher, 1974; Hohenberg and Halperin, 1977; Metzner and colleagues, 2012). We borrow only that methodological lesson. $W^{(L)}$ is not identified with a renormalization-group

transformation, and no energy or length scale is assumed. The coarse-graining operator $CG[\cdot]$ belongs later in Scale; resolution here means only frame-relative discriminatory access as earned in Boundary.

○ INTERPRETIVE Effective structure can depend on the level at which it is resolved. Open question: which kinds of unresolved variation cross a higher-order threshold and which average out (Question 5).

7.5 From Effective Asymmetry to Asymmetric Constraint Propagation

An effective asymmetry is still not orientation. It becomes orientational when it enters the dependency architecture. Suppose a change in r_i changes the admissible states of r_j while the reversed dependency is not structurally equivalent:

■ $\Delta r_i = \Delta \mathcal{P}(r_j)$, while $\Delta r_j \not\equiv$ an equivalent $\Delta \mathcal{P}(r_i)$

This is stronger than unequal labels and weaker than physical causation. It says the relational organization distinguishes two dependency roles because exchanging them changes admissible consequences. At the simplest level this justifies the orientational relation $r_i <_o r_j$. The richer object is the whole asymmetric constraint structure $K = [K_{ij}]$, which may branch, converge, overlap, or support several non-redundant orientational modes.

7.6 Anchor-Relative Orientation

Orientation becomes consequential once Closure has supplied a higher-order identity O_F that can function in the organizational anchor role A_F . The anchor is not itself a direction. It is an earned reference-bearing identity relative to which relational profiles and dependency consequences can be compared. Orientation arises when dependencies organized relative to that reference cease to be interchangeable.

Let F be the identity criterion defining O_F , and let A_F denote that closed identity functioning as the organizational anchor earned in Closure. An oriented dependency sequence may be written:

■ $A_F <_o \Sigma_1 <_o \Sigma_2 <_o \dots <_o \Sigma_k$

The subscript o marks orientational dependency, not temporal precedence. A_F supplies an endogenous reference against which the organization can later test identity-class re-entry. Closure has earned this reference role for the closed organization as a whole.

Key distinction. A_F is not an orientation. It supplies an earned reference identity; orientation is the persistent consequential non-equivalence of dependency roles relative to that identity and the organization that maintains it.

7.7 How Much Persistence Is Enough?

“Persists” is underspecified on its own. The criterion here is functional: the asymmetry must persist through enough relational transformation to remain consequential when the recursive organization tests re-satisfaction of F . Suppose the sequence reaches a configuration Σ_k that again belongs to O_F :

$$\blacksquare \Sigma_k \in O_F$$

The higher-order identity criterion is again satisfied even though the resulting configuration need not reproduce the earlier realization. Orientation counts as structurally persistent when the orientation-bearing asymmetry changes either the possibility of that re-satisfaction or the relational condition in which it occurs.

■ orientation persistence threshold = the minimum retention required to affect anchor-relative identity re-entry

This avoids requiring indefinite persistence. An asymmetry is genuine orientation if it survives exactly as long as it takes to alter a later closure or return condition. One that appears and vanishes without affecting any higher-order dependency is a transient perturbation instead.

It uses only re-satisfaction of the identity criterion F and the representative-independent addressability earned in Closure. Recurrence, departure, exact versus non-identical return, path consequence, winding, and phase remain Return’s subject. The dependence therefore runs from Closure’s identity machinery into Orientation, not from a yet-undefined return predicate backward into this chapter.

■ Persistence of orientation can be defined functionally by consequence for later identity re-entry rather than by duration. Open question: whether re-entry compatibility is the right threshold or only one available criterion (Question 6).

7.8 Relational Irreversibility: Reversal That Fails to Recover the Anchor

Orientation is weaker than irreversibility. A dependency structure can be oriented while a reversed organization still recovers the same higher-order

identity. The pre-temporal notion of irreversibility proposed here is therefore anchor-relative.

Let $\mathfrak{D}$ be an orientation structure and let $\text{Ret}(A_F; \mathfrak{D})$ indicate whether an admissible sequence organized under $\mathfrak{D}$ can depart from and re-enter O_F (the predicate is defined explicitly in 8.3). The map $\mathfrak{D} \mapsto \mathfrak{D}^{-1}$ denotes role reversal of the orientational structure; it is a transformation in the analyst's representation, not retained precedence. If:

$$\blacksquare \text{Ret}(A_F; \mathfrak{D}) = 1 \text{ while } \text{Ret}(A_F; \mathfrak{D}^{-1}) = 0$$

then reversal fails to reconstruct the same identity-re-entry relation, and the organization is relationally irreversible with respect to A_F .

Working proposition. Relational irreversibility appears when reversing the orientational dependency conditions destroys, changes, or redirects re-entry into the identity class referenced by A_F .

This is not yet thermodynamic irreversibility and not an arrow of physical time. It is a structural non-equivalence between forward and reversed dependency organizations. Later chapters can ask whether physical temporal irreversibility is a special realization of this more primitive architecture.

○ SPECULATIVE Anchor-relative irreversibility is a candidate precursor of temporal irreversibility, not an instance of it.

7.9 Symmetry Breaking Without Hard-Coding Direction

The strongest objection to derived orientation is that direction must already be hidden in admissible transformation. Meeting it requires separating three questions: whether symmetry is absolute, whether asymmetry can become effective, and whether an effective asymmetry is retained.

If an initial configuration were absolutely symmetric, admissible transformation perfectly symmetry-preserving, and the successor unique, symmetry would remain invariant. The third condition is substantive. Chapter 3 already types $\mathcal{U}$ as a transition relation rather than a generally single-valued function, so multiple successors may be admissible without probability having been introduced. Equivariance constrains symmetry-related branches; it need not force a unique symmetric successor. Established symmetry-breaking theory likewise distinguishes symmetry of laws from symmetry of particular states or solution branches (Bernstein, 1974; Michel, 1980; Brading, Castellani and Teh, 2023).

This framework does not need to claim that a perfectly homogeneous metaphysical state chooses a direction without further structure. This is because 1.5's origin leaves lower-order variation unspecified rather than denied. The question becomes whether some variations participate in organizations that survive higher-order resolution and closure. The proposed mechanism is differential persistence:

■ unresolved variation $\rightsquigarrow$ effective asymmetry $\rightsquigarrow$ differential persistence $\rightsquigarrow$ closed higher-order organization $\rightsquigarrow$ orientation

A perturbation does not directly create orientation. Most perturbations may disappear, cancel or remain below the higher-order resolving threshold. A perturbation becomes relevant only when its consequences are incorporated into a higher-order dependency structure that persists and remains consequential to return. This is a restrained form of structural selection. Among dynamically accessible asymmetric configurations, those compatible with maintaining or recovering a higher-order identity persist under a wider class of admissible transformations than those that destroy it. "Selected" implies no agency, optimization, probability or biological fitness. It means differential persistence under the already declared dynamics and perturbation class.

7.10 What Selects One Branch?

If two candidate orientations $\mathfrak{D}$ and $\mathfrak{D}^{-1}$ are initially exchange-related, what makes one persist? The best answer available here is conditional rather than universal. Recursive return can break their dynamical equivalence even when the underlying generative rule privileges neither branch in advance.

■ $\text{Ret}(A_F; \mathfrak{D}) \neq \text{Ret}(A_F; \mathfrak{D}^{-1})$

If one branch preserves or recovers F while its reverse does not, the two cease to be equivalent relative to the higher-order identity. Re-entry compatibility can therefore differentially stabilize asymmetries after they arise. This does not explain every possible first fluctuation. The weaker result is enough: the rule need not encode which orientation will survive, only permit relational variation, after which higher-order closure and identity re-entry discriminate among the resulting branches.

○ SPECULATIVE Symmetry breaking supplies candidate asymmetries; compatibility with recursive closure and anchor-relative return can differentially stabilize some asymmetric dependency structures, producing derived orientation without a primitive preferred direction.

Equivariant bifurcation theory supplies a mathematical analogue, in that symmetric dynamical laws can possess lower-symmetry solution branches whose symmetry type is constrained by the system's group action (Golubitsky, Stewart and Schaeffer, 1988; Gatermann, 2000). The present proposal is not an application of the equivariant branching lemma. It identifies a family of tools worth testing in the computational companion.

7.11 Multiple Degrees of Orientational Freedom

Orientation should not be reduced to a single global before-and-after axis. Because the underlying object is an asymmetric constraint structure K_{ij} , an organization may support several non-redundant modes of orientational dependency. At this stage the framework earns an independence problem, not a cardinal orientational dimension: cardinality, rank, and orthogonality remain later formal achievements.

■ orientational independence $\neq$ vector-space dimension $\neq$ spatial dimension

Examples include branching dependencies, converging dependencies, coupled loops and overlapping oriented closures. Such organization can be richer than a line while remaining non-spatial. This preserves the later possibility that some stable orientational modes contribute to emergent geometry while others remain non-spatial relational properties.

Relation likewise stopped at non-redundant relational variation rather than assigning an internal numerical dimension. Orientation inherits that discipline. Formalism may later determine whether a suitable independence structure admits rank-like representation; Geometry must separately earn any spatial dimensional interpretation.

Open question: how should orientational independence be defined before linear algebra and orthogonality are earned, and how does it relate to the independence structure inherited from Relation?

7.12 Local Orientation, Global Orientability and Cycles

Local orientation does not imply a single global orientation. A domain may contain several non-equivalent directed dependencies without admitting one consistent global ordering. This matters because a directed cycle is oriented even though it cannot be represented as a global acyclic order:

■ $A <_o B <_o C <_o A$

The cycle does not erase orientation; it shows that orientation is weaker than partial order. In graph theory, orienting an edge simply assigns a direction. At the same time, stronger global properties such as strong connectivity or acyclicity impose further constraints. Robbins' theorem characterizes when an undirected graph admits a strongly connected orientation. The relevance here is formal rather than ontological (Robbins, 1939).

The important cycle for this framework is anchor-relative. Orientation earns the relation $\prec_o$; Return will ask what it means for an oriented sequence to depart from and later re-enter O_F , whether re-entry is exact or merely identity-equivalent, and what path-dependent structure survives it.

7.13 Orientation Is Not Yet Partial Order, Causality, Time or Geometry

Four collapses must be prevented explicitly.

Orientation is not partial order. A directed dependency need not be transitive or acyclic.

Orientation is not physical causality. Dependency may be logical, structural or dynamical without establishing relativistic causal influence.

Orientation is not metric time. The symbol $\prec_o$ and the sequence indices express generative and dependency organization, not duration.

Orientation is not spatial direction. No left or right, angle, coordinate axis, length or embedding has been derived.

Causal set theory is a useful comparison because it deliberately begins with a stronger structure, a locally finite partial order interpreted as proto-causality. That order encodes substantial spacetime information, but even there continuum geometry requires further conditions and reconstruction (Surya, 2019). We stay weaker: it asks how directed dependency itself can be derived before assuming the partial-order axioms causal-set theory begins from.

7.14 Resolution Crossing Without a Hidden Observer

A predictable objection is that “resolution” makes orientation observer-dependent. The reply distinguishes an external epistemic resolving map from an internally realized higher-order equivalence. An external modeler may describe a coarse-graining with $W^{(L)}$, but the ontic counterpart comes from Closure. A higher-order identity groups lower-order realizations according to an invariant F . If a lower-order asymmetry makes no difference to F or to any admissible higher-order relation, it is effectively invisible to that identity. If

recursive organization makes the asymmetry alter F-relevant dependency or return, it has become internally consequential whether or not anyone notices.

■ observer coarse-graining $\neq$ ontic higher-order equivalence, though the former may model the latter

This is also why Origin's resolution-relative formulation does not become epistemic idealism. The theory does not claim reality is symmetric because an observer cannot see deeper. It claims only that the initial ontology should not assert more absence of distinction than its admitted resolving frame can justify. Boundary generalizes the same restraint to later resolving frames.

7.15 Computational Derivability

The computational burden is sharper than “can arrows appear?” A valid model must begin with admissible transition relations that encode no preferred orientational branch and test whether higher-order organization produces persistent non-equivalence under reversal. A minimal program proceeds in seven steps.

Initialize an ensemble of relational states symmetric at the chosen resolving level, allowing either unresolved microvariation or symmetry-related perturbations without directional labels.

Apply a symmetric, equivariant admissible transition relation $\mathcal{U}$, and verify computationally that the relation itself does not privilege a branch under the declared exchange transformation g .

Detect emergent closed organizations using Closure's criteria, with F specified independently of the target orientation.

Within each closure, test whether dependency interventions produce $K_{ij} \neq K_{ji}$. External diagnostics may use counts or probabilities even though those quantities are not yet ontological primitives of the modeled system.

Test persistence: does the asymmetry survive enough recursive updates to alter the closure's return condition?

Reverse the discovered orientation structure. Does the reversed organization still permit re-entry into O_F under the same identity criterion F?

Compare against matched controls in which apparent orientation is created only by labels, initial directional bias or hard-coded asymmetric rules.

The strongest success condition would be a family of models in which symmetric rules generate symmetry-related candidate branches. However,

recursive closure and return produce robust branch-specific persistence without a preferred direction being supplied by the programmer.

Falsification guardrail. If stable orientation appears only when the admissible transition structure, the initial resolved state, the organizational anchor A_F , or a target topology already encodes the eventual direction, the derivation has failed. If every apparent asymmetry vanishes under role exchange once labels are removed, orientation has not been earned.

7.16 Worked Example: Five Relational Regimes

Regime	Relational condition	Interpretation
A. Resolved symmetry	$KAB \sim KBA$	Roles remain exchangeable; no orientation
B. Latent asymmetry	A finer description differs, but $W^{(L)}(\Sigma) = W^{(L)}(g\Sigma)$	The difference lies below the relevant resolving threshold; no higher-order orientation
C. Effective asymmetry	$W^{(L)}(\Sigma) \neq W^{(L)}(g\Sigma)$, but the asymmetry is transient	Higher-order structure resolves a difference that does not survive to constrain return
D. Persistent orientation	$KAB \not\sim KBA$, and the difference alters re-entry into O_F	Derived orientation: the asymmetric dependency is persistent and consequential
E. Anchor-relative irreversibility	$\text{Ret}(A_F; \mathfrak{D}) = 1$ while $\text{Ret}(A_F; \mathfrak{D}^{-1}) = 0$	Reversing orientation fails to recover O_F relative to A_F ; relational irreversibility

The point of Regime E is not an arrow of time. It establishes only that a recursive dependency organization and its reversed counterpart have different consequences for return. Return can then ask what further structure makes return itself recurrent, phase-bearing, or capable of supporting a later temporal interpretation.

7.17 Competing Interpretations

Primitive direction. The simplest alternative treats directed relations as primitive. That makes orientation easy and weakens the project's parsimony, since source and target asymmetry is inserted rather than derived. This chapter rejects the route unless simulation shows derived orientation is impossible under the allowed ontology.

Absolute spontaneous symmetry breaking. A stronger origin story begins from a literally homogeneous, perfectly symmetric Ω and invokes spontaneous symmetry breaking. Established physics shows symmetric laws can possess

asymmetric states or solution branches, so the idea is not incoherent. Applying it to an absolutely structureless prephysical origin would exceed what this framework can justify, which is one reason the origin of 1.5 is defined by resolution rather than by absolute absence.

Hidden fine structure. The opposite extreme posits a detailed microstructure beneath Ω . That relocates the explanatory burden and risks smuggling in the very asymmetries the book means to derive. The chapter permits unresolved variation only as a possibility; it assumes no specific hidden entities, dimensions, directions or dynamics.

Purely epistemic orientation. A fourth reading treats orientation as an observer's choice of ordering. That becomes inadequate once asymmetric dependency has interventionally different consequences for closure or return. Observer labels may describe orientation; the non-equivalence of admissible transformations supplies its ontic content.

7.18 Objections and Replies

Objection 1: The chapter renames asymmetry as orientation. **Reply:** Not every asymmetry qualifies. Orientation additionally requires entry into relational dependency and enough persistence to alter higher-order return. Latent and transient asymmetries are excluded by construction (7.4, 7.7).

Objection 2: $K_{ij} \not\sim K_{ji}$ already assumes direction. **Reply:** K_{ij} is introduced as a bookkeeping relation for how admissible variation in one component changes another. The test is role exchange: if swapping i and j leaves all F -relevant possibilities invariant, there is no orientation. The arrow is assigned only after non-equivalence is established.

Objection 3: Making Ω only resolution-symmetric abandons the minimal origin. **Reply:** That definition is already the book's, adopted in 1.5 for reasons of its own. It makes the origin weaker, not richer: it asserts no hidden furniture and only refuses to infer absolute absence from non-resolution. This chapter inherits it rather than proposing it.

Objection 4: Unresolved variation is unfalsifiable. **Reply:** Specific hidden variation would be unfalsifiable if freely invented, and the framework does not posit any. What is testable is the derivation: candidate simulations must show higher-order orientation arising without coarse-grained directional bias. If that cannot be done, the resolution-relative origin has not solved the dynamical problem.

Objection 5: Symmetric rules cannot produce asymmetric outcomes. **Reply:** A symmetric law can admit lower-symmetry solution branches, which is the standard distinction between the symmetry of equations and the symmetry of states. The exact mechanism depends on instability, degeneracy, fluctuation, boundary conditions or non-unique dynamics. This chapter uses that as an analogy and leaves the project-specific mechanism open.

Objection 6: Re-entry-based persistence is circular because Return comes next. **Reply:** Section 7.7 uses only re-satisfaction of the already-earned identity criterion F and representative-independent addressability from Closure. It assumes nothing about departure, recurrence, exactness, path consequence, winding, or phase, all of which remain Return's subject.

Objection 7: Anchor-relative irreversibility is secretly time. **Reply:** No duration, metric, past, future or entropy is invoked. The claim is only that applying a reversal transformation to a dependency structure changes whether a recursive configuration re-enters an identity class. That is structural reversibility, not temporal reversal.

Objection 8: Orientation requires a single axis. **Reply:** The general object is the asymmetric constraint structure, not a line. Several independent orientational modes may coexist (7.11), and a single arrow is the smallest example.

Objection 9: Differential persistence smuggles in probability or fitness. **Reply:** "Differential" means only that under the declared update and perturbation class, one organization retains F while another does not. No probability measure or optimization principle is required; survival frequencies may be external simulation diagnostics.

Objection 10: Why should return compatibility select what exists? **Reply:** At this stage it should not be elevated into a universal law. It is a candidate mechanism internal to closed recursive identities, and its value is that it yields a testable distinction between transient asymmetry and orientation that participates in stable higher-order organization. How general it is, computation must decide.

7.19 What Orientation Has Not Yet Earned

Spatial direction or coordinates. Orientation remains relational and anchor-relative.

Metric distance or scale. No interval, ruler, ratio of lengths or physical size has been derived.

Metric time. Sequence and return remain generative and dependency notions.

Thermodynamic irreversibility or entropy production.

Physical causation or relativistic light cones.

Global partial order. Directed cycles remain admissible.

Geometry or dimensionality from orientation alone.

Chirality or parity violation, though oriented loops may later supply prerequisites.

A universal law that return compatibility always selects stable orientations.

A specified mechanism for the unresolved variation beneath the minimally resolved origin.

7.20 Ontological Defensibility Pulse: Orientation

This is the chapter's Pulse sidebar. It applies to the central proposition. It is set apart from our argument so that a reader can skip it on a first pass.

Pulse question	Applied to Orientation
1. Entities required	No new substance: retained relations, constraints, identity classes, resolving frames, $\mathcal{U}$, and Closure-earned A_F
2. Ontological level	Pre-geometric organization: from exchange-symmetric roles to persistent asymmetric dependency
3. Lower-order dependencies	Difference, Distinction, retention, $\mathcal{P}$, $<$, mutual constraint, closure, identity equivalence, and A_F
4. New emergent properties	Orientation as consequential non-equivalence of dependency roles; anchor-relative irreversibility
5. Claim types	Formal and relational core; interpretive on resolution; speculative on selection by return
6. New primitives	Ideally none: orientation is a property of earned dependency structure, and 1.5's origin asks restraint, not hidden structure
7. Fewer assumptions?	Strengthened if symmetric rules yield asymmetric closures with no direction hard-coded; weakened if an arrow must be inserted

Pulse question	Applied to Orientation
8. Observational constraints	Role exchange, dependency ablation, persistence under admissible succession, reversal, A_F -relative re-entry comparison, matched controls

7.21 Implications and Handoff

We entered an exchange-symmetric relational world and leave with a derived bearing. Persistent consequential asymmetry can justify oriented dependency without making direction primitive.

That changes what we can follow. A relational transformation can now have an ordered route through its own dependency structure.

Return follows such a route past its starting identity and asks a new question: can the organization become that identity again without undoing everything that happened along the way?

■ $A_F <_o \Sigma_1 <_o \Sigma_2 <_o \dots <_o \Sigma_k$, with $\Sigma_k \in O_F$

The next question is not whether the sequence comes back later in metric time. It is whether an oriented sequence can re-satisfy the identity criterion of its anchor, what distinctions survive that re-entry. Whether return itself generates a new higher-order relational invariant.

Handoff to Return. Under what conditions can a sequence of relationally ordered dependencies re-enter the identity class of its anchor without erasing the orientational consequences accumulated through the sequence?

Questions Opened by This Framework

What is the weakest formally non-circular definition of K_{ij} that captures constraint propagation without presupposing causality, probability, metric or time?

Can the origin condition $\text{Res}_{W_0}(\Omega) = \emptyset$ be stated without making Ω observer-dependent or covertly positing inaccessible microstructure?

What mathematical structure should represent resolving depth before physical scale is derived: nested equivalence relations, partitions, sigma-algebras, category-theoretic quotients, or something simpler?

Can a symmetric, equivariant admissible transition relation generate higher-order closures with $K_{ij} \not\sim K_{ji}$ when no preferred orientation is encoded at the resolved initial level?

What kinds of unresolved variation suffice for asymmetry to cross a higher-order resolution threshold, and which merely average out?

Is return compatibility a general selection mechanism or only one route by which asymmetry becomes persistent?

Can anchor-relative irreversibility be defined entirely through equivalence classes and admissible transformations, without binary success variables such as $\text{Ret}(A_F; \mathcal{O}) = 1$?

Are derivation order, retained dependency order and derived orientation the same relation at different levels, or irreducibly distinct?

What conditions let local orientations compose into a globally consistent structure, and what arises when they cannot?

How should d_O be defined before linear algebra and orthogonality are earned, and how does it relate to d_R ?

Can directed cycles preserve orientation while supporting a return invariant that later becomes phase or winding?

What further constraints are necessary before oriented dependency becomes a partial order, proto-causality or temporal order?

Could apparent large-scale symmetry itself be emergent from many lower-order asymmetries, and how would the framework distinguish symmetry restoration from unresolved asymmetry?

What would falsify the claim that orientation is derived rather than primitive in the proposed computational program?

Selected References Cited in Orientation

Bernstein, J. (1974). Spontaneous symmetry breaking, gauge theories, the Higgs mechanism and all that. *Reviews of Modern Physics*, 46(1), 7–48.
<https://doi.org/10.1103/RevModPhys.46.7>

Brading, K., Castellani, E., & Teh, N. (2023). Symmetry and symmetry breaking. In *The Stanford Encyclopedia of Philosophy* (Fall 2023 edition).
<https://plato.stanford.edu/archives/fall2023/entries/symmetry-breaking/>

Fisher, M. E. (1974). The renormalization group in the theory of critical behavior. *Reviews of Modern Physics*, 46(4), 597–616.
<https://doi.org/10.1103/RevModPhys.46.597>

Gattermann, K. (2000). *Computer Algebra Methods for Equivariant Dynamical Systems*. Lecture Notes in Mathematics 1728. Berlin: Springer-Verlag.
<https://doi.org/10.1007/BFb0104059>

Golubitsky, M., Stewart, I., & Schaeffer, D. G. (1988). *Singularities and Groups in Bifurcation Theory*, Volume II. Applied Mathematical Sciences 69. New York: Springer-Verlag.

Hohenberg, P. C., & Halperin, B. I. (1977). Theory of dynamic critical phenomena. *Reviews of Modern Physics*, 49(3), 435–479.
<https://doi.org/10.1103/RevModPhys.49.435>

Metzner, W., Salmhofer, M., Honerkamp, C., Meden, V., & Schönhammer, K. (2012). Functional renormalization group approach to correlated fermion systems. *Reviews of Modern Physics*, 84, 299–352. <https://doi.org/10.1103/RevModPhys.84.299>

Michel, L. (1980). Symmetry defects and broken symmetry: Configurations, hidden symmetry. *Reviews of Modern Physics*, 52(3), 617–651.
<https://doi.org/10.1103/RevModPhys.52.617>

Robbins, H. E. (1939). A theorem on graphs, with an application to a problem of traffic control. *American Mathematical Monthly*, 46(5), 281–283. doi:10.2307/2303897.

Surya, S. (2019). The causal set approach to quantum gravity. *Living Reviews in Relativity*, 22, 5. <https://doi.org/10.1007/s41114-019-0023-1>

Note on these references. The literature above is comparison, constraint or mathematical analogue; none of it is evidence for the ontology proposed here. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 8

Return: When Order Re-Enters Its Origin

Claim ~ Return occurs when a nontrivially transformed, oriented relational sequence genuinely departs from and later re-enters the identity class O_F referenced by the Closure-earned organizational anchor A_F , even when the underlying state differs.

Chapter discipline. This chapter inherits orientation, criterion-based identity O_F , and the organizational anchor A_F earned by Closure. Return here means re-entry into an identity class, prior to any period, loop or memory. The chapter asks what must occur before a transformed configuration can count as having returned to the same higher-order identity.

- distinction $\rightsquigarrow$ retention $\rightsquigarrow$ structure $\rightsquigarrow$ closure $\rightsquigarrow$ orientation $\rightsquigarrow$ return
- return of identity $\neq$ exact repetition of state

8.1 Where Orientation Leaves Us

Orientation lets us follow change instead of merely comparing states. We can now move with an ordered relational sequence while remembering that the order is still not a clock. The route is still not a path through space.

The useful perspective is therefore neither a circle nor a timeline. We follow identity itself: it is present, lost under transformation, and perhaps recovered.

In Return, we ask when that recovery deserves to be called return. The answer must allow the organization to come back as the same higher-order identity without requiring the same lower-order state.

The subscript o marks orientation of dependency, not spatial direction. What remains unresolved is whether such a sequence can become re-addressable to the identity from which it was organized.

A word about the chapter's title. Throughout, "origin" means the Closure-earned organizational reference A_F , not the primordial reference condition Ω . Return concerns re-entry into O_F relative to that anchor role. Nothing here claims that a returning organization re-enters Ω .

- orientation $\neq$ return

A dependency structure can continue differentiating indefinitely. Return therefore adds a new property. The challenge is to define that property without drawing a geometric loop and then mistaking the picture for a derivation.

8.2 Why a Circle Cannot Be the Definition

The intuitive picture of return is a circle, but the picture is useful only after its hidden commitments are separated. A drawn cycle already contains directedness, sequence, and a criterion for calling its terminal realization “the same” higher-order identity as its initial realization. In ordinary physics it also suggests elapsed time and a spatial path, neither of which is available here.

We therefore treat the circle as a later encoding, not a primitive definition. The minimally adequate form is ordered departure followed by re-entry into an identity class:

$$\blacksquare A_F <_O \Sigma_1 <_O \Sigma_2 <_O \dots <_O \Sigma_R, \text{ with } \Sigma_R \in O_F$$

The important relation is not that the trajectory draws a closed shape. It is that the resultant configuration Σ_R again satisfies the independently specified criterion F defining O_F , the identity whose reference-bearing role is A_F .

A melody can return to its tonic without the final acoustic pressure field being numerically identical to the opening one. The analogy illustrates only the logical distinction between returning to a structural role and reproducing every underlying state variable.

8.3 Defining $\text{Ret}(A_F; \cdot)$: Anchor Identity Must Precede Return

Orientation used $\text{Ret}(A_F; \cdot)$ anticipatorily to express whether a directionally organized sequence can recover the same higher-order identity. Return now defines that predicate explicitly.

$$\blacksquare O_F = [\Sigma]_{\sim F}$$

F denotes the identity-relevant organization by which multiple realizations count as the same higher-order identity O_F . Closure adds the reference-bearing role A_F when that identity becomes dynamically persistent and representative-independently addressable. Return inherits both the criterion and that earned reference role.

$$\blacksquare \text{Ret}(A_F; \Sigma_k) = 1 \text{ iff } \Sigma_k \in O_F \text{ after genuine departure}$$

This definition must not be tuned after the trajectory is known. A defensible return test fixes F independently, permits nontrivial transformation,

determines whether the sequence genuinely leaves O_F while F remains applicable, and then asks whether a resultant configuration re-enters that same identity class.

Closure already introduced lumpability as an analogy for higher-order addressability (6.12). Fine-grained states may be aggregated into macro-states while preserving the relevant transition structure under specified conditions. That comparison remains useful here, but it is inherited rather than newly introduced.

■ The return predicate is defined, not posited: $\text{Ret}(A_F; \cdot)$ abbreviates conditions on previously earned structure. Open question: the weakest non-circular F that makes return objective rather than observer-imposed (Question 1).

8.4 Persistence, Departure and Return Are Different

A system that never leaves its identity class has persisted; it has not necessarily returned. Otherwise every stable object would count as continuously returning to itself.

■ Persistence: $\Sigma_0 \sim_F \Sigma_1 \sim_F \Sigma_2 \sim_F \dots$

■ Return: $\Sigma_A <_o \Sigma_{-F} <_o \Sigma_R$, with $\Sigma_A \in O_F$, $\Sigma_{-F} \notin O_F$, and $\Sigma_R \in O_F$

Meaningful return therefore requires a genuine departure relative to the tested identity criterion. At least one intermediate configuration must fail that criterion:

■ $\exists i : \Sigma_i \notin O_F$, while F remains applicable

Departure need not mean destruction of every lower-order component. It means only that the organization used to define this particular anchor is not satisfied during part of the sequence.

Two different situations hide inside that requirement and should be separated. The criterion F concerns particular relations and roles. It can be evaluated on a configuration only while those relata and roles remain available to the criterion.

■ departure: the relata F concerns persist, but the organization does not satisfy F ; the criterion is applicable and false

■ dissolution: the relata or roles F concerns are themselves unavailable, so the criterion has no subject and is inapplicable rather than false

Return as defined here requires the first and weaker case. A sequence departs when its anchor's criterion remains a meaningful question with a negative answer. It returns when that same question again has a positive one. The folded structure below is a departure in this sense. The parts persist, the extended organization does not hold, and the criterion stays askable throughout.

Dissolution is a stronger condition and deserves a different name. If an organization disperses so completely that its identity criterion ceases to apply. Some later configuration nevertheless satisfies that criterion again, what has occurred is re-instantiation rather than return. The distinction is not idle: whether a dissolved identity can be reconstructed at all is the question underneath death and recovery, phase change, reconstruction from records and substrate replacement. we do not settle it, and the Register carries it as open.

■ Return requires departure under a criterion that remains applicable throughout. Open question: whether a dissolved identity can be reconstructed, and whether such re-instantiation is a stronger form of return or a different relation altogether.

A deployable structure may fold into a configuration that no longer performs its extended structural role and later unfold into a functionally equivalent one. Its material may remain continuously present while the higher-order identity criterion under examination is left and later recovered.

8.5 Minimal Formal Conditions for Return

A candidate minimal definition can now be stated without metric time or geometry.

Anchor identity: an independently constrained identity class O_F exists and functions in the Closure-earned reference role A_F .

Oriented transformation: admissible orientational dependencies generate a nontrivial sequence from a realization of O_F .

Departure: at least one intermediate configuration lies outside O_F while F remains applicable to it (8.4).

Re-entry: a resultant configuration Σ_R again lies inside O_F .

■ $\text{Ret}(A_F; \cdot) = \text{departure from } O_F \wedge \text{oriented transformation} \wedge \text{re-entry into } O_F$

The expression is schematic conjunction, not arithmetic. No magnitude has yet been assigned to departure, transformation or re-entry.

This definition closes the dependency Orientation left explicit. Section 7.7 defined the persistence threshold for orientation as the minimum retention required for an asymmetry to remain consequential to later identity re-entry. Return now strengthens that re-satisfaction condition by requiring genuine departure before re-entry. No backward primitive is introduced.

■ Return decomposes into four conditions on already-earned structure. Open question: whether orientation is necessary for return or merely one sufficient route (Question 2).

8.6 Return of Identity Is Not Repetition of State

The strongest distinction here is between identity-class recurrence and exact state repetition.

■ $\Sigma_R \in O_F$ does not require $\Sigma_R = \Sigma_A$

Σ_R may preserve the organization constitutive of O_F while differing in relations that are not part of F . This makes possible change internal to preserved identity:

■ $\Sigma_R \in O_F$ and $\Delta(\Sigma_A, \Sigma_R) \neq 0$

The metaphysics of persistence has long distinguished numerical identity from qualitative similarity and has examined the criteria by which identity through change is assessed. The present framework borrows only the structural lesson: preservation of an identity criterion need not require preservation of every qualitative feature. The broader literature treats criteria of identity and of persistence as distinct philosophical problems (Noonan and Curtis, 2018).

For this chapter, Σ_A and Σ_R are distinct configuration tokens that may belong to the same relational identity class O_F . That distinction becomes decisive if a later dependency order is required to remain acyclic.

8.7 Type Return, Token Acyclicity and the Causal-Set Comparison

Suppose the dependency relation is strict. If the same state token A occurs both before and after B , one risks writing a literal cycle into an order that may have been defined to be acyclic:

■ $A < B < C < A$

A safer building is:


■ $A_0 < B < C < A_1$, where $A_0 \sim_F A_1$ but $A_0 \neq A_1$

The sequence has returned to the identity type referenced by A_F without returning to the identical state token. Ordinary language blurs this: “the system returned to A” can mean that a later state occupies O_F , not that one and the same event has appeared twice.

This matters when comparing the framework with causal-set theory. Causal sets are locally finite partial orders in which the order represents proto-causality. As a result, token-level causal cycles are excluded by the partial-order structure. Identity-class recurrence, by contrast, can be represented by distinct ordered elements sharing a higher-order structural role. The comparison is structural only: we have not derived physical causality (Surya, 2019).

■ identity recurrence can coexist with event-token acyclicity

The distinction also prevents a later discussion of physical cycles from being conflated with closed timelike curves. A recurring organization need not imply that a causal event returns into its own antecedent chain.



Nothing travelled backwards and nothing was restored. A_1 is a different token that satisfies the same identity criterion as A_0 ,

which is why the loop exists at the level of the class and not at the level of anything in it.

Figure 8.1. Return through a different token. On the left the token path runs A_0 to B to C to A_1 and is perfectly straight: no token appears twice and nothing goes backwards. On the right the same history at the level of the identity class is a closed loop. The everyday counterpart is a relay: the baton finishes in the lane it started, and no runner runs twice. The insight is that the loop exists at the level of the class and at no level below it, so return requires neither restoration nor reversal — A_1 is a different token that satisfies the same identity criterion as A_0 , which is the whole of what has recurred.

8.8 Return as Relational Re-Addressability

Closure gave closure an external consequence. A sufficiently integrated organization can be addressed as one higher-order unit when external relations descend to its equivalence class. Return can now be characterized operationally as restoration of that higher-order address after departure.

$$\blacksquare E(\Sigma_R) \sim_G E(\Sigma_A)$$

The external relation E need not resolve every internal difference. If it can interact with Σ_R in the same identity-relevant way that it interacted with the earlier realization Σ_A , the higher-order address associated with A_F has been restored.

Software can suspend a service, alter internal buffers and later restore an interface with the same externally defined contract. The exact machine state has changed, yet the service becomes addressable under the same functional identity. Designed systems prove nothing about spontaneous ontology. The analogy isolates the distinction between identity of interface and identity of microstate.

8.9 Closure and Return Must Remain Distinct

Closure concerns the sufficiency and organization of constitutive dependencies. Return concerns re-entry into an identity class after departure. Neither entails the other.

$$\blacksquare \text{Closed}_F(\mathcal{R}) \not\Rightarrow \text{Ret}(A_F; \cdot)$$

A closed organization may transform into a different closed organization and never recover its former identity. Conversely, a recurrent pattern may be imposed by a larger system without possessing the internal dependency sufficiency Closure requires.

Theoretical biology later combines related ideas in a much richer setting. Closure-of-constraints accounts characterize biological organization through mutually dependent constraints that maintain one another, explicitly within thermodynamic and time-scale assumptions unavailable here. Their relevance is prospective: a living system may eventually require both organizational closure and robust recurrent restoration. However, neither concept should be loaded with biological meaning at this stage (Montévil and Mossio, 2015).

■ closure + robust return $\neq$ life, but may become one prerequisite for self-maintenance

8.10 Return, Recurrence and Periodicity

Ordinary language compresses several distinct concepts. We keep them separate.

Concept	Minimal criterion	What it does not yet imply
Persistence	The identity criterion remains satisfied through admissible transformation	Departure or recurrence
Return	One nontrivial departure followed by identity-class re-entry	Repeated return
Recurrence	Return occurs more than once	Equal interval between returns
Exact repetition	A later configuration reproduces the complete tested state	That exact repetition is generic
Periodicity	Recurrence with a stable metric interval	Not available before physical time is earned

A useful nesting is:

- exact repetition $\subset$ recurrence $\subset$ return-capable organization

Periodicity remains outside this nesting until metric temporal intervals are available. A return count may be a logical or external simulation index; a period requires a physical measure of duration.

8.11 What Established Recurrence Theory Does and Does Not Give Us

■ ESTABLISHED

Classical dynamical systems contain rigorous recurrence theorems. Under measure-preserving dynamics on a finite-measure accessible state space, Poincaré recurrence implies that almost every point of a region returns arbitrarily close to its initial condition under suitable assumptions. Return maps likewise study repeated intersections of trajectories with selected sections (Saussol, 2009).

These results are valuable analogues because they show that mathematically serious recurrence need not mean literal duplication of a complete microstate. But they are not derivations of this chapter. They presuppose state spaces, measures, dynamical evolution and evolution parameters richer than the present ontology. Their role here is diagnostic: later Formalism may legitimately recover or approximate such tools once their prerequisites have been earned.

- Return is pre-metric; Poincaré recurrence is a later mathematical analogue

8.12 Conservative and Transformative Return

The identity-class distinction permits two qualitatively different regimes. Under conservative return, the system re-enters O_F while preserving nearly all currently resolved relations, so that at the tested resolution return approaches repetition. Under transformative return, the system re-enters O_F while retaining differences outside F :

- $\Sigma_R \sim_F \Sigma_A$ but $\chi(\Sigma_R) \neq \chi(\Sigma_A)$

The symbol χ denotes an internal condition not constitutive of F .

Transformative return is the more generative case because traversal can leave a relational consequence behind while higher-order identity is restored.

8.13 Difference Within Preserved Identity

Before Return, difference most naturally separated one state or organization from another. Non-identical return introduces a further possibility:

- difference can accumulate within an equivalence class

We can now separate the question “does this configuration belong to O_F ?” from “in what internal condition is this realization?” That separation is structurally important because later theories routinely distinguish stable identity from internal state. None of those later interpretations is yet derived.

8.14 Retained Consequence Is Not Yet Memory

If a returned realization differs from its antecedent because of the route by which it returned, the sequence is path-dependent. Boundary made retained dependency available, and Return can now combine it with identity-class recurrence.

- same O_F identity + different return-conditioned state = retained path consequence

The term memory should nevertheless remain deferred. A system may exhibit hysteresis or path dependence without possessing any mechanism that internally uses the retained distinction to regulate its own organization. Memory requires the stronger condition: retained change must become internally consequential to a self-maintaining system.

- retention $\neq$ path dependence $\neq$ memory

A crack in a rock can record a history without thereby constituting memory in any biological or cognitive sense. The distinction keeps passive retention from being read as agency.

8.15 Return Without Physical Time

The strongest intuitive objection is immediate: return sounds temporal. A configuration satisfies F , departs from O_F , and a later dependency state again satisfies F . If physical time has not been derived, has the chapter smuggled it in through ordinary grammar?

The answer depends on whether dependency order can be specified without metric duration. Boundary already supplies retained-dependency precedence:

$$\blacksquare \Sigma_a < \Sigma_b$$

The claim is only that the admissibility or organization of Σ_b depends on retained consequence inherited from Σ_a . The relation assigns no real-valued coordinate t , no duration Δt , and no rate of change.

■ return requires ordered dependency; return does not yet require metric time

A mathematical proof or recursive definition offers a limited analogy. One proposition may depend on another. A recursive evaluation may re-enter a previously defined type, without the logical order itself being a physical clock. Computation on a real machine takes time; the formal dependency relation need not be defined by that duration.

8.16 What Return Adds to Orientation's Irreversibility

Orientation introduced anchor-relative relational irreversibility in anticipatory form (7.8). Return does not derive it a second time. It supplies the explicit departure-and-re-entry semantics used by that criterion.

$$\blacksquare \text{Ret}(A_F; \mathfrak{O}) = 1 \text{ while } \text{Ret}(A_F; \mathfrak{O}^{-1}) = 0$$

The first states that the orientational structure $\mathfrak{O}$ supports departure from and re-entry into O_F . The second states that reversing the relevant orientational roles fails to recover that identity. Orientation's criterion is therefore grounded rather than promissory.

This remains weaker than thermodynamic irreversibility. Return adds semantic precision to an inherited criterion; it does not add a second irreversibility principle.

8.17 Return as a Candidate Structural Selection Mechanism

■ SPECULATIVE

Return may do more than classify trajectories. It may help explain why some organizations remain available for further building. Suppose perturbative variation produces several asymmetric dependency organizations. Some reconstitute their anchor identity after transformation; others disperse into configurations that do not again satisfy F . If return-capable organizations repeatedly regenerate higher-order addresses while non-returning organizations cease to participate as stable units, recursive dynamics will contain more re-instantiations of the former.

■ return compatibility $\rightsquigarrow$ repeated re-instantiation $\rightsquigarrow$ greater availability for higher-order organization

This should not yet be called natural selection. There is no reproduction, heredity, population or fitness function. It is a weaker proposal: recursive organization may filter transient structures from recurrent ones. A computational model must show this happens without explicitly rewarding return, or the apparent selection is merely programmed preference.

8.18 Error Tolerance and the Identity Domain

Exact repetition is fragile. Identity-class return permits variation and therefore makes robustness possible.

■ $\text{Dom}_F = \text{O}_F = \{\Sigma : \Sigma \sim_F \Sigma_A\}$

Dom_F is the identity domain associated with criterion F and organizational anchor A_F . The notation avoids “basin of attraction,” which would presuppose richer state-space structure than has been earned.

A return mechanism is robust when admissible perturbations alter the route or the final microstate while the resultant configuration still re-enters Dom_F . The declared diagnostic transformation family $\mathfrak{T}_{\text{test}}$ inherited from Boundary and reused in Closure can therefore be applied, provided it is fixed before the result is inspected.

■ $T \in \mathfrak{T}_{\text{test}}$ and $\text{Ret}(A_F; T\Sigma) = 1$

The broader the admissible variation over which F remains objectively constrained, the less likely the return criterion is an artifact of exact coding.

8.19 Nested Return and Reference-Level Dependence

Higher-order closure immediately creates more than one possible return criterion. A lower-order component may return while a larger organization does not, or the larger organization may return while its components are replaced.

$$\blacksquare \text{Ret}(A_F; \cdot) \neq \text{Ret}(H_G; \cdot)$$

Here A_F is a lower-order organizational anchor and H_G is a higher-order identity/reference role that contains or depends on it. Return is therefore indexed to an organizational reference level.

A city's transportation network can recover its functional pattern after repairs even though individual vehicles and road surfaces have changed. Conversely, a particular vehicle can return to operating condition while the network remains disrupted. The analogy illustrates nested equivalence criteria, not spatial ontology.

This multilevel dependence will matter for Scale, because recurrence can be resolvable at one organizational level and invisible at another.

8.20 Joint Return Is Not Yet Synchronization

Suppose two orientational modes each support recurrence. We may ask whether their return conditions coincide in dependency structure.

$$\blacksquare \text{joint return} \neq \text{synchronous return}$$

Synchronization requires a shared temporal metric, or at minimum a justified comparative interval structure, and Return possesses neither. The restraint matters because recurring systems are natural candidates for clocks. A clock is not created merely by writing a recurrence relation.

8.21 Pre-Phase, Winding and What Return Makes Possible

■ SPECULATIVE

Non-identical recurrence creates a structural precursor to phase. If A_0 and A_1 satisfy the same identity invariant but differ in an internal relational variable, we have separated anchor identity from condition within the anchor:

$$\blacksquare A_0 \sim_F A_1 \text{ while } \chi(A_0) \neq \chi(A_1)$$

Physical phase normally requires a parameterized cycle, algebraic structure and often metric time or angle. None is yet available. Return supplies only the

prerequisite distinction. Two realizations can occupy the same recurring identity class while differing systematically in internal condition. Repeated returns may later admit a count n or a winding index if Formalism earns the appropriate algebra and topology. For now n can function only as an external derivational or simulation index.

8.22 Return as a Precondition for Reusable Standards

Why should Return precede Scale? Because measurement requires re-identifiable reference structure. A ruler that irreversibly changes with every comparison is a poor standard. A clock that cannot reinstantiate a comparable state cannot mark repeated intervals. Before meters and seconds can be defined, a framework needs structures capable of serving again as the same reference in the relevant sense.

■ stable identity + repeatable return $\rightsquigarrow$ reusable relational reference

Return does not itself create a unit. It makes unit-like reuse conceivable. Formalism must first determine which comparisons are legitimate. Scale can then ask whether recurring relational structures establish endogenous standards without importing an external metric.

8.23 Computational Diagnostics of Return

As in Closure, an external simulation may use mathematics richer than the ontology it tests. Counting iterations, measuring graph properties or assigning ensemble statistics is permissible as diagnostic instrumentation. As a result, long as those quantities are not silently promoted into primitives of the modeled world. A computational implementation should test at least the following.

Anchor independence. Is F specified before observing which trajectories recur?

Nontrivial departure. Does the candidate trajectory actually leave Dom_F ?

Re-entry. Does a resultant state satisfy F under the same criterion?

Microstate difference. Are some returns non-identical at lower resolution?

Perturbation robustness. Does return survive a declared nontrivial transformation class?

Label invariance. Does return survive arbitrary relabeling of representational tokens?

Orientation dependence. Does reversing orientational roles preserve or destroy return?

Hard-coding test. Does recurrence disappear when explicit cycle templates are removed from the update law?

Coarse-graining test. Can return appear at one resolution while lower-order states do not recur?

Nested return. Can higher- and lower-order identity classes return independently?

Falsification guardrail. If return occurs only because the admissible transition structure explicitly contains the target cycle or a privileged instruction to restore O_F , return has not been derived.

8.24 Worked Example: Five Relational Regimes

Regime	Relational condition	Interpretation
A. Persistence without return	$\Sigma_0 \sim \Sigma_1 \sim \Sigma_2$; the identity criterion never fails	Stable persistence; no departure, therefore no return
B. Departure without return	$A_0 < B < C < D$; no later state re-enters O_F	Oriented transformation without recurrence
C. Exact repetition	$A_0 < B < C < A_1$ with $A_1 = A_0$ under the full tested state	Strong return; a potentially brittle special case
D. Non-identical identity return	$A_0 < B < C < A_1$; $A_1 \sim_F A_0$ but $A_1 \neq A_0$	General return with retained internal difference
E. Return asymmetry	Forward orientation returns; the role-reversed organization does not	A_F -relative relational irreversibility, inherited from Orientation

Regime D is the chapter's central case. It shows why return need not collapse into either trivial persistence or exact repetition. Regime E shows how Orientation's irreversibility criterion becomes fully interpretable once $\text{Ret}(A_F; \cdot)$ is defined.

8.25 Competing Interpretations

Dynamical. Return is recurrence in a state space. This will likely become mathematically productive after Formalism.

Topological. Return resembles loop closure. This may later motivate homotopy, winding or cyclic invariants, but no topological loop is yet part of the ontology.

Information-theoretic. Return restores an identity-relevant macrostate after transformation. Lumpability and coarse-graining provide useful later formalisms.

Organizational. Return is a higher-order relational address being restored. This is the preferred reading, because it uses only identity, orientation, transformation and equivalence structures already available.

■ preferred definition: relational re-entry into an independently specified identity class

8.26 Objections and Replies

Objection 1: Return secretly assumes time. **Reply:** It assumes ordered dependency, not metric duration. If later analysis shows that any coherent notion of re-entry requires a temporal metric rather than generative order, the chapter fails and Return must move after Time.

— — — —

Objection 2: If the resultant token is not the initial token, nothing literally returned. **Reply:** The chapter defines return at the level of higher-order identity, not numerical identity of a state token. If F cannot be independently constrained, this reply collapses and the return claim becomes observer-imposed.

— — — —

Objection 3: The equivalence relation can always be chosen loosely enough to manufacture recurrence. **Reply:** This is a major risk. F must be fixed before the trajectory is inspected, linked to previously established identity and closure criteria, and challenged under a declared perturbation class. Post hoc equivalence is not admissible.

— — — —

Objection 4: Return is closure by another name. **Reply:** Closure concerns constitutive dependency sufficiency; return requires departure and re-entry. A closed organization can fail to return, and an externally driven recurrent system can return without internal closure.

— — — —

Objection 5: Return creates a causal loop. **Reply:** Not if the terminal realization is a distinct token A_1 in the same identity class as A_0 . An identity class can recur while the event order stays strictly acyclic.

— — — —

Objection 6: A loop already presupposes topology. **Reply:** The formal criterion uses equivalence-class re-entry. Loop imagery is analogical, and topology must be earned later if the formalism warrants it.

Objection 7: Any finite deterministic system must eventually repeat. **Reply:** That result depends on finiteness, determinism and closed state evolution, none of which is presently assumed. More importantly, combinatorial repetition is weaker than robust return to an independently meaningful higher-order identity.

Objection 8: Poincaré recurrence already explains return. **Reply:** Poincaré recurrence presupposes a measure-preserving dynamical system on an appropriate finite-measure state space and an evolution parameter. It is a later formal analogue, not a foundational derivation.

Objection 9: Path-dependent return is already memory. **Reply:** It is retained consequence. Memory is reserved for systems in which retained distinctions become internally consequential within a self-maintaining organization (Memory).

Objection 10: Structural selection by return is teleology in disguise. **Reply:** The speculative selection claim requires no goal. Return-compatible structures may simply be re-instantiated or remain relationally available. If the model explicitly rewards return, the mechanism is invalid.

Objection 11: A return predicate adds a new primitive. **Reply:** $\text{Ret}(A_F; \cdot)$ is shorthand for departure plus oriented transformation plus re-entry into a previously defined equivalence class. If an additional primitive operator turns out to be required, it must be declared.

Objection 12: Orientation may not be necessary for return. **Reply:** This remains open. Unordered recurrence may be definable more weakly. Return concerns ordered return inherited from Orientation, and Formalism should test whether orientation is necessary or merely one sufficient route.

8.27 What Return Has Not Yet Earned

Metric time, temporal duration, period or frequency.

Synchronization between recurring relational modes.

Spatial circularity, orbit, rotation or geometric loop.

Topology, homotopy class or physical winding number.

Physical phase or angular coordinate.

Causal loops or closed timelike curves.

Poincaré recurrence as a physical theorem of this model.

Entropy, thermodynamic irreversibility or an arrow of time.

Biological or cognitive memory.

Oscillation, wave propagation or resonance.

Conservation laws.

A universal principle that all persistent structures must return.

A proof that return-compatible structures are generically selected.

The refusal to claim these results is part of the derivation. Return earns one identifiable layer: ordered identity recurrence after nontrivial transformation.

8.28 Ontological Defensibility Pulse: Return

This is the chapter's Pulse sidebar. It applies to the central proposition. It is set apart from our argument so that a reader can skip it on a first pass.

Pulse question	Applied to Return
1. Entities required	No new substance: identity classes O_F , organizational anchors A_F , configurations, orientation, admissible transformations, and $\mathcal{U}$
2. Ontological level	Pre-geometric and pre-metric recursive organization: from oriented dependency to identity-class recurrence
3. Lower-order dependencies	Difference, Distinction, retention, mutual constraint, structural persistence, closure, addressability, A_F , and orientation
4. New emergent properties	Re-entry into an independently specified identity class after departure, and non-identical recurrence within preserved identity
5. Claim types	Formal and relational at the core; interpretive on recurrence and persistence; speculative on selection and pre-phase

Pulse question	Applied to Return
6. New primitives	Ideally none. $\text{Ret}(A_F; \cdot)$ is a predicate over already defined relations, not a new ontological operation
7. Fewer assumptions?	Strengthens if return follows from generic recursive constraints, not an encoded cycle, and F is fixed independently
8. Observational constraints	Test non-hardcoded return, robustness, coarse-graining dependence, reversal asymmetry, token and type, nested return

Return tightens the ontology only if return is genuinely decomposable into previously earned identity, transformation, orientation, departure and re-entry. If a special return operator, a hidden clock, a target cycle or a post hoc equivalence criterion must be inserted, the derivation has not succeeded.

8.29 Implications and Handoff

Return gives the ontology something Closure alone did not supply: an earned organizational reference A_F can be left and its identity class O_F can later be recovered after nontrivial oriented transformation.

That matters because comparison becomes far more powerful once the same relational standard can appear again. Yet we still lack a common formal language for deciding which comparisons are legitimate.

Formalism therefore changes our vantage once more. We step back from the individual structures and ask whether they can all be represented inside one disciplined formal view without mistaking the view for the world.

For the first time, an endogenous reference can be recurrently re-addressed after genuine departure. The framework still lacks the mathematical right to quantify that reuse as period, phase, winding, or metric recurrence.

Handoff to Formalism. What mathematical relations are now justified by the structure already earned, and which formal operations would merely smuggle in metric, geometric, probabilistic or temporal assumptions?

The same higher-order identity can now return without the underlying state repeating.

Questions Opened by This Framework

What is the weakest non-circular identity invariant sufficient to make return objective rather than observer-imposed?

Is orientation strictly necessary for return, or only for ordered return?

Can robust return emerge under generic local relational rules without a hard-coded cycle?

Can a system be recurrent at a higher-order resolution while never repeating any lower-order microstate?

What forms of coarse-graining preserve return, and what forms manufacture or erase it?

Can return remain robust under perturbation without collapsing into trivial persistence?

When is the identity domain Dom_F objectively constrained rather than chosen for descriptive convenience?

Does anchor-relative reversal failure supply a necessary precursor to a later temporal arrow, or is it orthogonal to thermodynamic asymmetry?

Can multiple independent orientational modes re-enter the same O_F relative to A_F under different internal conditions?

Can nested return structures generate stable hierarchies of identity without metric scale?

What additional formal structure is required before a return count becomes a winding number or a phase?

Can recurring relational structures provide endogenous standards for scale without an external unit?

Under what conditions does retained consequence across return become usable memory rather than passive path dependence?

Do return-compatible structures become more prevalent under recursive dynamics without explicit selection rules?

What result would falsify the claim that return is derived rather than encoded?

Selected References Cited in Return

Kemeny, J. G., & Snell, J. L. (1960). *Finite Markov Chains*. The University Series in Undergraduate Mathematics. Princeton: D. Van Nostrand. Reissued by Springer (1976) in Undergraduate Texts in Mathematics.

Montévil, M., & Mossio, M. (2015). Biological organisation as closure of constraints. *Journal of Theoretical Biology*, 372, 179–191. <https://doi.org/10.1016/j.jtbi.2015.02.029>

Noonan, H. W., & Curtis, B. L. (2018). Identity. In *The Stanford Encyclopedia of Philosophy*. Used only for the distinction between criteria of identity and qualitative change.

Saussol, B. (2009). An introduction to quantitative Poincaré recurrence in dynamical systems. *Reviews in Mathematical Physics*, 21(8), 949–979.

Surya, S. (2019). The causal set approach to quantum gravity. *Living Reviews in Relativity*, 22, 5. <https://doi.org/10.1007/s41114-019-0023-1>

Note on these references. These works are mathematical analogues, comparison classes or later-stage formalisms; none is evidence for the ontology proposed here. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 9

Formalism: When Relations Become Calculable

Claim ~ Formalism becomes justified when the relational commitments already earned can be represented in one composable structure whose operations preserve their intended meanings using only what has been earned.

Chapter discipline. This chapter inherits everything earned from Difference through Return, from $\mathcal{U}$ and $<$ to the organizational anchor A_F and $\text{Ret}(A_F; \cdot)$. Its burden is to state the weakest common formal carrier that preserves the meanings already earned from Difference through Return.

- distinction $\rightsquigarrow$ retention $\rightsquigarrow$ structure $\rightsquigarrow$ closure $\rightsquigarrow$ orientation $\rightsquigarrow$ return $\rightsquigarrow$ formal admissibility
- mathematical representation $\neq$ ontological identity

9.1 Where Return Leaves Us

Chapters 2 through 8 have given us local tools: Difference, admissible succession, retained distinction, mutual constraint, closure, endogenous reference, orientation and Return. Formalism changes perspective from using those structures locally to asking whether they fit inside one coherent formal frame without changing their ontological types.

From that vantage we can compare configurations, follow admissible transitions, tell frame equivalence from identity equivalence, and track retained and oriented dependency. We can also ask when a higher-order identity O_F supports representative-independent dynamics, with its organizational anchor A_F remaining a role of that identity rather than a primitive point.

The danger grows with the power of the view. A convenient graph, matrix, quotient, or transition system can clarify our ontology. It can also smuggle in structure our ontology never earned. Our task is to keep encoding and commitment separate.

The task is twofold. We need a formal carrier in which the earned concepts can coexist and compose. A rule for distinguishing structure that belongs to our ontology from structure introduced only because a particular encoding makes calculation easy. The foundational question is what the weakest common formal structure is in which identity, transformation, closure, orientation and

return can be represented together. At the same time, every stronger mathematical commitment remains either derived or explicitly external.

■ Seven chapters of local mathematical devices can be stated in one place, which is a precondition for checking them against each other. Open question: whether the carrier proposed here is the weakest adequate one (Question 1).

9.2 Formalism Is Not Ontology

The first discipline of the chapter is negative. A graph representing a relational domain does not make reality a graph. A matrix recording relations does not make our ontology linear algebra. A simplex realizing a closed incidence pattern does not make simplices primitive. A category organizing compositions does not turn objects and morphisms into substances.

■ representation of $X \neq$ ontological identity of X

This distinction has run through the book. Formalism must make it explicit, because formal power increases the risk of ontological smuggling.

Mathematics arrives in bundles. A vector space brings scalar multiplication and addition. An inner product brings angle and norm. A topology brings neighborhoods and continuity. A probability space brings a measure. None of that is free merely because a later theory may need it.

A formalism is admissible in one of three ways. It may directly encode structure already earned, it may define a new structure from what has been earned, or it may be used as external representational machinery while being denied ontological force.

■ formal resource = inherited $\vee$ derived $\vee$ explicitly representational

Anything else is explanatory debt.

9.3 The Formal Admissibility Rule

Formal Admissibility Rule. A symbol, operator, relation or construction may perform ontological work only when its content is inherited from earlier chapters or definable from inherited structure. Richer mathematics may be used externally for proof, simulation or bookkeeping, but its additional structure must not be silently read back into the modeled world.

The rule generalizes the discipline already used in Closure's simulations. An external program may count iterations even when our ontology has no intrinsic clock. A researcher may store relations in a matrix package without granting our ontology a vector space.

■ metalanguage richness $\neq$ object-language richness

From this chapter onward the book will freely use ordinary mathematics to study our model. The burden is to identify which parts of that mathematics are claims about our model itself.

9.4 The Minimum Relational Signature

A candidate carrier can be stated very weakly. Let $\mathcal{C}$ be a collection of admissible relational configurations, $\mathfrak{R}$ the family of relations resolved within those configurations, and $\mathcal{U}$ the admissible transition relation between configurations.

■ $\mathfrak{G} = (\mathcal{C}, \mathfrak{R}, \mathcal{U})$

$\mathcal{P}$, $<$, $<_o$, $\sim_w$, $\sim_F$, O_F , A_F and $\text{Ret}(A_F; \cdot)$ are not added as primitive components of $\mathfrak{G}$: they are inherited or derived structures defined over the carrier.

$\mathcal{C}$ is not assumed to be a vector space, manifold, topological space, probability space or metric state space. It is only the collection over which the earned relational descriptions range. $\mathfrak{R}$ is not restricted in advance to binary relations. $\mathcal{U}$ retains the type fixed in Distinction: an admissible transition relation on configurations. Formalism consolidates that typing rather than revising it.

■ $\mathcal{U} \subseteq \mathcal{C} \times \mathcal{C}$, where $\Sigma \mathcal{U} \Sigma'$ means that Σ' is an admissible successor configuration of Σ

A binary relation can be represented as a subset of a Cartesian product. Relational composition can be defined without assuming uniqueness of output. Standard relation theory supplies the mature analogue. Closure, orientation and return are not added as new primitive components of $\mathfrak{G}$. They remain predicates or derived structures over it.

9.5 Admissible Transition Remains Relational

Distinction already typed $\mathcal{U}$ as a relation rather than a function. Formalism now makes the consequence explicit at the general configuration level: no unique successor is implied unless uniqueness is separately earned. For a configuration Σ , define its successor set:

■ $\mathcal{U}[\Sigma] = \{ \Sigma' \in \mathcal{C} : \Sigma \mathcal{U} \Sigma' \}$

Successor structure can therefore be characterized by quantification before Scale licenses internal cardinal magnitude. A configuration may have no

admissible successor, exactly one, or several. Determinism is a property of $\mathcal{U}$ on a specified domain, not part of $\mathcal{U}$'s primitive type.

Successor set	Condition	Interpretation
Empty	No Σ' satisfies $\Sigma \mathcal{U} \Sigma'$	No admissible continuation under the present rule
Singleton	Exactly one Σ' satisfies it	Deterministic continuation at this resolving level
Multiple	At least two distinct Σ' satisfy it	Branching admissibility, not yet probability or randomness

Where every admissible configuration has one and only one successor, the relation admits a functional representation on that domain. An external analyst may write $|\mathcal{M}[\Sigma]| = 1$ as bookkeeping; the modeled ontology need only state uniqueness by quantification. Branching is equally compatible with the relational type and introduces no probability measure by itself.

Branching does not imply stochasticity: no weights have been assigned. Nor does it establish metaphysical indeterminism. A coarse resolving frame may merge fine-grained states whose distinct successors remain unresolved. The same effective state can have several admissible successors even if a finer description is deterministic.

■ effective branching $\neq$ fundamental randomness

What this preserves from Orientation. Orientation already treats $\mathcal{U}$ relationally. Symmetry arguments must therefore distinguish two claims: covariance of the admissible successor relation, and selection of a particular successor trajectory. Equivariance can constrain the set $\mathcal{M}[\Sigma]$ without forcing one member to be selected. Orientation is carried by persistent consequential asymmetry, represented by $\prec_0$, not by assuming deterministic evolution.

■ Determinism is a special case of admissible transition, not a presupposition of the notation. Open question: the exact conditions under which an F-equivalence supports well-defined quotient dynamics for branching transitions (Question 2).




Figure 9.1. A configuration may have no successor, exactly one, or several; determinism is the special case of exactly one. Roads show the three cases as a dead end, a corridor and a junction. Branching seen at a coarse resolution need not be randomness: each car approaching a fork already has its route, yet “a car on this road” could go either way.

9.6 Trajectories Without Metric Time

Once $\mathcal{U}$ is relational, a trajectory is a composable chain of admissible transitions.

$$\blacksquare \Sigma_0 \mathcal{U} \Sigma_1 \mathcal{U} \Sigma_2 \mathcal{U} \dots \mathcal{U} \Sigma_k$$

The index orders the written sequence; it does not measure duration. This preserves the distinction developed in Boundary, Orientation and Return between dependency order and physical time. If $\mathcal{U}$ later becomes causal or temporal, that will take additional structure.

$$\blacksquare \text{transition order} \neq \text{elapsed duration}$$

9.7 Composition and Identity

Relations compose when the output side of one matches the input side of another. This ordinary relation theory defines by quantifying over an intermediate state.

■ $\Sigma (\mathcal{U} \circ \mathcal{U}) \Sigma'' \iff$ there exists Σ' such that $\Sigma \mathcal{U} \Sigma'$ and $\Sigma' \mathcal{U} \Sigma''$

This gives earlier talk of repeated application a precise meaning without requiring $\mathcal{U}$ to be functional. $\mathcal{U}^2$ is $\mathcal{U} \circ \mathcal{U}$, and $\mathcal{U}^k$ is k compositions. An identity relation is also available.

■ $\text{Id}_{\mathcal{C}} = \{ (\Sigma, \Sigma) : \Sigma \in \mathcal{C} \}$

That such a relation exists does not mean nothing changes whenever identity holds. Return already separated exact state identity from higher-order equivalence. A nontrivial transition may preserve F without being the identity relation.

■ $T \neq \text{Id}_{\mathcal{C}}$ while $T(\Sigma) \sim_F \Sigma$

9.8 Invertibility Is Not Return and Not Physical Reversibility

Composition permits an inverse relation, or an inverse map in the functional case, and three ideas must not collapse together.

■ algebraic invertibility $\neq$ identity-class return $\neq$ physical reversibility

If T has an inverse, that inverse formally recovers its input under the declared encoding. Return's return is weaker: a later state need only re-enter the anchor's identity class. Physical reversibility is stronger in a different direction, requiring the formal inverse to correspond to an available process. A process may therefore return without being invertible, since a many-to-one transformation can erase lower-order detail while later dynamics reconstitutes an F -equivalent identity. And an invertible map need not be traversable in both directions.

Keeping these apart prevents the irreversibility criterion of Orientation and Return from being replaced by a purely algebraic notion.

9.9 Equivalence Is Not Yet Congruence

Boundary through Return rely on identity equivalence, written $\Sigma_a \sim_F \Sigma_b$. That two configurations instantiate the same higher-order identity does not yet

guarantee that admissible succession treats their equivalence classes compatibly.

Universal algebra names an equivalence relation compatible with the relevant operations a congruence. If equivalent inputs always give equivalent outputs, the classes inherit a well-defined quotient structure. This is the formal precedent closest to the addressability criterion of 6.12. For a deterministic special case compatibility requires:

$$\blacksquare \Sigma_a \sim_F \Sigma_b \Rightarrow QF(\mathcal{M}[\Sigma_a]) = QF(\mathcal{M}[\Sigma_b])$$

For a branching $\mathcal{U}$ the criterion is weaker and trajectory-sensitive. Equivalent representatives must have successor behavior that can be matched at the quotient level.

■ equivalence $\rightsquigarrow$ transformation-compatible equivalence $\rightsquigarrow$ quotient-level dynamics

We should not declare every F-equivalence a congruence. It should ask which identity criteria are strong enough to support one.

■ Equivalence and compatibility are different demands, and only the second supports quotient dynamics. Open question: whether exact congruence is too strong for physical and biological systems (Question 10).

9.10 Quotient Structure and Higher-Order Identity

If $\sim_F$ partitions admissible configurations into equivalence classes, let $QF(\Sigma) = [\Sigma]_{\sim_F}$ and write $\mathcal{C}/\sim_F$ for the quotient collection. Closure interprets a dynamically persistent class $O_F = [\Sigma]_{\sim_F}$ as a candidate higher-order identity and, where representative-independent addressability is available, that identity can function in the organizational anchor role A_F . Formalism now asks whether admissible succession also descends to those classes.

$$\blacksquare [\Sigma]_{\sim_F} \mathcal{U} [\Sigma']_F \text{ whenever } \Sigma \mathcal{U} \Sigma'$$

For this to be legitimate, choosing a different representative of $[\Sigma]_{\sim_F}$ must not change the higher-order result in a way that destroys the quotient description. That gives the chapter its strongest candidate formalization of higher-order autonomy. When lower-order realizations form an equivalence class and admissible transformations descend consistently to that class, the higher-order identity supports dynamics independent of any arbitrary choice of lower-order representative.

■ quotient-compatible dynamics $\Rightarrow$ higher-order formal autonomy

That is stronger than saying quotienting is a convenient description and weaker than claiming all genuine emergence must be quotient structure. The chapter adopts the middle claim: quotient-compatible dynamics is sufficient for a form of higher-order autonomy. Is not asserted to be necessary for every emergent phenomenon.

■ Emergence acquires a testable criterion rather than a metaphor, and 9.27 shows the criterion failing on a small example. Open question: whether approximate rather than exact quotient autonomy can be formalized once comparison is earned (Question 3).

9.11 Lumpability as a Later Probabilistic Analogue

Closure's addressability condition has a recognized analogue in stochastic dynamics. Kemeny and Snell's theory of lumpability asks when a Markov chain projected onto blocks of states remains a well-defined Markov chain. The probabilistic theorem is richer than anything available here, since it presupposes transition probabilities, but its structural lesson holds. Coarse-graining is dynamically legitimate only when the lower-order distinctions being ignored do not create ambiguous higher-order evolution.

■ well-defined quotient dynamics now; probabilistic lumpability later, if probability is earned

Coarse-graining can also be mathematically useful without making every coarse-grained category ontologically real. The additional claim of higher-order autonomy requires stability and well-defined dynamics, not merely a partition.

9.12 Structural, Frame and Behavioral Equivalence

The framework now contains several kinds of sameness that must remain notationally distinct. Identity equivalence, $\Sigma_a \sim_F \Sigma_b$, says that the configurations satisfy the same identity criterion F . Frame equivalence, $\Sigma_a \sim_W \Sigma_b$, says that resolving frame W cannot discriminate them. Behavioral equivalence, written provisionally $\Sigma_a \approx_{\mathcal{U}} \Sigma_b$, says that they support matching patterns of admissible succession.

■ $\sim_F$, $\sim_W$ and $\approx_{\mathcal{U}}$ are not interchangeable

These can overlap without being identical. Two configurations may be structurally the same object while a finer frame resolves internal differences. They may be frame-equivalent yet behave differently under a transformation invisible to that frame. And behavioral equivalence can be stricter than the

identity criterion F. The distinction stops the book sliding between ontic identity, observer resolution and dynamical similarity.

9.13 Bisimulation as a Candidate Maximal Behavioral Criterion

Transition-system theory supplies a mature concept for matched behavior. If one state can make a transition, a bisimilar state must be able to make a corresponding transition into a state that remains related, and conversely.

- $a \approx b$ and $a \mathcal{U} a' \Rightarrow$ there exists b' with $b \mathcal{U} b'$ and $a' \approx b'$

Bisimulation is useful because it tests equivalence against future relational possibilities rather than present appearance. It should not be promoted to our definition of all object identity. Two realizations may preserve F while differing in some admissible futures.

- bisimulation = candidate strong behavioral equivalence, not universal identity criterion

Open question: whether higher-order identity can be constrained behaviorally without collapsing into bisimulation (Question 4).

9.14 Return as Quotient Recurrence

Return can now be restated economically in the formal carrier. Let $O_F = [\Sigma_0]_{\sim F}$ be the higher-order identity whose Closure-earned organizational reference role is A_F . A later configuration Σ_k may differ from Σ_0 while re-entering O_F after genuine departure.

- $[\Sigma_0]_F = [\Sigma_k]_F$, while $\Sigma_0 \neq \Sigma_k$

At the quotient level, a return-capable trajectory may be represented as $O_F \mathcal{U} \dots \mathcal{U} O_F$. This does not mean the anchor role A_F is itself a state token that loops. A_F is the reference role of O_F ; the recurrence is re-entry of distinct lower-order realizations into the same identity class.

- identity-type recurrence can coexist with token-level acyclicity

9.15 Fixed Points and Identity-Class Fixed Points

A fixed point of a functional transformation satisfies $T(\Sigma) = \Sigma$. Return's return is more general, since a macro-identity can be preserved while the lower-order state changes.

- $[T(\Sigma)]_F = [\Sigma]_{\sim F}$, equivalently $\bar{T}([\Sigma]_{\sim F}) = [\Sigma]_{\sim F}$

Call this an identity-class fixed point, or quotient fixed point. It separates exact microscopic stasis from higher-order dynamical persistence. It may later connect to invariant sets, attractors, cycles and stability. Those notions usually presuppose topology or metric neighborhoods and are not imported here. We earn the distinction and defers attractor language.

9.16 Symmetry as Structure-Preserving Transformation

Orientation used exchange tests to distinguish symmetric from oriented dependency roles, and formalism can state the idea generally. Let g be a relabeling or transformation of the formal structure. If all relevant relations are preserved, g is an automorphism of that encoding. Such transformations form a group under composition.

$$\blacksquare g(\mathbb{G}) \cong \mathbb{G}$$

Orientation appears when an exchange that previously preserved the relevant structure no longer does.

$$\blacksquare g_{\text{swap}}(\mathbb{G}_{\text{oriented}}) \not\cong \mathbb{G}_{\text{oriented}}$$

This gives Orientation a cleaner formal reading. The arrow records a broken interchangeability of roles, not a primitive direction. One caution matters. Orientation should not be defined as a smaller automorphism group, since different structural changes reduce symmetry for unrelated reasons. The narrower statement is that the exchange transformation of the roles in question ceases to preserve the constraint organization.

9.17 Relations Among Relations

Once a relation is itself a stable, addressable structure, it can participate as a relatum in a higher-order relation, written schematically $\mu(r_a, r_b)$. This does not automatically create a new ontological category. The same relational grammar may be recursively re-instantiated at a higher organizational level.

$$\blacksquare \text{relation} \rightsquigarrow \text{closed relational organization} \rightsquigarrow \text{higher-order relatum} \rightsquigarrow \text{relation among higher-order relata}$$

The line-graph building in graph theory. There, edges of one graph become vertices of another, is one encoding of the move, though the ontological claim is more general. The formal challenge is to prevent an uncontrolled type regress. If relations among relations always require a new primitive relation type, our framework proliferates categories. If higher-order relata are

equivalence classes or closed organizations of lower-order structure, recursive building can proceed with the same grammar.

- same relational grammar, new organizational level

Open question: whether relations can become relata recursively without generating an infinite hierarchy of primitive types (Question 7).

9.18 Binary Relations May Not Be Expressively Sufficient

The early ontology is written with pairwise relations r_{ij} . However, not every higher-order constraint is necessarily reducible to pairwise relations without adding auxiliary entities. General relation theory permits n -ary relations, $R(q_1, q_2, \dots, q_n)$. A graph privileges binary incidence; hypergraphs and general relational structures let one relation involve several relata jointly.

Two routes stay open. Under binary sufficiency, every higher-order constraint can be represented without loss by pairwise relations, possibly with auxiliary relational positions. Under genuine higher arity, some constraints are more faithfully represented as irreducibly n -ary at the level being modeled.

- binary convenience $\neq$ binary ontological sufficiency

The question should not be settled by convenience, and it is worth saying plainly what settling it would cost. Relation's matrix formulation and Orientation's constraint relation K_{ij} are both pairwise. If higher arity turns out to be required, those are the sections that change. This makes this one of the few open questions in Book I with a known repair bill.

9.19 Matrices Remain Representations

Matrices have appeared in Distinction, Relation and Orientation. A matrix $R = [r_{ij}]$ is an indexed array recording relational information. By itself it provides no vector addition, scalar multiplication, norm, angle, determinant, eigenvalue interpretation or physical dimension.

- matrix notation $\neq$ vector-space ontology

Those structures may become legitimate later if the entries and permitted operations justify them. The rule matters because calculations will use linear-algebra software externally. A successful calculation does not retroactively grant every algebraic operation physical meaning.

9.20 Simplicial Structure as One Realization, Not the Definition of Closure

Earlier versions of the project treated simplex formation as too close to our definition of closure. Closure corrected that: closure is relational dependency sufficiency, not geometric completion. Simplicial mathematics can nevertheless be recovered as one possible realization of nested incidence. There, a k -simplex has faces of lower dimension. The boundary operator maps k -chains to $(k-1)$ -chains, with the characteristic identity $\partial(\partial X) = 0$.

The identity matters because internal interfaces cancel under successive boundary operations. This is a useful analogy for how lower-order constitutive detail disappears from a higher-order boundary description. The implication runs one way only.

- earned closure $\rightsquigarrow$ simplicial realization may be useful
- $\partial^2 = 0 \neq$ foundational closure ontology

9.21 Finite-Order Recurrence Is First-Order on an Enlarged State

Distinction left a formal debt, using first-order update notation while noting that a recurrence can depend on several antecedent terms. Suppose $x_{n+1} = f(x_n, x_{n-1}, \dots, x_{n-k+1})$. Define an enlarged state $X_n = (x_n, x_{n-1}, \dots, x_{n-k+1})$. Then there is a first-order update F with $X_{n+1} = F(X_n)$.

- first-order state update $\neq$ historical amnesia

The lesson is not that our ontology stores a literal tuple. It is that finite historical dependence can be represented by a present state whose structure carries the needed retained consequences. This is why retained state dependence in Boundary to Return does not require an infinitely long primitive memory. Formalism earns only the state-sufficiency transformation.

9.22 Independence Before Orthogonality: Introducing d_R

Relation raised the need to distinguish independent relational modes. Formalism is the first place a candidate symbol d_R can be introduced without pretending that vector-space rank was already available. The required first step is therefore an independence structure, not a number.

Matroid theory is useful because it abstracts a notion of independence from linear algebra. Let V_R be a set of candidate relational modes and $\mathcal{J}_R$ a family of subsets satisfying whatever independence axioms the model can justify. Write the candidate independence system as $\text{Ind}_R = (V_R, \mathcal{J}_R)$. This remains

representational until the required axioms are shown to arise from the relational organization itself.

Only if a suitable finite independence structure is earned may the framework introduce a rank-like count as a candidate pre-metric relational dimensionality: $d_R := \text{rank}(\text{Ind}_R)$. This is the first legitimate introduction of d_R in the derivation. It counts independent relational modes under the declared independence criterion; it does not yet mean spatial dimension, vector-space dimension or orthogonal axes.

- independence can be formalized before orthogonality

- SPECULATIVE d_R as a matroid-rank-like count of independently variable relational modes. Orthogonality would require additional structure, typically an inner product or an equivalent earned construction, and is not licensed merely because later physics may use it.

9.23 External Counting and Internal Magnitude

Formalism must distinguish what the analyst may count from what our ontology can internally compare. The meta-theory may freely say a simulation contains a thousand nodes or that a recurrence was iterated five hundred times.

- external cardinal bookkeeping $\neq$ endogenous magnitude

In Scale, we ask when comparison itself becomes structurally available as scale. Formalism permits finite sets, indices and model sizes in the mathematics while refusing to read them as intrinsic measures available to the modeled system. This preserves the earlier distinction between quantification and counting, and between counting and measurement.

9.24 Formal Carrier, Not a Hidden Medium

Earlier manuscript stages used the word substrate for the total evolving relational structure. No additional medium is presently required beneath the relations. The formal carrier is the structured collection of relational configurations and admissible transitions themselves.

- formal carrier = relational organization under consideration

- formal carrier $\neq$ material medium beneath relation

If later physics requires a further ontological carrier, we must say so explicitly. Until then, adding a medium would duplicate explanatory work without

necessity. This resolves the word conservatively: if substrate is retained, it names the total relational structure at a given level, not a substance in which relations float.

9.25 Syntax, Semantics and the Meaning of an Arrow

Syntax is the written formal language; semantics is the relational content the symbols represent. The book therefore fixes a convention wherever an arrow-like mark could hide ontology (Appendix A.2): $\rightsquigarrow$ marks derivational progression; $\mapsto$ marks an explicit map, coupling or update of a particular item; $<$ marks retained-dependency precedence and $<_{\circ}$ oriented dependency; and $\mathcal{U}$ itself states admissible succession. The plain $\rightarrow$ marks only a map between sets or a limit, and $\Rightarrow$ marks logical implication; neither denotes dependency, orientation, coupling or time.

■ same glyph $\neq$ same semantic relation

Formalism therefore requires typed notation, and a notation ledger should specify for every operator whether it denotes a relation, a function, a predicate, an equivalence, a representational sequence or an external bookkeeping device. This is not cosmetic: type ambiguity can create apparent derivations by moving illicitly between meanings.

9.26 Candidate Formal Core

The results so far support a deliberately weak core, $\mathbb{G} = (\mathcal{C}, \mathfrak{R}, \mathcal{U})$, with:

$\mathcal{C}$, admissible relational configurations, with no assumed metric, topology, vector structure or probability measure.

$\mathfrak{R}$, the family of earned relations, not restricted in advance to one arity.

$\mathcal{U} \subseteq \mathcal{C} \times \mathcal{C}$, the admissible transition relation.

$\sim_F$, inherited structural equivalence induced by declared identity criteria.

$\mathfrak{T}$, declared transformation and test classes used to state invariants.

Derived predicates and structures: PresW and retained r_{ij} ; reachability $\mathcal{P}$; retained-dependency precedence $<$; identity equivalence $\sim_F$ with $O_F = [\Sigma]_{\sim_F}$; Closed_F; representative-independent higher-order addressability; organizational anchor A_F ; oriented dependency $<_{\circ}$ and orientation structure $\mathfrak{O}$; and Return, written $\text{Ret}(A_F; \cdot)$.

The core is compatible with several concrete encodings. Graphs, hypergraphs, transition systems, relation algebras, simplicial complexes and categorical

descriptions may each capture part of the same content. The ontological commitment belongs to what survives faithful changes of encoding, not to the machinery of one notation.

■ representation-invariant relational content = candidate ontological commitment

This is representational pluralism with a minimal common core, not formal relativism. Different encodings are admissible only insofar as they preserve the earned structure.

9.27 Worked Example: When a Macro-Identity Has Well-Defined Dynamics


A minimal example shows why equivalence alone is insufficient. Let $\mathcal{C} = \{a, b, c, d, e\}$. Let an identity criterion F give $a \sim_F b$ and $c \sim_F d$, with e forming its own class. Write the quotient identities $O1 = [a]_{\sim_F}$, $O2 = [c]_{\sim_F}$ and $OE = [e]_{\sim_F}$. Suppose the transition relation contains $a \mathcal{U} c$, $b \mathcal{U} d$, $c \mathcal{U} e$ and $d \mathcal{U} e$. At the quotient level both representatives of $O1$ lead to $O2$, and both representatives of $O2$ lead to OE .

■ $A \mathcal{U} B \mathcal{U} E$

The macro-dynamics is well defined even though a and b are distinct lower-order states. Now change one transition, so that $a \mathcal{U} c$ and $b \mathcal{U} e$. Then a and b are still F -equivalent. However, their higher-order successors differ, since $[c]_{\sim_F} = B$ and $[e]_{\sim_F} = E$ with $B \neq E$. The quotient update from A is now ambiguous unless the macro-rule explicitly allows both branches. A claim of deterministic higher-order dynamics would fail.

The example shows three things. An equivalence class can define a higher-order identity without yet defining higher-order dynamics. Transformation compatibility is the extra burden required for autonomous quotient dynamics. And determinism can differ by level: a deterministic micro-rule may become branching after coarse-graining. Branching micro-rules can collapse to one macro-successor when all branches land in the same class.

Return can be added by extending the example with $e \mathcal{U} b$. If $O1$ is dynamically closed and functions in an organizational reference role A_F , the lower-order trajectory $a \mathcal{U} c \mathcal{U} e \mathcal{U} b$ is not exact repetition, while the quotient trajectory $O1 \mathcal{U} O2 \mathcal{U} OE \mathcal{U} O1$ re-enters the identity class referenced by A_F .



One transition is the whole difference. Where members of a class do not agree on where they go, the higher description cannot be used without dropping back to the lower one.

A call centre can route by customer tier until one caller in the tier has to be routed by name.

Figure 9.2. Quotient compatibility, and the single transition that decides it. Two states form the class [X] and two more form [Y]. On the left both members of [X] transition into [Y], so the higher-level transition from [X] to [Y] is well defined. On the right one member goes elsewhere, and [X] no longer has a single successor class. The everyday counterpart is a call centre routing by customer tier until one caller in that tier has to be routed by name. The insight is how little separates the two cases: one transition is the whole difference, and where the members of a class disagree about where they go, the higher description cannot be used without dropping back to the lower one.

9.28 Computational Diagnostics

A computational implementation may use richer mathematics than our ontology, subject to 9.3. The following checks should be routine.

Representation invariance. Relabel states or use an alternative faithful encoding; claimed ontological results should survive.

Transition typing. Verify whether $\mathcal{U}$ is relational, functional, total, partial, deterministic or branching rather than assuming one case.

Compatibility test. Check whether the chosen F-equivalence supports a well-defined quotient transition.

Quotient return. Test whether higher-order recurrence can occur without lower-order state repetition.

Coarse-graining determinism test. Determine whether determinism is preserved, created or destroyed by the quotient.

Behavioral-equivalence comparison. Compare F-equivalence with a stronger bisimulation-like criterion.

Higher-arity test. Compare binary encoding with an n-ary or hypergraph representation and check whether invariants change.

Relations-among-relations test. Reify lower-order relations as higher-order relata and verify which structural properties survive.

Simplicial realization. Where a simplicial representation is used, verify boundary identities such as $\partial^2 = 0$ without reading them as foundational closure.

Finite-order recurrence reduction. Verify the equivalence between a k-th order recurrence and a first-order update on an enlarged state.

Independence test. Explore whether a matroid-like independence system reproduces the pre-vector-space notion of d_R .

Falsification guardrail. If a formal result depends on structure that exists only because the chosen representation inserted it, whether coordinates, metric, directed edges, linear combinations, probabilities or target cycles, the formalism has exposed an unearned assumption rather than derived an ontological property.

9.29 Comparison of Candidate Formal Languages

The table ranks candidates for encoding, not for adoption. A language enters our ontology only by the admissibility rule of 9.3. No row below is declared to be our ontology.

Formal language	What it gives	Main risk	Role here
General relational structure	Arbitrary n-ary relations	Very weak operational guidance	Baseline meta-language
Transition system	Admissible state-to-state behavior	May over-emphasize state tokens	Core candidate representation
Graph	Pairwise incidence and connectivity	Binary and adjacency bias	Useful representation
Hypergraph	Collective n-ary incidence	Higher arity may be representational rather than ontic	Candidate where pairwise encoding distorts
Relation algebra	Identity, converse, composition of relations	Binary-relation emphasis	Useful algebraic layer
Universal algebra, congruence	Compatibility, quotients, homomorphisms	Operation-first bias	Key tool for higher-order autonomy
Coalgebra, bisimulation	Behavior and transition equivalence	High abstraction overhead	Comparison tool

Formal language	What it gives	Main risk	Role here
Category theory	Typed composition and universal constructions	Too general to constrain ontology by itself	Meta-language, not foundation
Simplicial complex	Nested incidence and boundary operators	Topological and geometric over-reading	One later realization
Matroid	Independence without vector-space commitment	May not match dynamic dependence	Candidate formalization of d_R
Vector space	Linear combination, rank, basis	Imports scalars, linearity, dimension	Not yet admitted as ontology
Topological space	Neighborhood and continuity	Imports topology	Not yet earned
Probability space	Weighted alternatives	Imports measure and probability	Not yet earned

Stronger languages become ontologically relevant only when later derivations license their additional structure.

9.30 Objections and Replies

Objection 1: Set-theoretic language already assumes objects. **Reply:** Yes, at the meta-language level. Using a collection $\mathcal{C}$ does not establish that the modeled ontology consists of primitive set-theoretic individuals, and a different foundational mathematics could encode the same content. The claim concerns representation, not the metaphysics of sets.

— — — —

Objection 2: Calling $\mathcal{U}$ a transition relation still smuggles in becoming. **Reply:** $\mathcal{U}$ is already the second foundational commitment introduced in Distinction: a constraint on admissible succession, not metric time or physical becoming. Formalism preserves that typing. If even succession cannot be justified in an eventual physical realization, the problem reaches back to the foundation rather than being created here.

— — — —

Objection 3: A quotient is only coarse-graining by an observer. **Reply:** It can be. The framework distinguishes frame equivalence from structural equivalence, and a quotient acquires ontological significance only when the identity criterion is independently constrained and the relevant dynamics descends to the classes.

— — — —

Objection 4: Congruence language presupposes algebraic operations the ontology lacks. **Reply:** The chapter uses congruence as a precedent for compatibility, not as a declaration that $\mathfrak{G}$ is a universal algebra. The requirement is representation-

independent: equivalent lower-order realizations must not generate contradictory higher-order dynamics.

Objection 5: Why not use category theory from the start? **Reply:** It is excellent for composition and representation independence, but its generality does not identify which objects and morphisms the ontology has earned. Better used as a meta-language unless a specific construction carries explanatory content.

Objection 6: Why not use graph theory? **Reply:** Graphs are efficient when relations are binary, but nodes and edges tempt readers to import adjacency and locality. General relational structure keeps those optional.

Objection 7: A branching $\mathscr{W}$ means the theory is indeterministic. **Reply:** No. Branching records multiple admissible successors at the represented level. Finer distinctions or later probability structure may change the interpretation, and determinism is the singleton-successor case.

Objection 8: If equivalence classes can have autonomous dynamics, emergence has been solved by definition. **Reply:** No. The burden is to show that an independently motivated equivalence relation is compatible with actual admissible transformations, and many arbitrary partitions fail that test, as 9.27 demonstrates.

Objection 9: Bisimulation should define identity because it is behaviorally exact. **Reply:** It may be too strong. A higher-order identity can preserve F while permitting different lower-order futures, so bisimulation is a strong comparison criterion rather than the universal definition.

Objection 10: Matroid independence is linear algebra in disguise. **Reply:** Matroids abstract properties of independence shared by linear systems but apply more broadly. Their relevance is that they permit formal independence without granting an inner product or orthogonality.

Objection 11: The formal core is too weak to predict anything. **Reply:** That is acceptable here. Formalism's job is to expose the lawful structure inherited by later chapters, and predictive power should arise when additional structure is earned rather than inserted.

Objection 12: Representational pluralism makes the ontology unfalsifiable, since one can always switch formalisms. **Reply:** The opposite should hold. A claimed ontological result must survive faithful changes of representation, and one that exists in a single encoding is downgraded to representational artifact.

— — — —

Objection 13: First-order enlargement merely hides memory in the state. **Reply:** Correct, and that is the point. Finite historical dependence can be represented in present state structure. The result does not establish biological memory; it shows that first-order notation is compatible with retained state dependence.

— — — —

Objection 14: Quotient autonomy may be only approximate in real systems. **Reply:** Likely. Exact compatibility is an ideal formal case, and later chapters may need graded or effective autonomy. Formalism establishes the exact benchmark without claiming all higher-order organization satisfies it.

9.31 What Formalism Has Not Yet Earned

Metric distance, length, duration, speed, angle or norm.

Vector-space structure, inner products, orthogonality or basis vectors.

A physical topology, manifold, continuum or coordinate chart.

Probability weights, stochastic dynamics or quantum amplitudes.

Physical causality or a causal cone.

A Hamiltonian, action, energy or field equation.

A claim that reality literally is a graph, matrix, simplex, category, automaton or quotient algebra.

A universal claim that every emergent entity must be a quotient structure.

A proof that binary relations suffice for every higher-order constraint.

A proof that physical or spatial dimensionality is d_R , or that d_R must equal a matroid rank in every realization.

A proof that determinism is fundamental, or that indeterminism is.

A physical interpretation of fixed points, attractors or recurrence periods.

Numerical scale, proportion or measurement units, and physical dimensionality.

We earn something narrower but foundational. A common formal language in which the earlier ontology can be expressed, transformed and quotiented without silently importing later physical structure.

9.32 Ontological Defensibility Pulse: Formalism

This is the chapter's Pulse sidebar. It applies to the central proposition. It is set apart from our argument so that a reader can skip it on a first pass.

Pulse question	Applied to Formalism
1. Entities required	No new substance: configurations, relations, transitions, equivalence criteria and transformation classes from from Origin to Return
2. Ontological level	Pre-metric relational organization made explicit as a composable mathematical structure
3. Lower-order dependencies	Distinction, retention, resolvability, constraint, invariance, closure, addressability, orientation, precedence, return
4. New emergent properties	Formal composability, transition typing, compatible equivalence, quotient dynamics, representation-invariant autonomy
5. Claim types	Formal at the core; interpretive on the representation boundary; speculative on matroid independence and arity
6. New primitives	None: $\mathcal{U}$ weakens from function to relation, and quotient and congruence language build on inherited structure
7. Fewer assumptions?	One weak signature replaces several chapter-local devices, with no metric, geometric, probabilistic or temporal commitment
8. Observational constraints	Indirect: internal consistency, representation invariance, the diagnostics of 9.28, and whether later chapters can build on the core

9.33 Implications and Handoff

Formalism leaves us with a new kind of visibility. The structures earned from Difference through Return can now be compared inside one common language without collapsing their types. Higher-order identity O_F , organizational reference A_F , retained dependency $<$, oriented dependency $<_o$ and Return can be represented alongside admissible succession without turning any of them into metric or temporal primitives.

But the view is still qualitative. It distinguishes same from different, dependent from independent, and recurrent from non-recurrent. It does not yet tell us how much.

Scale changes the lens from kind to magnitude. We ask whether comparison itself can acquire an internally grounded scale before any ruler, coordinate, or metric distance exists.

■ lower-order multiplicity + compatible equivalence $\rightsquigarrow$ autonomous higher-order description

Return can then be understood as quotient recurrence, deterministic evolution as the singleton-successor case of a more general transition relation. Finite historical dependence as first-order evolution on a sufficiently specified state.

Yet our framework still lacks magnitude. It can say that structures are equivalent or distinct, dependent or independent, compositionally related or recurrent. It cannot say how large a difference is, how one relational organization compares in magnitude with another, or whether a recurring relation establishes a stable proportion.

Handoff to Scale. Once comparison is formally legitimate, when can comparison carry magnitude without importing an external ruler?

■ Formalism tells us when structures can be compared; Scale asks when comparison becomes magnitude.

Questions Opened by This Framework

Is a transition relation the weakest adequate representation of generative update, or can $\mathcal{W}$ be reduced to a more general relational dependency already present in $\mathcal{R}$?

Under what exact conditions does an F-equivalence support well-defined quotient dynamics for branching transition systems?

How should approximate, rather than exact, quotient autonomy be formalized once a notion of comparison is earned?

Can higher-order object identity be constrained by behavioral equivalence without collapsing identity into bisimulation?

Which distinctions in Relation to Return are representation-invariant across graphs, hypergraphs, transition systems and other faithful encodings?

Are genuinely n-ary relations required anywhere in the ontology, or can binary structure represent all relevant constraints without artificial helper entities?

Can relations become relata recursively without generating an infinite hierarchy of primitive types?

Does the line-graph or relation-reification construction preserve the closure and return properties that matter ontologically?

Can the three-part closure test of 6.4 be expressed as one common property of the formal core?

Does exact congruence capture too strong a notion of higher-order autonomy for physical and biological systems?

What forms of coarse-graining preserve determinism, and what forms create or erase effective branching?

Can $\sim_F$, $\sim_W$ and $\approx_{\mathcal{U}}$ be related by general inclusion theorems, or are they context-dependent?

Can matroid independence provide a non-linear, pre-metric definition of d_R adequate for later scale and dimensional analysis?

Which formal operation, if any, is needed before an independence count becomes a physically meaningful dimension?

What later evidence would force vector-space structure, topology or probability to enter as ontology rather than as external representation?

Selected References Cited in Formalism

Encyclopedia of Mathematics, entries “Binary relation” and “Congruence (in algebra)”, for standard relation composition and for equivalence compatible with operations.

Kemeny, J. G., & Snell, J. L. (1960). *Finite Markov Chains*. The University Series in Undergraduate Mathematics. Princeton: D. Van Nostrand. Reissued by Springer (1976) in Undergraduate Texts in Mathematics.

Milner, R. (1989). *Communication and Concurrency*. Prentice Hall International Series in Computer Science. New York: Prentice Hall. Standard development of bisimulation and process equivalence.

Park, D. (1981). Concurrency and automata on infinite sequences. In *Theoretical Computer Science: 5th GI Conference*, Lecture Notes in Computer Science 104, 167–183. Berlin: Springer. doi:10.1007/BFb0017309. The origin of bisimulation as a coinductive relation.

Whitney, H. (1935). On the abstract properties of linear dependence. *American Journal of Mathematics*, 57(3), 509–533. The founding paper of matroid theory.

Note on these references. These works are mathematical precedents and comparison classes; none is evidence for the ontology proposed here. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 10

Scale: When Recursion Acquires Relative Magnitude

Claim ~ Scale becomes available when relational organizations can establish stable comparisons of magnitude from correspondences recoverable within the structure itself, so that magnitude is measured by the organization's own standards.

Chapter discipline. This chapter inherits reusable higher-order identity O_F , the organizational reference role A_F , Return, quotient structure, admissible transition relations, and the candidate pre-metric independence measure d_R introduced in Formalism. Its burden is to earn how much before anything earns how far.

- formal comparability $\rightsquigarrow$ correspondence $\rightsquigarrow$ relative magnitude $\rightsquigarrow$ proportion $\rightsquigarrow$ recursive scale
- relative magnitude $\neq$ metric distance

10.1 Where Formalism Leaves Us

Formalism lets us hold the earlier ontology in one formal view. Configurations can be distinguished, transitions followed, equivalence classes recognized, and returned identities compared without committing ourselves to geometry.

Now change the question. Place two relational organizations before us and ask not whether they differ, but whether one is larger. The current frame goes silent.

Nothing is wrong with the formalism. We have simply reached the edge of what it resolves. Scale adds a new relational capacity: comparison of magnitude.

- $\mathcal{G} = (\mathcal{C}, \mathcal{R}, \mathcal{U})$

Its routes are relational trajectories:

- $\Sigma_0 \mathcal{U} \Sigma_1 \mathcal{U} \Sigma_2 \mathcal{U} \dots \mathcal{U} \Sigma_k$

We can already compare kind. We can say that two organizations are equivalent or distinct, that one relation is independent of another, or that a trajectory returns to an identity class. None of this yet tells us how much.

To make magnitude visible, we must resist the ordinary shortcut of importing numbers or a ruler. We first need a relation that can distinguish equal, greater, lesser. Eventually proportionate organization from within the structure itself.

- The map is structurally coherent and quantitatively mute
- formal comparability $\neq$ magnitude

Only after that step will a later chapter be allowed to ask how far. Scale must come before distance.

- Formalism's core supports comparison of kind while supplying nothing about amount. Open question: whether the weakest adequate notion of magnitude is cardinal, as this chapter assumes (Question 1).

10.2 Separating the Meanings of Scale

The word scale names several things in ordinary mathematics and physics. If we do not separate them now we can appear to advance while standing still.

Sense	What it means	Status here
External model scale	The analyst chooses a size, an iteration count, a plot range	Bookkeeping only, as 9.23 allows
Organizational level	One closed organization becomes a relatum at a higher level	Already available, and not magnitude
Resolution	Which distinctions a frame can resolve	Available since 4.3, and not magnitude
Comparative magnitude	One organization is the same as, larger than or proportionate to another	What this chapter earns
Metric scale	A ratio of lengths against a unit	Not earned here, and not in this volume until Distance

Two separations matter immediately. A higher organizational level is not automatically larger, and a larger organization is not automatically farther from anything.

- organizational level $\neq$ magnitude
- scale $\neq$ distance

Distance stays closed on the map until Distance.

10.3 The Shortcut That Fails

Faced with a map that has no scale bar, the obvious response is to write numbers beside the landmarks. That is exactly what we cannot do yet. Writing three here and five there, before explaining what makes three and five available, would import counting as a primitive and then discover it as a result.

- primitive numeral $\rightsquigarrow$ magnitude — not admitted as the foundational route

We can recognize individual marks. We cannot yet assume a counting stick. What we need is a weaker operation, one that reveals sameness of magnitude without first naming the magnitude.

- correspondence $\rightsquigarrow$ comparative magnitude $\rightsquigarrow$ numeral as a later label

10.4 Pairing

Take two collections of distinguishable members. Do not count them. Pair them instead, one against one.

Let A and B be finite relational organizations whose relevant members are distinguishable under the declared criterion. If every member of A matches exactly one member of B and every member of B is matched, the pairing is a bijection.

- $f : A \leftrightarrow B$

Something has been learned before any numeral: the two organizations have the same cardinal magnitude.

- $A \sim\# B$

Read plainly, A and B are the same size in the cardinal sense. This is because neither leaves a member unmatched when paired with the other. This is the first quantitative landmark in the chapter and it is still relational. No unit has been introduced and nothing has been measured.

Equinumerosity behaves as an equivalence relation, so eligible organizations group into classes sharing a magnitude.

- $A \sim\# A; A \sim\# B \Rightarrow B \sim\# A; A \sim\# B \wedge B \sim\# C \Rightarrow A \sim\# C$

We can now say “the same amount” before we possess the number that names it.

- Sameness of magnitude is definable by correspondence alone, with no numeral and no unit. Open question: whether the declared membership criterion can itself be constrained independently (10.28, and Question 5).

10.5 More and Less

The more informative case is when pairing fails. Suppose every member of A still pairs uniquely into B , but B has members left over. We need not know how many remain: the failure is itself the information, and it is an injection.

■ $f : A \hookrightarrow B$

For finite organizations this says A is no larger than B. If A injects into B while B does not inject into A, B has the greater cardinal magnitude. The standard benchmark is the Cantor–Schröder–Bernstein theorem. If each injects into the other, a bijection between them exists.

■ $A \hookrightarrow B \wedge B \hookrightarrow A \Rightarrow A \sim_{\#} B$

We have an order of magnitude without a ruler.

■ same, no larger, larger — all available before numerical labelling

We have moved from structures that differ to structures that differ in amount. This is a real transition rather than a notational one.

10.6 Magnitude as a Stable Class

A single pairing is useful; something reusable is better. Formalism showed how equivalence classes stabilize identity, and the same move works for magnitude. If $\sim_{\#}$ is equinumerosity, the magnitude class of A is:

■ $[A]_{\sim_{\#}}$

Every organization in the class pairs one to one with every other. The class captures a comparative property while ignoring which particular members carry it. The parallel with identity is exact and worth seeing:

■ object identity $[\Sigma]_{\sim_F}$; cardinal identity $[A]_{\sim_{\#}}$

The first says when different realizations count as one higher-order object. The second says when different collections count as one magnitude.

10.7 Only Now Do Numerals Arrive

With finite magnitude classes established relationally, natural-number symbols may be used as labels for them.

■ correspondence $\rightsquigarrow$ equinumerosity class $\rightsquigarrow$ cardinal label

For a finite organization A, writing $\text{mag}(A) = n$ now reads as compression. A belongs to the finite magnitude class conventionally labelled n. The numeral did not create the magnitude. It names a relation that was available first through correspondence.

This matters because earlier chapters used finite examples, indices and model sizes freely in the analyst’s metalanguage while denying them ontological force

(9.23). Scale is where finite cardinal magnitude begins to belong to the modelled world rather than to the notation, and the distinction does not dissolve.

■ external counting does not become internal magnitude because the analyst writes a number

10.8 Coming Back for Unfinished Work: Threshold Aggregation

Relation left something undone. Existential and universal aggregation reduced to quantification (5.12). However, threshold aggregation, most of them, at least three, a majority, needed cardinality and was deferred to this chapter. We can come back for it now.

Let A_P be the relations satisfying a predicate P :

■ $A_P = \{ r \in \mathfrak{R} : P(r) \}$

Before any numeral, let K be a standard finite collection. The threshold condition is relationally expressible as an injection:

■ $K \hookrightarrow A_P$

Once cardinal labels exist, the same condition compresses to $\text{mag}(A_P) \geq k$. Nothing was added to our ontology beyond comparative magnitude. A debt from Relation is paid with an instrument earned here.

■ Threshold aggregation needs no primitive beyond correspondence, which closes the Relation deferral. Open question: whether weighted aggregation, which needs more than cardinality, can be earned at all in this volume.

10.9 Magnitude Is Not Yet Proportion

We can say equal, greater and lesser. We still cannot say by what factor one magnitude differs from another.

■ $A > B$ does not yet give $\text{mag}(A)/\text{mag}(B) = r$

This is easy to miss because ordinary arithmetic supplies ratios the moment it supplies numbers. Here the two arrive separately, and the ground between them must be crossed on foot. Ordering magnitudes is weaker than comparing them by a stable proportion. Proportion is what the rest of we earn.

10.10 Comparing Part to Whole

Suppose a higher-order organization W composed of two non-overlapping sub-organizations:

$$\blacksquare W = A \sqcup B$$

The symbol is disjoint composition and implies no spatial separation. Write $\text{Cmp}(X, Y)$ for the comparative magnitude relation of X to Y . This here means only what 10.4 and 10.5 earned. Pairing succeeds, or it fails one way, or it fails the other.

What we would like to say is that the whole stands to A as A stands to B :

$$\blacksquare \text{Cmp}(W, A) \approx \text{Cmp}(A, B)$$

The difficulty looks severe. Correspondence gives same, larger and smaller between two collections. Sameness of pattern across two different pairs looks like a further thing, and the obvious way to state it is with ratios, which we do not have. The apparent choice is to assert the pattern now and justify it later, or to wait.

Neither is necessary. Take one more building that correspondence already supports. Given two organizations X and Y , form the collection of ordered pairs drawn one from each, written $X \times Y$. This needs nothing new: pairs were available from Distinction, and ordered pairs from Orientation. This earned the asymmetry of roles that makes a first and a second differ. Nothing is counted; a collection of pairs is exhibited.

Sameness of comparative form can now be stated as a single correspondence. The whole stands to A as A stands to B exactly when the pairs drawn from W and B match, one to one, the pairs drawn from A and itself.

$$\blacksquare \text{Cmp}(W, A) \doteq \text{Cmp}(A, B) \iff W \times B \leftrightarrow A \times A$$

This is cross-multiplication, written as the bijection it always was. Read the familiar form to check it: $W/A = A/B$ holds exactly when $W \cdot B = A \cdot A$. The product of two finite collections is the collection of their ordered pairs. No numeral, no ratio and no unit has been used. We have used pairing, ordered pairs, and pairing again.

The building states the part-to-whole case without a number anywhere in it. With $W = A \sqcup B$, the condition reads $(A \sqcup B) \times B \leftrightarrow A \times A$. The pairs drawn from the whole and the smaller part match the pairs drawn from the larger part with itself.

■ Proportion is definable by correspondence alone; ratio, when it arrives, represents a relation that pairing had already fixed. Open question: whether the construction extends beyond finite organizations, where products and bijections are unproblematic.

10.11 Giving the Comparison a Numerical Representation

Correspondence has given us proportion, and it is laborious. Exhibiting a bijection between $W \times B$ and $A \times A$ is exact and unwieldy, which is what notation is for. With finite cardinal magnitude available, let $\text{mag}(X)$ be the earned magnitude of X . The same relation compresses to a ratio:

■ $\text{Cmp}(X, Y) \mapsto \text{mag}(X)/\text{mag}(Y)$

and the part-to-whole pattern of 10.10 becomes statable:

■ $\text{mag}(W)/\text{mag}(A) = \text{mag}(A)/\text{mag}(B)$

The order matters and is the point. The ratio represents a comparative relation that 10.10 established by correspondence. It does not create that relation by being written. If the notation were withdrawn the relation would still hold. Read backwards, this looks like ordinary arithmetic about sizes. Read forwards, it is a compression of pairings we could have carried out one at a time.

■ Ratio is a compression of the correspondence of 10.10, not an additional primitive. Open question: whether any later result needs the ratio form rather than the correspondence behind it.

10.12 The Same Comparison Across Levels

Recursive building gives us more than one magnitude to compare. If a rule builds each level from those before it, each level has a magnitude, and consecutive levels have a comparison. What we are now able to ask. This we could not ask in Formalism, is whether that comparison stays the same as the building proceeds.

■ $\text{Cmp}(O_{n+1}, O_n)$ for successive levels of one recursive organization

This is where perspective changes: we are no longer looking at one organization and asking its size. However, standing between levels and asking whether the relation between them holds steady.

10.13 When the Scale Relation Stabilizes

Write the successive comparative ratios as $\text{mag}_{n+1}/\text{mag}_n$. If they approach a stable value λ^* ,

$$\blacksquare \text{mag}_{n+1}/\text{mag}_n \rightarrow \lambda^*$$

then λ^* functions as a stable scale factor for that recursive regime. Not every recursion converges: a ratio can oscillate, cycle, stay bounded without settling, or behave irregularly. Scale is not defined here as convergence. What the chapter establishes is that recursive composition can produce a stable comparative relation, and that when it does, the stability belongs to the relation rather than to any level's magnitude.

One more confusion is worth closing:

$$\blacksquare \text{recursion depth} \neq \text{scale}$$

The index n records which stage of the derivation we are at. It says nothing about how large anything is.

10.14 A Familiar Case: Fibonacci

Only now, with magnitude, proportion and recursive comparison in hand, is the familiar case worth approaching. Suppose a composition rule yields magnitudes satisfying:

$$\blacksquare \text{mag}_{n+1} = \text{mag}_n + \text{mag}_{n-1}$$

With the conventional starting values this produces 1, 1, 2, 3, 5, 8, 13, and so on. The statement is conditional: if relational composition produces this recurrence in magnitude, Fibonacci growth follows. Nothing in the ontology says that recursion must take this form.

$$\blacksquare \text{a familiar pattern is not evidence because we recognize it}$$

10.15 What the Case Actually Teaches

The integers are not the interesting part. The interesting part appears when we compare each term with the one before it. Writing $r_n = F_{n+1}/F_n$, the recurrence gives:

$$\blacksquare r_{n+1} = 1 + 1/r_n$$

If the ratios approach a positive fixed value r , then $r = 1 + 1/r$. As a result, $r^2 = r + 1$, whose positive solution is:

■ $\varphi = (1 + \sqrt{5})/2$

The lesson is exact and modest. The magnitudes keep changing while the relation between successive magnitudes settles.

■ changing magnitude $\rightsquigarrow$ stable inter-level proportion

That is why φ belongs here at all. It is an established example of recursive change producing stable relative magnitude. This is precisely what scale was defined to be.

10.16 Not Following It Too Far

A striking case can become a distraction. That the Fibonacci ratio approaches φ does not show that φ is a constant of emergence. Consider the general recurrence:

■ $\text{mag}_{n+1} = a \cdot \text{mag}_n + b \cdot \text{mag}_{n-1}$, with characteristic relation $\lambda^2 = a\lambda + b$

Different coefficients select different dominant ratios. The safe conclusion is narrow: φ is one fixed ratio generated by one recurrence. Any stronger claim would need an independent reason why our ontology should prefer $a = b = 1$, and we have none.

■ stable recursive scaling $\nrightarrow \varphi$

○ SPECULATIVE Nothing here privileges φ . The Register records golden-ratio universality as Rejected, and this section is where that rejection is demonstrated rather than asserted.

10.17 Scale as a Relational Fixed Point

The case generalizes. Let R be a map on comparative ratios, taken in the analyst's metalanguage rather than as a relation of the modelled world. As a result, that $r_{n+1} = R(r_n)$. A stable scale factor is then a fixed point:

■ $R(\lambda) = \lambda$

The underlying organization may keep changing while its comparative relation holds steady. This echoes a lesson the book has now used three times: higher-order invariance survives lower-order transformation. Scale is therefore compatible with a dynamic ontology. Stability of relation does not require stasis of state.

One caution about the type. R is written as a function because ratios are numbers and the analyst may compute with them. The modelled transition $\mathcal{U}$

remains a relation (9.5). Where branching makes several successor magnitudes admissible, a stable scale factor need not be unique.

10.18 Reusing a Comparison: Endogenous Standards

Closure and Return earned a reusable higher-order reference structure: O_F can survive realization change, function through A_F as an organizational reference, depart from its identity condition, and later become addressable as that identity again. None of this yet provides a quantitative standard. Reuse becomes a scale standard only when the same comparison relation can be re-instantiated across organizations or levels.

Now a returned or re-instantiated identity can take part in comparison. If the same comparative relation can be reconstructed each time, it becomes an endogenous standard:

■ $\text{Cmp}(O_{n+1}, O_n) \approx \text{Cmp}^*$ whenever the identity recurs

The standard is endogenous because nothing is carried in from outside: the structure supplies the relation repeatedly. This is still not a metre or a second. It is the more primitive achievement that makes a calibrated unit conceivable later.

■ $\text{return} \rightsquigarrow \text{reusable identity} \rightsquigarrow \text{reusable comparison} \rightsquigarrow \text{endogenous scale}$

■ Re-instantiable comparison can supply an endogenous standard without an external unit. Closure and Return provide reusable identity and reference; Scale adds repeatable magnitude comparison.

10.19 Two Neighbours That Must Stay Separate

With this much equipment, several ideas begin to look alike. Two separations matter.

Hierarchy is not scale. A quotient can sit at a higher organizational level while compressing many lower-order configurations into fewer effective ones. Higher means organizationally later, not greater in magnitude.

■ $\text{higher-order} \neq \text{larger}$

Resolution is not scale. A resolving frame fixes which distinctions are accessible; a scale relation compares magnitude. Physical theories routinely connect the two, and that connection is additional structure rather than a definition.

■ $\text{resolution} \neq \text{scale}$

10.20 Coarse-Graining, Finally

Earlier chapters discussed coarse resolution and deliberately withheld a scale-indexed coarse-graining operator; Orientation deferred it here by name. We can approach it now without circularity, provided the order is explicit:

■ relative magnitude $\rightsquigarrow$ comparison standard $\rightsquigarrow$ scale-relative equivalence $\rightsquigarrow$ coarse-graining

Let $\approx_s$ group configurations whose differences fall within a declared comparative standard s . A coarse-graining map is then written:

■ $CG_s : \mathcal{C} \mapsto \mathcal{C} / \approx_s$

The load-bearing phrase is “within a comparative standard”. This chapter supports it only where the standard has been earned relationally. Smallness by metric distance remains unavailable. This is the first legitimate scale-aware reduction of detail in our framework, and it is still pre-geometric.

10.21 Surviving a Change of Scale

With a scale transformation available, we can ask whether a feature survives it. Scale invariance means that some identified organization is preserved when the scale relation is applied. This is a statement about what stays the same rather than about how big anything is. Self-similarity is the stronger case, where the organization at one level reproduces the organization at another under the comparison. It can be stated abstractly, without fractals and without a metric.

■ scale invariance $\neq$ geometric self-similarity

The familiar fractal reading needs a metric and an embedding, and neither is available. What we have is the abstract form the geometric version will later instantiate if the geometry earns it.

○ SPECULATIVE Whether any relational organization in this framework is genuinely self-similar across levels is untested; the models of the companion can look, and Complexity returns to it.

10.22 Bounds Before Boundaries

Comparative magnitude lets us state a bound without stating a size. An organization can be no larger than a standard, or no smaller, and both are pairings rather than measurements. This matters for Boundary’s boundary work, which defined separability without any notion of extent. A bound in this

sense is a comparison, and a boundary in Boundary's sense is a preserved non-equivalence. They are different things that English names alike.

- relational bound $\neq$ geometric boundary

10.23 Several Modes, Several Scales

Relation counted independent relational degrees of variation and refused to call the count a rank. Orientation added orientational modes and left their relation open. Nothing requires one scale relation to govern all of them. Different modes may stabilize at different comparative ratios, or some may stabilize while others do not.

- one organization may carry several scale relations at once

Open question: whether a family of scale relations over independent modes composes into anything stronger, which would need structure Formalism declined to import (Question 11).

10.24 Worked Example: Number After Relation

A small exercise makes the order of discovery explicit. Take three organizations, $A = \{a, b, c\}$, $B = \{x, y, z\}$ and $C = \{u, v, w, q\}$. The braces are external notation; what our model requires is only that the listed members be distinguishable under the declared criterion.

First, pair A with B: $a \leftrightarrow x$, $b \leftrightarrow y$, $c \leftrightarrow z$. Nothing is left unmatched, so $A \sim \# B$. We know the two have the same cardinal magnitude without having named it.

Now inject A into C: $a \mapsto u$, $b \mapsto v$, $c \mapsto w$. The member q is unmatched, so for these finite collections C has the greater cardinal magnitude.

Only now do the conventional labels enter: $\text{mag}(A) = \text{mag}(B) = 3$, $\text{mag}(C) = 4$. The order is the lesson, and it is the whole chapter in miniature: number arrives after relation.

The same logic carries into recursion. If a rule builds M_{n+1} as the disjoint composition of M_n and M_{n-1} , then once cardinal magnitude is available, $\text{mag}(M_{n+1}) = \text{mag}(M_n) + \text{mag}(M_{n-1})$. Fibonacci growth follows from that particular building. The building remains a model choice unless something independent motivates it.

10.25 Computational Diagnostics

Each test asks whether an apparent scale is relationally grounded or painted on by the analyst.

Correspondence first. Establish equal magnitude and magnitude order by bijections and injections before any integer label is assigned.

Relabeling. Change every identifier in the representation; comparative magnitude must be unchanged.

Threshold recovery. Reconstruct the Relation threshold condition from a standard collection K before replacing it with numeral shorthand.

Hierarchy against scale. Build a higher-order quotient with fewer representatives, showing that a higher level need not be a greater magnitude.

Recursive composition. Generate organizations under several recurrence rules and record their earned magnitudes.

Ratio convergence. Determine whether successive comparative ratios stabilize, cycle, stay bounded or diverge.

Recurrence perturbation. Change the coefficients and verify that φ is not generically selected.

Initial conditions. Determine when a stable ratio is robust to admissible changes in starting magnitude classes.

Self-similarity control. Compare a recursively self-similar model against a non-self-similar one that still supports magnitude comparison.

Coarse-graining sanity. Permit a scale-indexed quotient only after the standard defining it has been independently earned.

Falsification guardrail. If the scale can be recovered only once the analyst supplies a numeral, a unit, a coordinate magnitude, a metric or an iteration count, then nothing was earned: the magnitude was in the notation.

10.26 Competing Routes

Four routes to magnitude were available. The chapter took the first for reasons worth stating rather than leaving to a table.

Route	What it offers	Hazard	Used here
Cardinality first	Equal, more and less from correspondence	Too crude for later physical magnitude	The foundational route

Route	What it offers	Hazard	Used here
Hierarchy first	Matches recursive organization directly	Confuses level with size	Rejected as a definition
Resolution first	Ties magnitude to what a frame can distinguish	Makes magnitude observer-relative	Rejected; 10.19 keeps them apart
Metric first	Immediate and familiar	Imports distance, units and geometry wholesale	Unavailable until Distance

Cardinality is the weakest of the four, which is our argument for it. It needs nothing but distinguishable members and pairing, both of which we have held since Distinction.

10.27 Objections and Replies

Objection 1: Bijection already assumes sets. **Reply:** Set notation belongs to the metalanguage. What the model requires is one-to-one correspondence among distinguishable members, which Distinction supplies. If the correspondence itself proves unavailable, the chapter fails.

— — — —

Objection 2: The numeral labels make the detour pointless. **Reply:** For calculation, yes. For derivation, no. The chapter tests whether what a numeral compresses can be produced without assuming the numeral, and it can.

— — — —

Objection 3: Cardinality is too crude to ground physical scale. **Reply:** Agreed, and it is not asked to. It is the weakest magnitude available here, and its job is to cross from no magnitude to some.

— — — —

Objection 4: Infinite cardinality behaves unlike finite size. **Reply:** Correct. The foundational use here is finite. Infinite cases are noted and not relied upon.

— — — —

Objection 5: Ratio arithmetic has still been imported. **Reply:** Ratio appears only after finite cardinal comparison, and 10.10 says plainly that the structural statement of proportion is unfinished without it. That is a declared debt, not a concealed one.

— — — —

Objection 6: Fibonacci was chosen to manufacture φ . **Reply:** It is treated as a conditional worked case, and 10.16 shows the general recurrence selecting other ratios. Any claim privileging φ would need independent motivation the framework does not have.

— — — —

Objection 7: A stable ratio is only the analyst's calculation. **Reply:** It becomes ontologically relevant only if the modelled organization realizes the comparative relation and the stability survives the diagnostics of 10.25. Otherwise it is arithmetic about a model.

— — — —

Objection 8: A reusable standard is already a unit. **Reply:** Not yet. It is a repeatable comparative relation. A unit needs a calibration scheme, which later chapters must earn.

— — — —

Objection 9: Coarse-graining is circular, since it presupposes smallness. **Reply:** That is why the operator appears only after comparative magnitude, and why it is indexed to an earned standard rather than to a metric.

— — — —

Objection 10: Self-similarity is already fractal and therefore geometric. **Reply:** Self-similarity is stated here as preservation of organization under a scale transformation. The fractal reading needs a metric and an embedding, and both are withheld.

— — — —

Objection 11: Multiple scale factors form a vector. **Reply:** A family of scale relations is not a vector space. Addition, scalar multiplication, basis and inner product all remain unearned, as 9.19 requires.

— — — —

Objection 12: Magnitude depends on how an organization is decomposed. **Reply:** This is the chapter's most serious vulnerability, and it is not fully answered. The membership and decomposition criteria must be constrained independently, as F must be in Closure and Return, or magnitude becomes an artifact of description. The Register carries it as open.

10.28 What Scale Has Not Yet Earned

Metric distance or length.

A physical unit: a metre, a second, a Planck length, an energy scale.

A coordinate system.

Vector-space structure, inner products, angles, basis vectors or orthogonality.

A manifold, continuum or metric topology.

Physical dimensionality or an embedding dimension.

Fractal dimension as a property of physical space.

A universal law of self-similarity, or any universal role for Fibonacci or φ .

Renormalization-group flow as physical dynamics.

A probability measure or a stochastic distribution over scales.

What it earns is narrower: comparison of amount, proportion between amounts, and a standard the structure supplies itself.

10.29 Ontological Defensibility Pulse: Scale

This is the chapter's Pulse sidebar. It applies to the central proposition. It is set apart from our argument so that a reader can skip it on a first pass.

Pulse question	Applied to Scale
1. Entities required	No new substance: distinguishable members, correspondences between them, and the recursive composition already available
2. Ontological level	Pre-metric quantitative organization: from comparison of kind to comparison of amount
3. Lower-order dependencies	Distinction, retention, invariance, closure, return, quotient structure, the formal core
4. New emergent properties	Cardinal comparison, proportion, a stable inter-level ratio, and a standard the structure supplies without an external unit
5. Claim types	Formal at the core; interpretive on the order of discovery; speculative on self-similarity and multiple scale modes
6. New primitives	None: correspondence is pairing, and pairing needs only distinguishable members
7. Fewer assumptions?	Strengthened, since threshold aggregation and the coarse-graining operator both cease to need primitives of their own
8. Observational constraints	The ten diagnostics of 10.25, in particular relabeling invariance and the recurrence perturbation that denies φ any privilege

10.30 Implications and Handoff

Scale began by changing the frame from comparison of kind to comparison of amount. We can now pair organizations, order finite magnitudes, represent proportion, and recognize when a recursive relation stabilizes across levels.

The important change is not that our ontology has acquired a ruler. It has acquired something prior to one: a repeatable relation of magnitude.

■ correspondence ↔ equinumerosity ↔ cardinal order ↔ cardinal label

That lets us zoom across recursive levels without confusing level with size. A changing organization can preserve a stable proportional relation even while no geometric separation has yet been defined.

■ relative magnitude ↔ proportion ↔ recursive scale

The next shift is decisive. We can now ask how much, but not how far. Distance applies the magnitude we have earned to relational separation and tests whether distance can emerge without being assumed.

None of this is geometry. It is what geometry will need. We can now answer how much, in a limited relational sense. We still cannot answer how far. The difference between those two questions is the whole of the next chapter.

Handoff to Distance. Comparative magnitude exists; landmarks still float without separation. Can the magnitude we have earned be applied to relational separation itself, so that how much becomes how far?

Questions Opened by This Framework

Is cardinal comparison the weakest adequate notion of magnitude, or is something weaker available?

Can the membership and decomposition criteria that fix a magnitude be constrained independently, as F must be?

What distinguishes a recursive regime whose comparative ratio stabilizes from one whose ratio does not?

Does the cross-correspondence of 10.10 extend beyond finite organizations, where products and bijections are unproblematic?

Does anything in the framework select particular recurrence coefficients, or are they always a model choice?

When is a stable ratio a property of the modelled organization rather than of the analyst's bookkeeping?

What further structure turns a repeatable comparison into a calibrated unit?

Which coarse-grainings preserve the comparative relations that defined them?

Can scale invariance be stated without any metric, and is any relational organization here genuinely self-similar?

How do several scale relations over independent modes interact, if at all?

Does a family of scale relations ever compose into something stronger without importing vector structure?

What would falsify the claim that magnitude here is earned rather than supplied by notation?

Selected References Cited in Scale

Cantor, G. (1895). Beiträge zur Begründung der transfiniten Mengenlehre, erster Artikel. *Mathematische Annalen*, 46, 481–512. Translated by P. E. B. Jourdain in *Contributions to the Founding of the Theory of Transfinite Numbers* (Open Court, 1915; reprinted by Dover), where this article begins at page 85. The origin of the modern concept of cardinality, and the source of the one-to-one correspondence this chapter uses without its numerals.

On the Cantor–Schröder–Bernstein theorem, any standard set-theory text. The result is used here only for finite organizations, where it is elementary.

Frege, G. (1884). *Die Grundlagen der Arithmetik: Eine logisch mathematische Untersuchung über den Begriff der Zahl*. Breslau: Wilhelm Koebner. Translated by J. L. Austin as *The Foundations of Arithmetic* (Blackwell, 1950). For sameness of number defined by one-to-one correspondence, the principle Frege took from Hume.

Hume, D. (1739–40). *A Treatise of Human Nature*. 3 vols. London: John Noon (vol. III, Thomas Longman). Book I, Part III, Section 1. The correspondence principle in its original form.

Note on these references. These works are mathematical precedents, not evidence for the ontology. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 11

Distance: When Relation Becomes Metric

Claim ~ Distance becomes available when distinct relational loci can be connected through admissible chains of mediation whose comparative burden is recoverable from the organization itself, allowing separation between loci to acquire magnitude.

Chapter discipline. Distance inherits relational identity, closure, orientation, return, formal composability, comparative magnitude, proportion, recursive scale, and endogenous standards. Its burden is this:

■ how much + relational separation $\rightsquigarrow$ how far

Distance also inherits one unresolved debt from Scale: if the relational decomposition being measured is arbitrary, the resulting distance is arbitrary with it.

11.1 Where Scale Leaves Us

Scale gave the relational world a new capacity: comparison of magnitude. Two organizations can be matched one to one. One can contain more admissible members than another. Parts can stand in stable proportion. Recursive organization can re-establish a comparative standard without importing an external ruler.

We can answer, in a limited relational sense: how much?

But the landscape still has no separation. Two relational identities may differ without anything yet telling us whether they are near, far, adjacent, remote, or connected through something between them. Magnitude hangs free of position.

So we change the question. Imagine two identities already available to the framework:

A, B

Do not place them on a line. Do not picture an empty space between them. Ask instead:

What relational structure must mediate between A and B for one to be reachable from the other within the organization?

That is the beginning of distance.

■ difference $\rightsquigarrow$ separation $\rightsquigarrow$ magnitude of separation

Distance succeeds only if the final term emerges without the second already being geometric.

11.2 Difference Is Not Separation

The framework has possessed non-identity since Distinction:

■ $A \neq B$

But two things can differ without their difference having magnitude. Two configurations may be non-equivalent; two higher-order identities may respond differently under the same transformation. None of this tells us how far apart they are.

■ $A \neq B \neq d(A,B)$

Distance requires more than distinction. It requires relational position.

Relation introduced position in a deliberately non-spatial sense: what an identity is relative to the organization around it. Here we extend that idea. Two identities are relationally separated when they occupy non-equivalent positions within an organization and the relation between those positions cannot be collapsed into identity under the declared criterion.

Call their pre-metric separation $\rho(A,B)$. At this stage ρ is not a number. It says only that the organization distinguishes the positions of A and B relationally.

■ relational separation $\neq$ metric distance

11.3 Separation Requires Mediation

Suppose A and B belong to the same relational organization. Their separation can be direct:

$A \ R \ B$

or mediated:

$A \ R \ X_1 \ R \ X_2 \ \cdots \ R \ B$

The symbols describe a chain of relational dependence or incidence. One distinction must be made before the chain does any work. Formalism typed $\mathcal{U}$ as the admissible transition between configurations. Mediation is not that relation. $\mathcal{U}$ carries one configuration to a successor; mediation holds between loci within a single configuration. Conflating them would make distance a

count of updates, which would both misdescribe separation and leave Time nothing of its own to earn.

- mediation between loci $\neq$ transition between configurations

Let an admissible relational chain from A to B be:

- $K_{AB} = (A, X_1, \dots, X_n, B)$

such that each neighboring pair participates in a relation admitted by the organization under the declared criterion.

Some pairs may be connected through fewer mediating relations than others. “Fewer” is now legitimate only because Scale earned comparative finite magnitude. Before Scale, counting intermediates would have been external bookkeeping. After Scale, the organization may itself support comparison among finite chains.

- relational mediation + earned magnitude $\rightsquigarrow$ comparable separation

11.4 The Unweighted Case

Begin with the cheapest case. Suppose every relation contributing to a chain is equivalent under the relevant comparison standard. Then the chain contains repeated instances of the same admissible relational step.

Let u denote that reusable relational standard, lettered to stay clear of the coarse-graining standard s of 10.20. For a chain containing n such relations:

- $L_u(K) = n u$

This is the first candidate for the magnitude of relational separation. The underlying statement is that one chain contains more, fewer, or the same number of equivalent mediating relations as another. Numerical notation compresses that earned comparison.

- equal relational steps + cardinal magnitude $\rightsquigarrow$ chain magnitude

11.5 Why Not Every Chain Defines Distance

Between A and B, several admissible chains may exist. If all contributing relations are equivalent under s , one chain may carry magnitude $2u$ while another carries $3u$.

Which one represents the separation between A and B? We cannot simply choose whichever route we prefer.

The natural candidate is the least sufficient relational mediation:


$$\blacksquare d_u(A,B) = \min_{K \in K(A,B)} L_u(K)$$

where $K(A,B)$ is the set of admissible relational chains connecting A and B.

The minimum is well defined only where that set is non-empty and finite. Finiteness comes from Scale, since the chains are compared by earned cardinal magnitude. Non-emptiness is a real condition rather than a technicality: two loci with no admissible chain between them have no distance at all, which is not the same as being infinitely far apart. That case returns in 11.15, where local metric structure fails to compose into a global geometry.

Distance is the smallest magnitude of relational mediation sufficient to connect two relational positions under the declared organization and scale standard.

The minimum is not yet a physical principle saying that systems move along shortest routes. Nothing moves. No action is minimized. The minimum selects the least relational structure necessary to mediate the two positions.



The route with fewer mediators covers more ground; the route with more mediators covers less. Mediation and extent are two magnitudes, and they need not agree.

Which one counts as farther depends on what is being measured, and how long each takes is a third question that neither answers. That is Chapter 11.

Figure 11.1. Competing chains and minimum mediation. Two admissible relational chains connect A to C. Under an unweighted standard in which each mediating relation belongs to the same magnitude class u , the upper chain carries $2u$ and the

lower chain $3u$, so the candidate distance $d_u(A,C)$ selects $2u$ as the least sufficient mediation. Each locus carries its everyday counterpart beside it, as an itinerary between cities, and each relation carries the distance flown. The two magnitudes disagree: the route with fewer mediators covers more ground, 14 900 km against 14 100 km, while the route with more mediators covers less. Counting mediators and measuring extent are different questions, and how long either journey takes is a third question that neither answers, which is what Time must earn.

11.6 Minimal Relational Work

There is a useful broader interpretation. We may describe $L(\kappa)$ as the comparative burden of structure required to connect two positions, provided “work” is understood pre-physically and implies no traversal.

Relational work is the comparative burden of relational structure required to connect one admissible position to another.

■ distance = minimum relational work of connection

Minimum relational mediation is formally sufficient at this stage. Relational work remains an interpretive analogy, and the chapter does not promote it into a minimality law about how organizations form.

11.7 The Weighted Case

Equivalent steps are only the simplest case. A mature relational organization may contain mediating relations that differ in comparative magnitude.

$w(r_1), w(r_2), \dots$

If those weights are already grounded by the comparative machinery of Scale, then:

■ $L(\kappa) = \sum_{r \in \kappa} w(r)$

and distance becomes:

■ $d(A,B) = \min_{\kappa \in K(A,B)} \sum_{r \in \kappa} w(r)$

Weighted shortest-path form is familiar mathematics, but the mathematics is representational. The ontological burden lies beneath it: why are these relations the relevant mediators, why are their weights internally recoverable, why is their composition additive, why is the chosen scale standard legitimate, and does the result survive faithful re-description?

The weighted construction therefore remains Provisional until its weights can be derived from independently justified relational magnitude.

11.8 Additivity Must Be Earned

The weighted expression hides an assumption. If a chain contains two mediating relations with burdens a and b , why should the composite carry $a+b$?

Scale earned comparative magnitude and proportion. It did not prove that every magnitude composes additively.


If the organizational rule supports concatenation such that mediating burdens combine without interference, then:

$$\blacksquare L(\Pi_1 \circ \Pi_2) = L(\Pi_1) + L(\Pi_2)$$

If composition changes relational burden nonlinearly, then simple metric addition is not yet justified.

Metric distance requires a compositional magnitude law for relational mediation.

Addition is one candidate law. It is not primitive merely because familiar geometry uses it.



One composition, two magnitudes. The sources are equally real in both rows; what differs is whether the quantity being reported is the one that adds.

$L(\kappa_1 \circ \kappa_2) = L(\kappa_1) + L(\kappa_2)$ holds only when relational burden is measured in the register that composes. Until the organization settles which that is, additivity is assumed rather than earned.

Figure 11.2. Why additivity has to be earned. One composition is shown in two registers. In the upper row the acoustic powers of two sources add: one unit and one unit make two, and the composite bar is the two source bars laid end to end. In the lower row the same event is reported in decibels, where 60 and 60 give about 63 rather than 120; the dashed outline marks what addition would have predicted. Neither row is wrong, and the sources are equally real in both. What differs is whether the quantity being reported is the one that composes. Relational burden

faces the same question: $L(\kappa_1 \circ \kappa_2) = L(\kappa_1) + L(\kappa_2)$ holds only when burden is measured in the register that composes, so until the organization settles which register that is, additivity is assumed rather than earned and the triangle inequality of 11.10 inherits the assumption.

11.9 Zero Separation and Identity

A metric normally requires $d(A,A)=0$. No mediation is required to connect a relational position to itself under the identity relation.

The converse is harder. Suppose two lower-order configurations differ but every admissible relational comparison assigns zero separation between them.

Define:


■ $A \sim_0 B$ iff $d(A,B)=0$

If $\sim_0$ is a legitimate equivalence relation compatible with the organization, zero-separated states should be treated as one higher-order locus:

$[A]_{\sim_0}$

The metric can then act on equivalence classes rather than lower-order representatives.

Metric identity may emerge by quotienting distinctions that carry no relational separation.



The two labels are not merged by convention. Every measurement puts them in the same place, and a route planner that keeps them apart proposes a journey of zero length between them.

Figure 11.3. Zero separation and quotient identity. A_1 and A_2 are distinct descriptions that every admissible comparison assigns zero separation, so each stands in the same relation to every other locus: both are 900 km from B. The quotient treats them as one locus $[A]$, and the metric acts on classes rather than on representatives. The everyday counterpart is longitude 0° and 360° , two labels

naming one meridian. They are not merged by convention or for tidiness. Every measurement places them identically, and a route planner that keeps them apart will offer a journey of zero length between them, which is the signal that they were never two places. Metric identity can therefore emerge by quotienting distinctions that carry no relational separation.

11.10 The Triangle Inequality

One defining property of ordinary metric distance is:

$$\blacksquare d(A,C) \leq d(A,B) + d(B,C)$$

Here it should not be assumed. Suppose the least chain from A to B has magnitude $d(A,B)$, and the least chain from B to C has magnitude $d(B,C)$. Concatenating them yields an admissible chain from A to C. If chain magnitude is additive, its magnitude is $d(A,B)+d(B,C)$. But $d(A,C)$ is defined as the minimum over all admissible chains connecting A and C.

Therefore:

$$\blacksquare d(A,C) \leq d(A,B) + d(B,C)$$

The triangle inequality is not inserted as a geometric axiom. It follows from:

chain composition + additive magnitude + minimality

This is one of the strongest formal results available to Distance, and its premise should be stated with it: the composition step assumes that mediating burdens add. Section 11.8 records that additivity is earned only where the organization supports concatenation without interference, so the triangle inequality inherits that Provisional status. Where composition is non-additive, a weaker inequality may survive, and that is an open question rather than a result.

11.11 Symmetry Is Not Free

A conventional metric also requires:

$$\blacksquare d(A,B)=d(B,A)$$


The framework cannot assume this. Orientation already earned consequential non-equivalence under role reversal. It is therefore possible that the admissible coupling $A \mapsto B$ requires different relational mediation from the reverse coupling $B \mapsto A$.

$$\blacksquare d(A,B) \neq d(B,A)$$

The first structure Distance earns may therefore be a directed distance rather than a symmetric metric.

If every relevant mediating relation is reversibly equivalent under the distance criterion, and every admissible chain has a reverse chain of equal magnitude, symmetry follows.

■ relational distance $\rightsquigarrow$ directed metric-like structure $\rightsquigarrow$ symmetric metric under reversible equivalence



The river is the same 80 km in both directions. What the flow changes is not the distance but what it costs to cross it, and the cost depends on the paddler's orientation to the flow.

Figure 11.4. Orientation can produce asymmetric distance, read as a kayak on a river. A is the upper landing and B the lower one, with 80 km of river between them; X and Y are the overnight camps, each 40 km from a landing. The band carries the current, running from A toward B at 10 km per day. The paddler makes 30 km per day in still water, so downstream the flow carries them at 40 km per day and each leg takes a day, giving the admissible coupling chain $A \mapsto X \mapsto B$ a burden of 2. Upstream the same effort makes 20 km per day, each leg takes two days, and the chain $B \mapsto Y \mapsto A$ carries 4. The river itself has not changed length, and neither landing has moved. What the flow changes is not the separation but what it costs to traverse, and the cost depends on the paddler's orientation with respect to the flow. Where mediating relations are not reversibly equivalent in that sense, $d(A,B) \neq d(B,A)$, and the first structure Distance earns is a directed measure rather than a

symmetric metric. Days and speeds are illustrative: duration and rate belong to Time, and the figure borrows them only to make the asymmetry visible.

11.12 A Metric Is a Special Case

We can now state the conditions under which the relational construction becomes a metric-like structure. On the relevant quotient domain, require non-negativity, zero-distance identity, and the triangle inequality. If reversible equivalence additionally yields symmetry, the quotient domain supports an ordinary metric.

■ relational organization $\rightsquigarrow$ metric axioms as consequences

The direction of explanation matters. Metric axioms should emerge from the organization rather than being used to define the organization in advance.

11.13 Distance Without Coordinates

Nothing in the construction requires coordinates. We can know $d(A,B) < d(A,C)$ without assigning coordinate tuples to A, B, and C.

■ metric relation $\neq$ coordinate representation

11.14 Distance Without an Embedding

The relational domain also need not sit inside a larger space. If $d(A,B)$ is determined entirely by relations internal to the domain, then the distance is intrinsic to that relational organization.

■ intrinsic distance $\neq$ embedding distance

An embedding tells us how a structure sits inside something else. An intrinsic metric tells us how positions within the structure relate to one another. Volume I needs the first before it can legitimately discuss the second.

11.15 Local Distance Does Not Guarantee Global Geometry

A domain may support valid pairwise distances without those distances composing into one globally coherent geometry. Different regions may employ different relational standards. Some may contain directed asymmetries. Others may possess disconnected components or incompatible scale calibrations.

■ local metric structure $\neq$ global geometry

This gives us another important boundary. Distance asks whether separation can acquire magnitude. Geometry will ask whether a sufficiently coherent family of such relations can be represented as a geometry.

11.16 Distance and Scale Dependence

Scale gives us reason to expect that distance may depend on organizational resolution. A fine-grained description may distinguish many lower-order identities while a coarser frame treats them as one higher-order identity.

The relational chains available at the fine level need not match those available after coarse-graining, so:

$d^u(A,B)$ may differ from $d^{u'}(A,B)$, where u and u' are the standards of two scale regimes

That does not necessarily mean one is false. They may describe separation at different organizational resolutions. The important requirement is consistency: does the coarse-grained distance preserve the relational distinctions relevant at that scale?

Distance may be scale-relative while still being structurally objective within a declared scale regime.

This is a candidate proposition, not yet a result.

11.17 The Decomposition Problem Returns

Scale ended with a serious unresolved problem: magnitude depends on what counts as a member of the organization. Distance inherits the same vulnerability in amplified form.

A distance construction depends on what counts as a locus, what counts as a mediating relation, which chains are admissible, which distinctions receive nonzero weight, and which scale standard is applied.

If the analyst is free to choose these after seeing the desired result, almost any metric can be manufactured.

A relational distance is admissible only when its loci, mediating relations, admissible chains, and scale standard are independently constrained.

This may be the most important falsifiability condition in Distance.

Among competing decompositions that represent the same higher-order organization, a decomposition requiring fewer arbitrary relational

commitments is preferable. The stronger result would be to show that the organization itself stabilizes some decomposition classes while alternatives fail under perturbation or coarse-graining. That remains open.




Figure 11.5. Scale-relative distance under coarse-graining, read as a street map against a subway map. The two rows carry the same five stations, and the grey ties mark which node is which across them. On the street map the separations are as they are on the ground: Quay to Market is 0.4 km, Old Bridge to Fairground is 3.8 km. On the subway map every link is one stop, so those two pairs are indistinguishable, though one is nine times the other. Analogous nodes therefore remain analogous under the coarse-graining, while their magnitudes do not survive it. The coarser description keeps the order of the stations and the fact that each pair is adjacent, and it was drawn to keep exactly that. This is why a scale-relative distance can be structurally objective inside its own regime and misleading outside it, and why 11.16 requires that a coarse-grained distance preserve the higher-order relations it claims to preserve, rather than all of them.

11.18 A Familiar Case

Take the five loci of Figure 11.1, with their everyday counterparts: A is Lagos, B is Doha, C is Perth, D is Nairobi and E is Colombo. The admissible mediating relations are A-B, B-C, A-D, D-E and E-C, each a single flight and each belonging to the same magnitude class u .

The first chain from A to C contains two equivalent mediators; the second contains three.

■ $L_u(A-B-C) = 2u$

■ $L_u(A-D-E-C) = 3u$

The candidate distance is therefore:

■ $d_u(A,C) = 2u$

Lagos to Perth by way of Doha is the least mediated route, and that is what the construction has selected.

The figure also carries the distances flown, and they run the other way. The two-mediator chain covers 5 900 km and then 9 000 km, for 14 900 km; the three-mediator chain covers 3 800, 5 200 and 5 100, for 14 100 km. The route with fewer mediators is the longer journey by 800 km.

■ fewest mediators $\neq$ least ground covered

Both statements are true, and neither is a correction of the other. They answer different questions, and each is a magnitude only relative to the standard that defines it. Under u , where every admitted flight counts alike, $d_u(A,C) = 2u$. Under a standard in which each flight carries a weight proportional to the ground it covers, the weighted construction of 11.7 selects the other chain, and the distance from Lagos to Perth becomes 14 100 km by way of Nairobi and Colombo.

■ change the magnitude standard, and the minimum may change route

Nothing in the example tells us that the loci occupy Euclidean space. No coordinates have been assigned, and no line has been drawn through a physical background: the kilometres are borrowed from the everyday reading, not derived by the framework. What the framework has is narrower. Given a declared standard, the least internally admitted relational mediation between A and C has a definite magnitude, and changing the standard is a change of question rather than a discovery that one answer was wrong.

11.19 What Near and Far Can Now Mean

Ordinary language may finally begin to return. If $d(A,B) < d(A,C)$, then B is relationally nearer to A than C is under the declared metric regime. If $d(A,B) > d(A,C)$, it is farther.

These words now compress something the framework has actually earned. They no longer mean merely that the analyst drew nodes closer together on the page.

■ near/far = comparative metric relations

■ relational near/far $\neq$ physical spatial near/far

11.20 Distance Is Not Yet Geometry

The existence of a metric does not automatically give us a familiar space. We still lack dimension, coordinates, angles, orthogonality, curvature, continuity, neighborhood topology as ontology, manifold structure, and spatial embedding.

A finite metric structure may be highly irregular. It may not resemble any low-dimensional Euclidean or Lorentzian geometry.

■ metric separation $\neq$ geometry

Distance earns a precursor, not the destination. Geometry will ask when a coherent relational metric structure can be represented as an effective geometry with stable dimensions and coordinate-like degrees of freedom.

11.21 Computational Diagnostics

Relabeling invariance. Renaming lower-order components must not change the distance.

Representation invariance. Faithful graph, hypergraph, matrix, or equivalent encodings should preserve the metric relations that matter.

Decomposition perturbation. Small changes in arbitrary descriptive partition should not radically alter distance unless those changes correspond to genuine changes in the organization.

Chain robustness. If several nearly equivalent chains exist, perturbing one should not destroy the metric globally.

Quotient compatibility. Zero-separated states or higher-order equivalent states should support well-defined distances on the quotient.

Scale consistency. Coarse-grained distances should preserve declared higher-order relations where the coarse-graining is claimed to be valid.

Symmetry test. Where symmetry is claimed, reversing admissible relational chains must preserve their magnitude.

Triangle test. Distances constructed from admissible chain composition should satisfy the triangle inequality when additivity is claimed.

Hidden-geometry control. The implementation must not encode coordinates, geometric neighborhoods, target dimensionality, or an embedding into the update rules.

Random-control comparison. Candidate relational structures should be compared with matched random organizations to test whether coherent metric structure is genuinely selected rather than trivially present in every arbitrary network.

These diagnostics constrain models. They do not by themselves show that nature instantiates the ontology.

11.22 Objections and Replies

Objection 1: This is just graph distance.

Reply: Formally, the simplest realization is graph-like shortest-path distance. The ontological claim is weaker: separation can acquire magnitude from internally weighted relational mediation without an external coordinate system.

— — — —

Objection 2: Path already assumes geometry.

Reply: Not here. A relational chain is a sequence of mediated relations. Geometric path imagery is optional; the formal definition can use chain or composition exclusively.

— — — —

Objection 3: Counting mediators assumes distance.

Reply: No. It assumes magnitude, which Scale has already earned through correspondence. Number of mediators and metric separation are different concepts. Distance asks whether the former can ground the latter.

— — — —

Objection 4: Shortest path is arbitrary. Why should the minimum matter?

Reply: Because distance is intended to capture irreducible relational separation rather than every possible detour between two positions. The minimum extracts the least mediation required by the organization. Whether this is uniquely correct remains open and should be tested against alternatives.

— — — —

Objection 5: The shortest chain may not represent physical distance.

Reply: Agreed. Distance does not yet claim physical spatial realization. It derives an intrinsic relational metric candidate.

— — — —

Objection 6: Additive weights have been smuggled in.

Reply: Only in the weighted candidate construction. Additivity must be justified by the composition rule. If relational magnitude composes non-additively, a different metric or metric-like structure is required.

Objection 7: Orientation destroys metric symmetry.

Reply: Correct. Symmetry is not primitive here. Directed relational distance may appear first; ordinary metric symmetry is recovered only where reversal preserves relational burden.

Objection 8: Decomposition lets the analyst manufacture any metric.

Reply: This is the strongest objection. The loci, relations, chain admissibility, and magnitude standard must be independently constrained. If they cannot be, the distance is descriptive rather than endogenous.

Objection 9: A metric already gives topology.

Reply: Mathematically, a metric can induce a topology. That does not require the ontology to treat topology as primitive. If such topology becomes useful later, it is derivative from the earned metric.

Objection 10: Minimum relational work is energy in disguise.

Reply: No physical energy is claimed. Work is an interpretive analogy for relational burden. The formal core requires only comparative mediation magnitude.

11.23 What Distance Has Not Yet Earned

Physical spatial length.

A metre or any physical calibration unit.

Coordinates.

Angles.

Inner products.

Orthogonality.

Basis vectors.

Spatial dimension.

A manifold.

Continuity.

Curvature.

Physical locality.

Velocity.

Metric time.

Light cones.

Causal speed.

Energy.

Action.

Geodesic motion.

General relativity.

Spacetime.

What Distance earns is narrower:

intrinsic magnitude of relational separation

and, under additional conditions:

a metric or directed metric-like structure over relational loci

11.24 Ontological Defensibility Pulse: Distance

This is the chapter's Pulse sidebar. It applies to the central proposition, and it is set apart from the argument so that a reader can skip it on a first pass.

Pulse question	Applied to Distance
1. Entities required	No new substance: relational loci, mediating relations between them, and the comparative magnitude earned in Scale
2. Ontological level	Pre-geometric metric organization: magnitude applied to separation rather than to amount
3. Lower-order dependencies	Distinction, retention, structure, closure, orientation, return, the formal core, comparative magnitude and proportion

Pulse question	Applied to Distance
4. New emergent properties	Chain magnitude, minimum mediation, zero-separation quotients, a directed metric-like structure, and the triangle inequality, derived given additivity
5. Claim types	Formal at the core; interpretive on relational work and on near and far; speculative on scale-relative distance and on global coherence
6. New primitives	None intended. Mediation is relational incidence already available; minimality is selection over an ordered finite set, not an optimization principle
7. Fewer assumptions?	Strengthened where metric axioms become consequences rather than definitions, and weakened wherever additivity or decomposition must be assumed
8. Observational constraints	The ten diagnostics of 11.21, in particular the hidden-geometry control and the random-control comparison

The central vulnerability remains decomposition. If the organization does not independently determine what counts as a locus and what counts as a relevant mediator, Distance inherits the arbitrariness of Scale in amplified form, and 11.17 states the condition under which the construction is admissible at all.

11.25 Implications and Handoff

Scale gave us magnitude without separation. Distance applies magnitude to relational mediation.

difference $\rightsquigarrow$ relational position $\rightsquigarrow$ mediation $\rightsquigarrow$ comparative chain magnitude $\rightsquigarrow$ minimum mediation $\rightsquigarrow$ distance

Three results matter.

First, distance need not begin with coordinates. It can arise as an intrinsic comparison among relational positions.

Second, the metric axioms need not all be primitive. Non-negativity, zero-distance equivalence, and the triangle inequality can arise from lower-order structure under stated conditions. Symmetry requires an additional reversible equivalence and therefore remains conditional.

Third, distance inherits every weakness of the relational decomposition beneath it. A metric is endogenous only if the organization itself constrains the loci, relations, and standards from which the metric is built.

We can now say, in a limited relational sense: how far.

But a collection of distances is not yet a geometry. We can compare any two loci and say how far apart they stand. We cannot yet say that knowing some separations constrains what the others can be, that the loci near one of them stay near it through admissible transformation, or that the whole admits any number of independent ways of varying.

Distance is pairwise. Everything it gives us is a relation between two loci, taken one pair at a time.

■ metric separation between loci $\neq$ organized constraint among separations

That gap is where the next chapter begins. Geometry asks when metric relations stop being merely pairwise and become mutually constraining: when neighborhoods persist, when overlaps limit what other distances can be, and when several independent modes of variation can be sustained at once. It is the same move the framework has made twice before. Retained distinctions became structure when they ceased to vary independently, and relations became organizations when their dependencies closed. Metric relations now face the same test.

Duration is a further question still, and a later one. A chain can carry magnitude without being traversed, and an order can hold without anything taking any length of time. Space must first say when geometric organization becomes physical extension, and only then can Time ask what gives ordered change a rate.

Handoff to Geometry. Distance gives magnitude to separation, one pair at a time. When do many separations constrain each other well enough to constitute a geometry?

Distance tells us how far two relational loci stand apart; Geometry must tell us when such separations organize.

Separation can now have magnitude: how far two relational loci stand apart is set by their minimum admissible mediation burden.




Figure 11.6. Distance as a derivational bridge.

Questions Opened by This Framework

Is minimum relational mediation the weakest adequate definition of distance?

Must relational distance be chain-based, or can pairwise relational invariants generate metric structure more directly?

Under what conditions is relational burden additive?

Can a useful generalized distance exist where additivity fails?

When does directed distance become symmetric?

Can zero-distance equivalence be constrained independently enough to support a legitimate quotient?

Which decomposition criteria keep distance from becoming analyst-dependent?

Can scale-relative distances converge toward a stable higher-order metric?

What coarse-grainings preserve minimum relational mediation?

Do generic relational systems produce coherent metrics, or is a stability-selection mechanism required?

Can independent relational modes later produce effective dimension without assuming orthogonality?

What additional structure turns a relational metric into geometry?

What would falsify the claim that distance has been derived rather than encoded?

Is minimum relational work merely an interpretive gloss, or can it eventually be formalized without importing physical energy?

Can the same minimality principle that selects relational distance help constrain the decomposition ambiguity inherited from Scale?

Selected References Cited in Distance

Bourbaki, N. (1966). *Elements of Mathematics: General Topology*, Part 1. Paris: Hermann; Reading, MA: Addison-Wesley. Translation of *Topologie générale*. For the standard metric axioms this chapter derives rather than assumes.

Dijkstra, E. W. (1959). A note on two problems in connexion with graphs. *Numerische Mathematik*, 1(1), 269–271. doi:10.1007/BF01386390. The shortest-path construction whose form the unweighted and weighted cases here reproduce.

Gromov, M. (1999). *Metric Structures for Riemannian and Non-Riemannian Spaces*. Progress in Mathematics 152. Boston: Birkhäuser. Translated by S. M. Bates from the 1981 French *Structures métriques pour les variétés riemanniennes*, with appendices by M. Katz, P. Pansu and S. Semmes. For metric structure developed without an ambient embedding, the mathematical neighbour of 11.14.

Note on these references. These are mathematical precedents and comparison classes, not evidence for the ontology. Bibliographic details were verified against primary or authoritative sources on 25 September 2026.

Chapter 12

Geometry: When Distance Becomes Dimension

Claim ~ Geometry becomes available when relational distances organize into mutually constraining layers that support stable neighborhoods, independent modes of variation, and transformations reproducible across scale. A probe that repeatedly resolves the same lower-order invariants of such a substrate then sees them as persistent multidimensional geometric properties, while the organization that generates them can hold more than any one projection shows.

Chapter discipline. Geometry inherits relational identity, closure, orientation, return, formal composability, endogenous magnitude, scale, and intrinsic metric separation. Its burden is first to show how many relational distances can form a coherent multidimensional organization, and only then to ask what portion of that organization is recoverable by a bounded probe.

- many relational distances $\rightsquigarrow$ coherent multidimensional organization
- underlying relational organization $\rightsquigarrow$ interaction-conditioned effective geometry

12.1 Where Distance Leaves Us

Distance gave relational separation magnitude. Distinct relational loci can now stand in comparative metric relation without coordinates, spatial embedding, or physical length. Near and far have acquired formal content, but only in the limited relational sense already earned by the preceding chapter.

A collection of distances is not yet a geometry. Suppose a domain contains loci A, B, C, and many others, and the framework can recover $d(A,B)$, $d(A,C)$, $d(B,C)$, and the corresponding relations among the rest. Those values may be internally meaningful while the total organization remains irregular, disconnected, directed, scale-dependent, or impossible to represent by any low-dimensional familiar geometry.

The new question therefore concerns relations among separations. When does knowing some distances constrain what other distances can be? When do neighborhoods persist? When do several independent ways of varying position become stable? When can one local description be translated into another without losing the relations that made the description geometric?

Geometry begins when metric relations cease to be merely pairwise and become a mutually constraining higher-order organization.

■ metric separation $\neq$ geometric organization

This move mirrors an earlier transition in the framework. Retained distinctions became structure when they ceased to vary independently. Geometry asks whether metric relations can undergo the same kind of higher-order closure.

12.2 From Pairwise Separation to Metric Neighborhood

For a locus A and an internally available scale ε , consider the family of loci whose relational distance from A lies below that scale. In conventional notation one might write $N_{\varepsilon}(A) = \{X : d(A,X) < \varepsilon\}$. Nothing in this expression requires us to picture a literal ball in a pre-existing space. At this stage it identifies a scale-relative relational neighborhood.

A useful neighborhood must do more than group whatever the analyst chooses to call close. Its membership must follow from the independently constrained distance relation. Neighboring domains should overlap where the metric organization warrants overlap, and those overlaps should remain sufficiently stable under admissible perturbation, relabeling, and coarse-graining.

We can therefore state a first candidate condition: local geometric coherence is the persistence of neighborhood relations under admissible transformation.

■ local geometric coherence = stable neighborhood relations under admissible transformation

If an arbitrarily small perturbation of an arbitrary descriptive partition completely rewires every neighborhood relation, then the system may possess metric values without possessing a robust geometry. The distinction is the same one that has appeared repeatedly in the series: a structure becomes ontologically interesting when its relevant relations survive transformation rather than depending on the notation used to display them.

12.3 Overlap Is the First Collective Geometric Constraint

Neighborhoods become geometrically informative when they overlap in constrained ways. If B belongs to a neighborhood of A and C belongs to a neighborhood of B , the organization may limit which relations between A and C remain admissible. The total pattern of overlaps then carries information that no isolated distance contains.

Let D denote the family of admissible relational distances. A geometry requires that members of D are not freely assignable independently of one another. The exact mathematical form will depend on the metric structure eventually recovered, but the conceptual condition is simple: changing one local relation can constrain several others.

This gives geometry a recognizable ontological level. Distance measured separation between loci. Geometry concerns organized constraints among systems of separations.


distance : relation between loci

geometry : relation among systems of distances

The distinction prevents the chapter from simply renaming a metric space as emergent geometry. A metric supplies the raw comparative structure. Geometry appears only where that structure acquires stable higher-order organization.

12.4 When Distances Become Neighborhoods

$N_{\varepsilon}(A)$ = the loci whose earned distance from A falls below the standard ε



Who counts as near depends on the relation, not on where the diagram puts anyone.

Introductions make a neighborhood without anyone being anywhere: nothing here is close in space.

Figure 12.1. From pairwise distance to stable neighborhood. Around the locus A, two internally available standards ε_1 and ε_2 pick out the loci whose earned distance from A falls below them. The everyday counterpart is degrees of introduction: A is you, B and C are people you know, D is a friend of a friend who still falls inside the

wider standard, and E is a stranger outside both. Membership follows from the relation rather than from where the diagram happens to put anyone, which is the whole content of the condition. The analogy is chosen for what it does not carry: a circle of acquaintance makes a neighborhood without anyone being anywhere, so nothing here is near in the sense Space has yet to earn. Its limit is that introductions are symmetric and these standards need not be, since Distance has already allowed $d(A,B) \neq d(B,A)$.

12.5 Geometry May Be Multilayered Before It Is Dimensional

A single metric relation need not exhaust the organization simultaneously active at a locus. The same lower-order identities may participate in several families of constraint. One family may preserve one pattern of separation; another may preserve a different pattern; a third may regulate which changes in either family can remain stable.

Call such a family a metric-relational layer. A layer is not a sheet, a hidden spatial surface, or a field already defined over a manifold. It is a distributed family of relational constraints whose members support internally comparable separation.

For bookkeeping we may write $\mathfrak{L}_\alpha = (X_\alpha, d_\alpha, K_\alpha)$, where X_α is the set of loci resolved in that layer, d_α is its admissible separation relation, and K_α denotes the constraints linking those relations. The notation does not assert that these ingredients are fundamental substances. It packages a higher-order relational organization.

Several such layers can be coupled. Let $K_{\alpha\beta}$ represent constraints between $\mathfrak{L}_\alpha$ and $\mathfrak{L}_\beta$. The resulting candidate substrate can be written schematically as $\mathfrak{L} = \{\mathfrak{L}_\alpha, K_{\alpha\beta}\}$.

$$\blacksquare \mathfrak{L} = \{ \mathfrak{L}_\alpha, K_{\alpha\beta} \}$$

This proposal changes the question from “Which single geometry is fundamental?” to “Under what conditions can several coupled metric organizations jointly produce a stable effective geometry?” The latter is a candidate research program, not an established description of nature.

12.6 Layer Is Not Dimension

The distinction between layer and dimension is non-negotiable. Three layers do not imply three dimensions, and a single layer could in principle support several independent modes of variation.

$$\blacksquare \text{number of relational layers} \neq \text{number of geometric dimensions}$$

A dimension should enter only when a local state can vary in more than one irreducible way. Suppose a neighborhood around A admits candidate variation modes $\delta_1, \delta_2, \dots, \delta_n$. If a change available through one mode cannot be reproduced, under the declared equivalence criterion, by admissible combinations of the others, then that mode contributes an independent degree of variation.

Formalism has already supplied the crucial discipline: independence can be represented before orthogonality. We therefore need not begin with perpendicular axes. An effective dimension is first a rank-like statement about how many independent relational variations are required to preserve the local distinctions relevant at the chosen scale. Geometry therefore reuses Formalism's d_R rather than introducing a second rank symbol: the geometric question is whether the already-defined relational rank remains stable and interpretable across the metric-neighborhood regime.

■ $d_R := \text{rank}(\text{Ind}_R)$, evaluated here on the stable independent relational modes that survive the declared geometric regime

The exact rank structure remains a formal question. Matroidal language is one candidate because it captures independence without requiring an inner product, but the ontology does not depend on that particular mathematical implementation.

12.7 Independence Before Orthogonality

Ordinary geometric intuition makes dimension difficult to picture without right angles. That intuition comes from living inside a mature spatial representation. It should not be imported into the derivation.

To say that two modes are orthogonal normally requires a comparison rule equivalent to an inner product. In a conventional notation, one writes $g(e_i, e_j) = 0$ for $i \neq j$. But the object g is additional structure. Independence asks only whether one admissible mode can be reduced to the others.


The derivational order should therefore remain:

■ independent variation $\rightsquigarrow$ basis-like structure $\rightsquigarrow$ comparison among modes $\rightsquigarrow$ angle $\rightsquigarrow$ orthogonality

The terms basis and span are representational conveniences here. The ontological proposition is thinner: a relational organization can require multiple irreducible ways of changing before any meaningful relation of ninety degrees exists among them.

This distinction becomes especially important if the first effective geometry is skewed, anisotropic, directed, or otherwise unlike Euclidean space.

12.8 Coupled Layers and Collective Modes



d_rank counts the modes that survive, not the controls that went in, and a mode keeps its identity when its realization changes.

Figure 12.2. Coupled layers and collective modes, read as strings and frets on a guitar. Which string and which fret are two independent controls, and the four marked settings — the first string open, the second at the fifth fret, the third at the ninth, the fourth at the fourteenth — all sound the same note. Read formally, the strings and frets are two coupled metric-relational layers, and the local degrees of freedom they carry between them leave fewer modes stable enough to be re-identified. The insight is double. Counting controls is not counting modes, which is why a layer is not a dimension; and the mode keeps its identity when its realization changes, which is the quotient identity of Formalism arriving in geometric dress. The analogy's limit is that a guitar's pitch is one-dimensional because a designer made it so, whereas here the question is whether the rank is fixed by the organization itself, which is what d_R is meant to measure and 12.18 tests a second way.

12.9 Cross-Layer Constraint as a Selection Mechanism

Multilayer organization becomes explanatory only if the coupling among layers does work. Suppose $\mathfrak{L}_1$ admits many local variations and $\mathfrak{L}_2$ admits many others. Once the two organizations constrain one another, some combinations may remain reproducible while others destabilize or disappear under repeated transformation.

The candidate mechanism is therefore selection in relational state space:

■ variation $\rightsquigarrow$ cross-layer constraint $\rightsquigarrow$ selection $\rightsquigarrow$ retention $\rightsquigarrow$ stable collective modes

This is not a new primitive. It is the same recursive logic already used throughout the framework: perturbation generates candidate configurations; constraint eliminates or suppresses some possibilities; retained configurations become available to later organization.

If that process repeatedly stabilizes a small number of collective modes, then effective dimensionality could be lower than the number of microscopic distinctions participating in the substrate. In schematic form, d_{eff} may be much smaller than d_{micro} .

■ $d_{\text{eff}} \ll d_{\text{micro}}$ (candidate possibility)

The inequality expresses only the possibility that a low-dimensional effective geometry can be a compressed description of a much richer relational organization.

12.10 Coordinates Arrive After Stable Modes

Once a family of independent modes is stable enough to be re-identified, coordinates become useful. A coordinate tuple $x \mapsto (x^1, \dots, x^n)$ is then a compressed label for relational position relative to those modes.

Coordinates do not produce the geometry. A different coordinate assignment may describe the same invariant relational organization. The decisive test is whether the relevant relations survive the transformation.

■ coordinate representation $\neq$ geometric ontology

This gives the chapter a useful principle for later physics: if two coordinate descriptions preserve the same relational invariants, their disagreement in labels should not be mistaken for an ontological difference.

In this framework coordinates are therefore earned as efficient representations of stable mode structure, not admitted as primitive addresses in an already existing container.

12.11 Local Metric Coupling

A stable n -parameter description is still not a full local geometry. The modes must also stand in reproducible comparative relations. A mature differential-geometric representation might write $ds^2 = g_{ij}(x) dx^i dx^j$. We should not

treat that formula as foundational here, but it tells us what additional content must ultimately be explained.

The coefficients g_{ij} specify how changes in different local modes contribute jointly to measured separation. From the present relational perspective, they can be interpreted as an effective rule summarizing local coupling among independently resolved modes.

■ $g_{ij} \sim$ effective local relation among variation modes and separation

This interpretation does not claim that every metric tensor is literally generated by multilayer coupling. It identifies a possible ontological role for the metric components if the candidate substrate succeeds.

The direction of explanation remains important: local metric relations should summarize the stable organization that has emerged, rather than being inserted as unexplained numerical fields whose structure the chapter is supposed to derive.

12.12 Effective Smoothness, Not Fundamental Continuity

The existence of stable local metric relations does not require the deepest substrate to be continuous. A finite, discrete, recursive, irregular, or layered organization may admit a regime in which neighboring effective relations vary slowly enough that a continuous approximation preserves the invariants of interest.

Let $\mathfrak{L}^\wedge(\sigma)$ denote the effective geometry at scale regime σ . If coarse-graining over that regime makes discrete changes sufficiently regular, then $\mathfrak{L}^\wedge(\sigma)$ may be approximated by a smooth geometric description.

■ $\mathfrak{L}^\wedge(\sigma) \approx \mathfrak{L}_{\text{smooth}}$ over a declared scale regime

The approximation sign is essential. Local smoothness is an earned modeling relation, not a declaration that reality is fundamentally a continuum.

This permits smooth and nonsmooth regimes to coexist. A domain may be well approximated by differential geometry over one range of scales while containing defects, transition regions, singular limits, or resolutions at which the approximation fails.

■ local smoothness $\neq$ global smoothness

■ effective continuity $\neq$ fundamental continuity

The framework therefore has no need to choose in advance between a fundamentally discrete ontology and a fundamentally continuous one. The empirical burden is to determine which relations survive at which resolution.

12.13 Geometry as a Lossy Resolution

A bounded reference frame does not necessarily resolve every distinction present in the organization it encounters. Earlier chapters already allowed distinct underlying states to become indistinguishable to a given frame. Geometry now applies the same principle to metric organization.

Let the richer relational substrate be $\mathfrak{Q}$. Let Π_F denote the resolution map associated with a bounded frame F . The effective geometry available to that frame may be written:

$$\blacksquare \Pi_F(\mathfrak{Q}) = \mathfrak{Q}_F$$

Projection here does not mean that a known higher-dimensional object is being projected onto an external screen. It means that distinctions in the underlying relational organization are compressed into the subset of invariants recoverable by the frame.


This immediately permits many-to-one resolution:

$$\blacksquare \mathfrak{Q}_a \neq \mathfrak{Q}_b \text{ while } \Pi_F(\mathfrak{Q}_a) = \Pi_F(\mathfrak{Q}_b)$$

The resulting effective geometry can still be objectively useful. Lossy does not mean fictitious. A lossy representation can preserve exactly the relations required for reliable prediction inside its domain.

$$\blacksquare \text{predictive adequacy} \neq \text{ontological completeness}$$

12.14 Stable Projection Does Not Uniquely Fix the Substrate



One probe cannot separate them. A second lamp at another angle can, and that is what cross-frame invariance asks for: agreement across probes that could have disagreed.

Figure 12.3. One stable projection does not fix the substrate. Two different organizations $\mathcal{L}_a$ and $\mathcal{L}_b$ are resolved by the same frame into the same effective geometry, so $\mathcal{L}_a \neq \mathcal{L}_b$ while $\Pi_F(\mathcal{L}_a) = \Pi_F(\mathcal{L}_b)$. The everyday counterpart is a shadow: a cylinder and a cone, lit from one direction, can cast the same circle on the same screen. The insight is that a lossy resolution can be perfectly reliable for what it resolves and still leave the substrate underdetermined, which is why one probe proves little and cross-frame invariance asks for agreement among probes that could have disagreed. The limit of the analogy matters here more than elsewhere: there is no lamp and no screen. Probe, target and resolution are all internal to the same organization, as 12.16 insists.

12.15 Measurement Is an Internal Relation

The projection map becomes more subtle when the frame must actively probe the organization it seeks to resolve. At sufficiently coarse scales, the influence of the measuring system may be negligible relative to the stable structure being measured. At finer scales that approximation need not hold.

A probe is itself a bounded relational system. It is made of the same reality it interrogates. Measurement should therefore be represented as an interaction within the substrate rather than as passive inspection from outside it.

Write I_F for the interaction induced by frame F . A more complete schematic relation is:

$$\blacksquare (\mathcal{L}, F) \xrightarrow{-I_F-} G_{\text{prime}} \xrightarrow{-\Pi_F-} O_F$$

where G_{prime} is the post-interaction relational organization and O_F is the resolved observable. Equivalently:

$$\blacksquare O_F = \Pi_F(I_F(\mathcal{Q}))$$

This separates two forms of information loss. Resolution loss occurs when several substrate distinctions map to the same effective result. Measurement back-action occurs when the coupling needed to resolve the system changes the relation being resolved. They may coexist, but they should not be treated as the same phenomenon.

The chapter does not identify this generic structure with any particular interpretation of quantum measurement. It establishes only the more general possibility that fine-scale observables may be interaction-conditioned projections rather than transparent copies of pre-existing classical properties.

12.16 Projection Onto the Same Organization

There is no ontologically privileged screen onto which the world is projected. Probe, target, detector, and the relations that connect them are all internal to the same organization.

“Reality projecting onto itself” should therefore be read operationally: one bounded subsystem interacts with another, some distinctions survive the interaction and resolution process, and those surviving distinctions become available as a stable effective representation.

■ measurement = relation between bounded subsystems of one relational organization

This formulation rejects both naive transparency and arbitrary subjectivism. What is resolved depends on substrate, frame, and interaction, but cross-frame invariants can still be real constraints imposed by the shared organization.

Objectivity is therefore relocated. It need not mean a view from nowhere. It can mean reproducibility of declared invariants across a sufficiently diverse family of admissible relational viewpoints.

12.17 Stable Projection and Cross-Frame Objectivity

One probe result proves little about the substrate. If frame F_1 yields $\mathcal{Q}_1$ and frame F_2 yields $\mathcal{Q}_2$, their disagreement can arise from different resolution, different coupling, different scale, or genuine structural variation.

But suppose independently constituted probes repeatedly recover the same higher-order invariants H even when their raw outputs differ. Then:

■ $H(\mathcal{Q}_1) \approx H(\mathcal{Q}_2) \approx \dots \approx H(G_n)$

The common structure has stronger standing than any one representation. It is a candidate cross-frame invariant.

We may therefore define effective geometric objectivity as invariance across a sufficiently broad family of admissible probes.

■ effective objectivity = cross-frame stability of declared invariants

This criterion is intentionally demanding. A family of identical instruments may share identical blind spots. Robustness should be tested across heterogeneous interactions whenever possible. Stable agreement is evidence for deeper organization; it is not proof that the resolved representation exhausts that organization.

12.18 When Multidimensional Properties Become Stable

Now suppose many admissible probes differ in their raw representations but repeatedly require the same number of independent local parameters to preserve the geometric relations under study. One frame uses coordinates $(x^1, \dots, x^n)$; another uses $(x_{\text{prime}}^1, \dots, x_{\text{prime}}^n)$. The labels differ, yet reducing the representation below n independent modes destroys distinctions that both frames recover.

That provides a second and operational candidate for effective dimension, alongside the structural one of 12.6:

■ d_{probe} = minimum number of independent parameters required to preserve the declared geometric invariants


The two need not coincide. d_R counts the independent modes the organization itself supports; d_{probe} counts the parameters a family of probes cannot do without. They agree when every structural mode is separately resolvable, and the framework has not shown that they must. The definition is operational but not arbitrary. The invariants must be specified independently, and the dimension must remain stable under admissible changes of probe, representation, and scale over the regime in which the claim is made.

This also gives us a crucial ontological distinction:

■ projected dimension $\neq$ fundamental dimensional complexity

An observed three-dimensional geometry would establish that three independent modes suffice for the stable geometric relations resolved in that regime. It would not, by itself, prove that the underlying organization contains only three relevant relational degrees of freedom at every scale.

12.19 Independence Is Not Orthogonality



Both pairs need two numbers to say where you are. Only the right-hand pair needs no angle to combine them.

Independence is what dimension counts. Orthogonality is an extra comparison rule, and it costs an inner product.

Figure 12.4. Independence before orthogonality. On the left, two irreducible modes δ_1 and δ_2 that are not perpendicular; on the right, the same two at a right angle. The everyday counterpart is two roads leaving a town at forty-six degrees: you still need both numbers to say where you are, and the roads are no less independent for meeting at an awkward angle. The insight is that dimension counts independent ways of varying, while orthogonality is a further comparison rule that costs an inner product the framework has not earned. The analogy's limit is that roads already lie in a space with angles in it; here the angle is what has not yet arrived, and the left-hand case is the general one.

12.20 Curvature as Failure of Global Compatibility

Local geometric coherence does not guarantee global uniformity. Imagine carrying a local comparison standard through a sequence of overlapping neighborhoods and returning to a relationally equivalent starting region. If the returned relation depends on the route taken, the local standards fail to compose into one globally path-independent comparison.

The mature mathematics of differential geometry represents this with connections, parallel transport, and curvature. The present chapter needs only the relational core: curvature-like structure appears when local geometric standards are individually coherent but cannot all be made mutually compatible by one global identification.


■ curvature-like structure = persistent failure of local geometric standards to remain globally compatible

This should not replace the mathematical definition of curvature. It identifies the kind of relational failure that the later formalism is expected to encode.

Curvature is therefore not introduced as a substance or as a bend visible only from outside an embedding. It is an intrinsic higher-order relation among local metric organizations.

12.21 Curvature as Failed Return

carry one comparison standard around a closed route



It comes back rotated. Nothing was done to it on the way, and no outside view was needed to notice.

Curvature is that failure to return equivalently, stated inside the organization rather than from an embedding.

Figure 12.5. Curvature as failed return of a comparison standard. A standard is carried around a closed route through overlapping neighborhoods and comes back rotated, though nothing was done to it along the way. The everyday counterpart is a walk on a globe: from the pole to the equator, a quarter turn along it, and back, keeping a stick pointed the same way at every step. The insight is that the failure is detectable from inside the organization and needs no outside view: curvature is a persistent failure of local standards to remain globally compatible, not a bend visible from an embedding. The analogy's limit is that a globe is already a surface in space, whereas the relational statement asks only that transport around closed routes fail to return equivalently.

12.22 Multilayer Curvature as an Effective Possibility

If several metric-relational layers contribute jointly to the effective geometry, then variation in their coupling can alter the geometry resolved by a coarse

probe even when each lower-order layer remains locally coherent in its own terms.

Suppose $K_{12}(A)$ differs from $K_{12}(B)$. A probe that does not separately resolve $\mathfrak{L}_1$ and $\mathfrak{L}_2$ may register only the changed collective relation. In the effective description, that variation may appear as a deformation of metric structure.

■ variation in cross-layer coupling $\rightsquigarrow$ variation in effective metric relations (candidate)

This is one of the chapter's most speculative proposals. It should be treated as a generative hypothesis to be modeled, not as an interpretation imposed on known gravitational geometry.

Its attraction is ontological economy: it asks whether a higher-order geometric property can arise from changing relations among structures already admitted, rather than requiring a new geometric substance at each descriptive level.

12.23 The Substrate Can Be Richer Than the Stable Geometric Projection

Consider a substrate that supports many lower-order relational modes δ_1 through δ_N . Under a particular family of interactions, only a smaller number of collective combinations remain independently resolvable. If three such modes dominate over a broad scale regime, the effective geometry available to those probes may be rank three.

■ $\Pi_F(\mathfrak{L}) \mapsto \mathfrak{L}_F^{\wedge}(3)$ while the underlying $\mathfrak{L}$ may remain structurally richer

Nothing in that statement requires hidden dimensions in the specific sense used by any existing high-energy theory. The unresolved distinctions might instead be strongly coupled, below the probe's resolution, dynamically suppressed, topologically constrained, or simply irrelevant to the invariants that define spatial position.

The weaker and more defensible proposition is therefore:

■ observed dimensionality = dimensionality of stable resolvable geometric variation

Whether that dimensionality is also fundamental is a further question.

12.24 The Projection Problem

The language of projection creates an immediate danger. If every inconvenient observation can be declared a lossy projection of an invisible substrate, the hypothesis cannot fail and therefore explains nothing.

A legitimate projection model must independently constrain three things: the candidate substrate $\mathfrak{Q}$, the interaction I_F , and the resolution map Π_F . These cannot all be chosen after seeing the output that the model is supposed to explain.

■ $\mathfrak{Q}$ + independently constrained interaction rules + independently constrained resolution $\rightsquigarrow$ predicted effective geometry

The strongest test is generative. Begin with admissible lower-order relations that contain no target coordinates or preferred dimensionality. Let the system organize under independently specified constraints. Then measure the stable effective rank and metric relations using probes that were not tuned to return the desired answer.

If the analyst must insert three-dimensional adjacency, Euclidean neighborhoods, or the target embedding into the update rules, the model has reproduced the conclusion by construction rather than earned it.

12.25 Computational Diagnostics

Relabeling invariance. Renaming lower-order elements must not change the effective geometry.

Representation invariance. Equivalent graph, hypergraph, matrix, tensor-network, or other faithful encodings should preserve the declared geometric invariants.

Decomposition perturbation. Small arbitrary changes in descriptive partition should not radically alter the effective geometry unless they correspond to genuine changes in the organization.

Hidden-dimension control. No coordinate tuple, target dimensionality, Euclidean neighborhood, or embedding may be encoded in the generative rules if dimensionality is the quantity being tested.

Rank recovery. The number of stable independent modes should be measured from the generated organization rather than stipulated.

Probe robustness. Heterogeneous admissible probes should recover the same higher-order geometric invariants over the regime in which effective objectivity is claimed.

Scale transition. Coarse-graining may change lower-order distances, but it should preserve the declared higher-order relations when the effective geometry is claimed to survive.

Curvature diagnostic. Route-dependent failure of relational standards to return equivalently should be distinguished from artifacts introduced by coordinate representation or probe asymmetry.

Random-control comparison. Candidate multilayer systems should be compared with matched random organizations to test whether low-dimensional coherence is selected rather than ubiquitous.

Failure visibility. If no stable rank, neighborhood structure, or cross-frame invariant emerges, the result should count against the candidate mechanism rather than being redescribed as a different hidden geometry.

12.26 A Dimensionality Research Program

A serious model should begin without a fixed target dimension. Construct a relational substrate from previously earned ingredients. Allow its coupled relations to update or stabilize according to rules that do not contain coordinate triples, Euclidean adjacency, or a preferred three-dimensional embedding.

At several organizational scales u , estimate the minimum number of independent collective modes required to preserve the declared metric relations. This yields a scale-dependent effective dimension $d_{\text{eff}}(\sigma)$.

■ $\sigma \mapsto d_{\text{eff}}(\sigma)$

The model should be allowed to fail. The effective rank may grow, fluctuate, collapse, vary by region, or settle near a noninteger value. Any of those outcomes is more informative than forcing the system toward three.

The particularly strong result would be spontaneous convergence toward a broad rank-three regime without the value three having been privileged in the rules:

■ $d_{\text{eff}}(\sigma) \rightarrow 3$ over a broad stable regime

Such a result would not demonstrate physical space. It would show that low-dimensional geometric organization can arise from the candidate relational machinery without target dimensionality being inserted beforehand.

12.27 A Projection-Stability Research Program

Once a candidate effective geometry emerges, probe it in multiple ways. Let F_1 through F_n differ in coupling architecture, resolution threshold, sampling path,

and coarse-graining strategy while remaining admissible under independently declared criteria.

For each frame calculate $O_i = \Pi_{Fi}(I_{Fi}(\mathcal{L}))$. Extract the invariant family H from each effective result. The hypothesis predicts approximate agreement of H across the regime in which a common geometry is claimed.

$$\blacksquare H(O_1) \approx H(O_2) \approx \dots \approx H(O_n)$$

A geometry that appears only under one specially tuned probe is weak evidence. A geometry whose rank, neighborhood relations, and curvature diagnostics survive diverse probing is substantially stronger.

This test operationalizes the chapter's central epistemic stance: an observed representation can be frame-relative and lossy while the invariants recovered across frames remain objective constraints on the underlying organization.

12.28 Competing Interpretations

The same successful effective geometry can support several interpretations. One may regard the geometry itself as fundamental. Another may regard it as emergent from non-geometric relations. A third may propose several metric-relational layers whose coupling produces the effective structure. A fourth may treat geometry primarily as a compact language for stable invariants without committing to geometry as a separate ontological entity.

This chapter does not decide among those possibilities merely by introducing multilayer notation. Its candidate claim is conditional: if independently constrained relational layers generate stable low-dimensional metric organization whose invariants survive scale change and heterogeneous probing, then effective geometry can be explained without assuming its familiar dimensional form at the foundation.

That would thin the ontology. If the construction fails and stable geometry requires an irreducible geometric primitive, the framework should stop the reduction there rather than conceal the failure behind new terminology.

12.29 Objections and Replies

Objection 1: This merely renames extra dimensions. **Reply:** A layer is a family of relational constraints, not a coordinate direction. Layer count and dimension count are independent quantities. If each layer is silently assigned an axis, the derivation has failed.

Objection 2: Calling the substrate geometric assumes geometry. **Reply:** This is why the foundational term should be metric-relational layer. Geometry is reserved for the higher-order organization that emerges when such layers acquire stable neighborhoods, independent modes, and coherent transformations.

— — — —

Objection 3: A metric already determines a topology. **Reply:** Mathematically, a metric can induce a topology. Ontologically, the chapter asks whether the induced neighborhood structure is stable, scale-coherent, and physically significant rather than merely definable in the meta-theory.

— — — —

Objection 4: Projection makes reality observer-dependent. **Reply:** Frame dependence does not imply arbitrariness. Different frames can resolve different lower-order details while recovering the same higher-order invariants. Objectivity is assigned to what remains stable across admissible interactions, not to one privileged representation.

— — — —

Objection 5: The projection hypothesis is unfalsifiable. **Reply:** It becomes unfalsifiable only if substrate, probe, and projection map are chosen after the result. The chapter explicitly requires them to be independently constrained and tested against hidden-dimension and random controls.

— — — —

Objection 6: Fine-scale measurement back-action is being smuggled in from quantum mechanics. **Reply:** No specifically quantum law is assumed. The weaker proposition is that a measuring system can physically interact with the system it measures. Quantum measurement may later provide one important realization of that general relation.

— — — —

Objection 7: Why should stable low-dimensional modes appear at all? **Reply:** The proposed mechanism is selection under cross-layer constraint, but this remains a research hypothesis. Computational models must demonstrate whether such selection actually occurs under non-tuned rules.

— — — —

Objection 8: Smooth geometry cannot emerge from a discrete substrate. **Reply:** The chapter does not assert that it must. It proposes a scale-dependent approximation criterion: if coarse-grained relations preserve the relevant invariants while varying regularly, a smooth description may become effective even if the lower-order organization is not continuous.

— — — —

Objection 9: Curvature requires differential geometry, so the chapter cannot derive it relationally. **Reply:** The chapter does not replace differential curvature with a verbal

definition. It identifies path-dependent incompatibility among local standards as the relational phenomenon for which differential curvature is a mature mathematical representation.

Objection 10: The proposal explains any observed dimensionality after the fact.

Reply: Not if target dimensionality is excluded from the rules and d_{eff} is measured rather than stipulated. The candidate rises or falls on whether stable dimension emerges generatively.

12.30 What Geometry Has Earned

If the candidate derivation succeeds, Geometry earns more than Distance but less than Space. It earns stable metric neighborhoods, higher-order constraints among distances, the possibility of several coupled metric-relational layers, rank-like independent collective modes, candidate effective dimension, coordinate representations of those modes, scale-dependent smooth approximation, and curvature-like incompatibility among local standards.

It also earns a disciplined distinction between underlying relational organization and the effective geometry recovered by a bounded probe.

stable multidimensional geometry may be an invariant effective projection of a relational substrate richer than the geometry resolved by any one bounded frame

This is the chapter's strongest speculative proposition. Its value depends entirely on whether the proposed substrate, interactions, and resolution maps can eventually be formalized and tested independently.

12.31 What Geometry Has Not Yet Earned

Geometry has not yet established that its dimensions are physical spatial dimensions. It has not established that three dimensions are uniquely selected. It has not shown that the substrate is fundamentally continuous or discrete. It has not shown that the effective geometry is globally smooth. It has not derived matter, quantum fields, particles, metric time, spacetime, gravity, energy, action, or causal speed.

It has not shown that a measured field excitation is literally a projection from a multilayer geometric substrate. It has established only a conceptual route by which interaction-conditioned projection could preserve stable multidimensional invariants while remaining ontologically incomplete.

It has not shown that curvature is gravity. It has not shown that measurement back-action is quantum collapse. It has not shown that every physical property can be reduced to geometry.

Those restrictions are strengths. They keep the chapter from converting a candidate generative mechanism into a total ontology before the necessary bridges have been built.

12.32 Ontological Defensibility Pulse: Geometry

This table applies the recurring Ontological Defensibility Pulse to the chapter's central proposition. It is separated from the main argument so that it can be skipped on a first reading.

Pulse question	Applied to Geometry
1. Entities required	No new substance is intended: relational loci, metric relations, higher-order constraint families, bounded resolving frames, and interactions among them.
2. Ontological level	Higher-order metric organization: relations among systems of relational distances rather than distance between isolated loci.
3. Lower-order dependencies	Distinction, retained difference, Relation, Closure, Orientation, Return, Formalism, Scale, and Distance.
4. Candidate emergent properties	Stable neighborhoods, coupled metric-relational layers, independent collective modes, effective dimension, coordinate-like representations, scale-dependent smoothness, and curvature-like compatibility failure.
5. Claim types	Formal on induced neighborhoods and independence before orthogonality; relational on cross-frame invariance; speculative on multilayer selection, projected dimensionality, and coupling-generated effective curvature.
6. New primitives	None intended. The largest risks are hidden primitives introduced through arbitrary layer decomposition, probe definition, or a hand-chosen projection map.
7. Fewer assumptions?	The chapter strengthens if low-dimensional geometry emerges without target dimension, coordinates, or embedding. It weakens whenever familiar geometry must be inserted into the generative rules.

Pulse question	Applied to Geometry
8. Observational / computational constraints	Hidden-dimension controls, random controls, rank recovery, heterogeneous-probe robustness, scale-transition consistency, and explicit failure criteria.

12.33 Implications and Handoff

Distance asked how far apart relational loci can be. Geometry asks what happens when many such separations cease to stand alone and begin constraining one another.

The candidate derivational sequence is:

distance ⇌ neighborhood ⇌ metric constraint ⇌ multilayer coupling ⇌ independent collective modes ⇌ effective dimension ⇌ geometry

A second sequence concerns observation:

■ relational substrate ⇌ measurement coupling ⇌ resolution loss ⇌ stable invariant projection

Together they permit a possibility that was unavailable before Distance: the familiar dimensional structure of an observed domain may be neither arbitrary nor ontologically exhaustive. It may be the stable relational form that survives when bounded subsystems interact with a deeper organized geometry.

We have therefore earned a candidate geometry. We have not yet earned physical space.

A geometry can possess dimension mathematically without those dimensions being physical extension. A stable projection can support near, far, orientation, dimensional rank, and curvature-like structure without yet establishing that its loci are places.

The next question is therefore:

When does effective geometric organization become physical spatial extension?

Handoff to Space. Geometry gives coherent multidimensional organization to relational distance. Space must determine when that geometry becomes physically instantiated as locality, extension, adjacency, and spatial position for interacting reference frames.

Distances can now organize into stable neighborhoods whose independent modes can support a candidate dimension.

Questions Opened by This Framework

Can an initially non-geometric or minimally metric relational substrate stabilize into a low-dimensional effective geometry without target dimensionality being encoded in its rules?

Can several metric-relational layers generate collective dimensions whose number differs from the number of layers?

What formal criterion best captures independence of relational modes before vector spaces and inner products are available?

Under what conditions does coarse-graining preserve dimensional rank?

Can a noninteger or scale-dependent relational dimension converge toward an integer effective dimension?

What independently constrains the decomposition of a substrate into layers?

What independently constrains an admissible probing reference frame and its resolution map?

Can distinct measurement couplings recover the same geometric invariants while producing different lower-order observables?

How much probe dependence is compatible with calling an effective geometry objective?

Can cross-layer coupling generate effective curvature without assuming a curved manifold at the substrate level?

Can smooth differential geometry arise as a controlled approximation of discrete, recursive, or irregular relational organization?

What conditions distinguish genuine emergent dimension from dimension inserted through graph construction, neighborhood rules, or target functions?

Can a computational model generate an approximately rank-three stable regime without encoding three-dimensional coordinates, adjacency, or embedding?

Can several inequivalent substrates project to the same effective geometry, and if so, what observations could distinguish them?

Can the same projection framework later explain why stable field-excitation observables appear object-like without reducing those observables to literal microscopic objects?

At what point does a stable geometric projection deserve the stronger interpretation physical space?

Selected References Cited in Geometry

The chapter's generative claims remain candidate hypotheses until formal models and discriminating tests are supplied.

Burago, D., Burago, Y., & Ivanov, S. (2001). *A Course in Metric Geometry*. Graduate Studies in Mathematics 33. Providence, RI: American Mathematical Society. doi:10.1090/gsm/033. Used as a standard reference for metric spaces, length structures, and convergence ideas relevant to the transition from distance to geometry.

Gromov, M. (1999). *Metric Structures for Riemannian and Non-Riemannian Spaces*. Birkhauser. Used as a mathematical comparison class for intrinsic metric structure without a required ambient embedding.

Lee, J. M. (2018). *Introduction to Riemannian Manifolds*, 2nd ed. Springer. Used as a mathematical reference for the mature concepts of local metric tensors, smooth manifolds, connections, and curvature that the chapter treats as later representations rather than primitives.

Oxley, J. (2011). *Matroid Theory* (2nd ed.). Oxford Graduate Texts in Mathematics 21. Oxford: Oxford University Press. Used as a formal comparison for independence and rank without presupposing Euclidean orthogonality.

Chapter 13

Space: When Geometry Becomes Coordinated

Claim ~ Space becomes available when distinct loci in an effective geometry are coordinated as stable localization relations: their positions cannot vary independently of the larger organization, and their neighborhoods constrain which couplings are available. Geometric separation then becomes physically consequential as locality, extension, adjacency and position, all earned from the relations themselves.

Chapter discipline. Space inherits everything earned through Geometry, in particular neighborhoods, independent modes of variation and effective dimensionality. Its burden is to coordinate them into space; duration and propagation are left to Time.

Its burden is narrower:

What additional organization makes a geometric locus a spatial location?

Geometry has already shown how many relational distances can become coherently organized. It has explicitly stopped short of identifying those geometric loci with physical places. Space begins at that withheld identification.

■ geometry $\rightsquigarrow$ joint resolvability $\rightsquigarrow$ coordinated localization $\rightsquigarrow$ consequential locality $\rightsquigarrow$ extension $\rightsquigarrow$ space

13.1 Geometry Can Exist Without Space

A geometry may possess metric relations, neighborhoods, dimensional rank, and transformations without thereby constituting physical space. A map has geometry. A graph may have metric structure. A mathematical manifold may have curvature. None of those facts alone establishes that its loci are places in which physically consequential relations occur.

■ geometric locus $\neq$ spatial location

Geometry organizes separation. Space must make that organization consequential. This distinction prevents a familiar intuition from doing hidden explanatory work. Once a diagram contains points, lines, and distances, it is easy to imagine those points as already located somewhere. But the diagram is a representation available to us. The ontology has not yet earned what the diagram depicts.

The problem is therefore not to place geometry inside space. It is to determine when geometry itself deserves the interpretation space.




Figure 13.1. A mouse can traverse a maze blueprint in one step to find the cheese, and needs twenty-nine steps to reach the same cheese in a maze built from that blueprint. Both panels carry the same maze: the same cells, the same walls, the same entrance at the lower left and the same cheese. The geometry is identical and the difference is entirely in what it costs to do something, which is this chapter's opening distinction: geometry organizes separation, and space makes the organization consequential. A wall is the familiar way to make a constraint visible, and constraint rather than masonry is what the figure is about: Matter arrives much later, and what makes the built case spatial is that the arrangement bears on what can be done.

13.2 Coordination Is Not Coordinates

■ coordination $\neq$ coordinates


Coordinates are representational labels assigned to an already-organized domain. For example, (x1, x2, x3) may identify a geometric position once sufficient structure exists to support such a representation.

Coordination means something deeper. Geometric loci are coordinated when their localization relations are mutually constrained such that changing the localization of one locus changes some larger pattern of relations by which that locus is situated relative to others.

Suppose A, B, and C belong to one geometric organization. Then changing A's localization may alter $d(A,B)$, $d(A,C)$, its neighborhood membership $N(A)$, and

the relational pathways through which A can couple to the surrounding domain. The essential condition is therefore not that A has a numerical address. It is that A's position has consequences for the rest of the organization.

coordinates describe position; coordination constitutes mutual position



Coordinates describe position. Coordination constitutes it: renaming a seat changes nothing, moving it changes everything.

Figure 13.2. Coordination is not coordinates. Move B and every relation around it moves with it; rename B and nothing changes at all. The everyday counterpart is a theatre: shifting one seat alters its neighbours, the aisle and the view of the stage, while relabelling it row 4, seat 12 alters nothing. The insight is that coordinates describe position and coordination constitutes it, so a spatial position is a role in a mutually constraining organization rather than a label attached to a thing. The analogy's limit is that a theatre is already built in space, whereas here the constraint among localizations is what space is made of.

13.3 Geometric Coherence Is Not Spatial Coordination

Geometry already required coherence. Distances could not simply be arbitrary values. Their higher-order organization had to support stable neighborhoods, compatible transformations, and reproducible structure across scale. But coherence does not yet imply coordination in the present sense.

■ geometric coherence $\neq$ spatial coordination

Geometric coherence means that the metric relations fit together as a consistent geometry. Spatial coordination means that geometric localization relations mutually constrain the roles available to instantiated relational structures.

■ consistent geometric relation $\rightsquigarrow$ mutually consequential localization relation

A mathematical geometry can remain unchanged whether or not anything physically depends upon its locations. A spatial geometry cannot.

13.4 Joint Resolvability Without Simultaneity

Before two loci can be spatially related, they must be jointly available within one effective relational organization. Let $\text{Joint}(A,B)$ mean that A and B are recoverable as distinct loci within the same effective geometry Geo.

■ $\text{Joint}(A,B) \neq A \text{ and } B \text{ exist at the same time}$

At this stage joint resolvability means only that both loci participate in one relational configuration from which their mutual geometric organization can be resolved. A safer vocabulary is therefore joint instantiation, joint resolvability, or configurational copresence.

The ontology has earned plurality within one configuration.

13.5 Localization Is a Relational Role

Ordinary language treats location as though an object first exists and is then assigned a position. The present framework reverses that dependence. A spatial location is not primitively possessed. It is constituted by relations.

Let $\lambda_{\text{Geo}}(A)$ denote the geometric relational profile through which A is situated within Geo. Then define a candidate localization class:

■ $\text{Loc}(A) = [\lambda_{\text{Geo}}(A)]_{\sim\text{Sp}}$

where $\sim\text{Sp}$ identifies lower-order realizations that preserve the geometric profile through which A is situated. Calling those relations spatially relevant would be premature here, since spatial relevance is precisely what 13.6 goes on to define: they become spatial once they are mutually coordinated. A location can therefore remain stable even while its microscopic realization changes.

■ $A' \neq A$, while $\text{Loc}(A') \sim \text{Loc}(A)$

This continues an argument already used repeatedly throughout the framework: higher-order identity does not require microscopic identity of every constituent. Now that principle applies to position itself.

13.6 Localizations Constrain Localizations

This is the central conceptual step. Suppose A, B, C, and other loci are jointly resolvable. Their organization becomes spatially coordinated when the localization of one cannot be varied freely without changing the relational localization structure around it.


■ $\Delta L(A) \mapsto \Delta \{ d(A,B), d(A,C), N(A), \dots \}$

The precise formal criterion remains to be developed, but the conceptual requirement is clear: spatial localizations are not independently assignable.

This repeats a pattern that appeared much earlier in the derivation. Relation became structurally significant when relations constrained relations. Geometry became significant when distances constrained distances. Space now appears when localizations constrain localizations.

■ relations constrain relations $\rightsquigarrow$ distances constrain distances $\rightsquigarrow$ localizations constrain localizations

That recursion is not decorative. It identifies the new organizational level. A point has become a place only when its placement belongs to a larger mutually constraining organization.



The same panel, somewhere else. No wall is added and none is taken away, and every route in the maze is different.

Figure 13.3. Localizations constrain localizations, read as one panel moved. The maze on the left is the one built in Figure 13.1, and the route to the cheese runs twenty-nine steps. On the right a single panel has been lifted from one place and set down in another: nothing is added, nothing is removed, and the same cheese is now thirteen steps away. The insight is that no localization in a coordinated organization can be varied on its own. Change where one element sits and the distances, the neighborhoods and the available routes among all the others change with it, which is what distinguishes spatial coordination from mere geometric coherence.

13.7 From Geometric Position to Spatial Position

■ reference state $\rightsquigarrow$ relational locus $\rightsquigarrow$ metric locus $\rightsquigarrow$ geometric locus $\rightsquigarrow$ spatial position

A relational locus is distinguishable by its relations. A metric locus participates in recoverable separation magnitude. A geometric locus participates in coherent higher-order organization among those separations. A spatial position participates in coordinated localization such that its geometric relations constrain the organization of the surrounding domain.

■ spatial position = stable localization role within coordinated geometry

Coordinates may later represent this role. They do not generate it.

13.8 Physical Consequence Without Presupposing Matter

Calling this organization physical risks circularity unless the term is constrained. At this stage, physical does not mean material.

A narrower criterion is available: a geometric distinction becomes physically consequential when changing it changes the admissible relational organization of other instantiated structures rather than merely changing an investigator's description.

Let $\text{Adm}(A,B \mid \text{Geo})$ denote the set of couplings admissible between A and B under geometric organization Geo. If $\text{Geo} \neq \text{Geo}'$ and this difference produces $\text{Adm}(A,B \mid \text{Geo}) \neq \text{Adm}(A,B \mid \text{Geo}')$, then the geometric distinction has consequences for relational organization.

■ physical spatiality = geometry with constitutive relational consequences

■ physical $\neq$ material

Matter can arrive later.

13.9 From Neighborhood to Locality

Geometry already supplies candidate neighborhoods. For example, $N_{\text{epsilon}}(A) = \{ B : d(A,B) < \text{epsilon} \}$. But a geometric neighborhood does not automatically constitute physical locality. To earn locality, neighborhood structure must constrain relational accessibility.

■ $\text{Adm}(A,B) = f(L(A), L(B), \text{Geo})$

This does not require nearer to mean stronger. Nor does locality require all coupling to be strictly local. The weaker and more defensible requirement is that geometric organization systematically constrain relational accessibility.

■ geometric neighborhood + consequential accessibility $\rightsquigarrow$ physical locality

Quantum Graphity provides a useful comparison class because it explicitly explores models in which locality and low-dimensional geometry arise dynamically from graph structure rather than being fixed background assumptions (Konopka, Markopoulou, & Severini, 2008). That work uses a specific quantum graph ontology; it demonstrates that emergent locality is a technically meaningful research target.


13.10 An Edge Is Not a Spatial Neighbor

■ edge $\neq$ spatial adjacency

Primitive incidence may represent dependency, constraint, transformation, correspondence, or some other relation. It becomes spatial adjacency only after several additional conditions are satisfied.

■ incidence $\rightsquigarrow$ metric neighborhood $\rightsquigarrow$ stable coordination $\rightsquigarrow$ consequential locality $\rightsquigarrow$ spatial adjacency

A candidate adjacency relation should survive relevant coarse-graining, coordinate removal, heterogeneous probing, perturbations that do not destroy the higher-order regime, and independent tests of relational accessibility. Otherwise spatiality may have been encoded in the representation rather than generated by the system.



Nearness on the page is an artifact of drawing. Locality has to be a fact about the relations, and the test is whether it survives being redrawn.

Figure 13.4. Page adjacency is not locality. On the left, A and B sit beside each other and share no relation; on the right the same network is redrawn and the genuinely related pairs stay related. The everyday counterpart is any network diagram, where what looks close is an artifact of the drawing. The insight is the test rather than the picture: locality must survive redrawing, the same invariance Relation applied to labels and Geometry applied to representations. The limit is that no drawing shows locality directly, only its stability under changes of layout.

13.11 Extension as Non-Collapsible Coordinated Difference

If A and B occupy non-equivalent localization classes, $L(A) \neq L(B)$, then there is spatial plurality. But not every plurality is yet extension.

Suppose collapsing the two classes, $L(A), L(B) \mapsto L$, destroys at least one declared spatial invariant H , so that $H(Geo) \neq H(Geo/L)$. Their distinction is then structurally irreducible at that scale.

■ extension = non-collapsible plurality of coordinated localization

Extension therefore does not have to be introduced as an independently existing continuum. It emerges because distinct spatial localization roles cannot be collapsed without changing the organization itself.

13.12 Spatial Distance Is Not Merely Relational Distance

■ relational distance $\neq$ spatial distance

The progression is mediation burden $\rightsquigarrow$ metric separation $\rightsquigarrow$ geometric separation $\rightsquigarrow$ spatial separation. Spatial distance is not a wholly new metric. It is an already-earned metric relation interpreted within coordinated physical localization.

■ $d_s(A,B) = d_G(L(A), L(B))$

This distinction matters because the ontology can possess distance-like structure before anything deserves to be called spatially far away.

13.13 Dimension Becomes Spatial Dimension

Geometry has already earned independent collective modes of variation, represented schematically as $\delta_1, \delta_2, \dots, \delta_n$. Nothing in Geometry required that every such mode correspond to physical spatial extension.

A geometric mode becomes a spatial dimension when variation along that mode changes localization within the coordinated physical domain.

■ geometric independent mode + localization consequence $\rightsquigarrow$ spatial dimension

■ $d_{\text{relational}} \neq d_{\text{geometric}} \neq d_{\text{spatial}}$

A richer substrate can therefore possess more organization than any bounded frame resolves as physical spatial dimensionality.

Cao, Carroll, and Michalakis (2017) provide a useful neighboring comparison: they construct an emergent geometry from entanglement relations and use multidimensional scaling to recover best-fit spatial dimensionality. Their proposal begins with Hilbert-space structure, so here it serves diagnostically: it shows a route for testing whether non-spatial organization can yield an effective spatial manifold.

13.14 Space Need Not Be Fundamentally Smooth

Once a spatial domain is recovered at one scale, it is tempting to infer that its smoothness belongs to the substrate. That inference is not warranted.

Let ℓ_r denote a characteristic scale of unresolved relational organization and ℓ_F the effective resolving scale of a probing frame. When $\ell_r \ll \ell_F$, many lower-order distinctions may be integrated into one resolved neighborhood.

■ $\text{Geo}_F \sim \text{Geo}_{\text{smooth}}$

The correct claim is therefore that effective smoothness does not imply fundamental continuity.

Causal-set theory provides a mature example of the broader possibility that discrete underlying organization can approximate continuum spacetime. Its specific causal partial order is not being adopted here (Bombelli, Lee, Meyer, & Sorkin, 1987).

Loop-quantum-gravity constructions likewise provide precedent for treating quantities associated with geometry, such as area and volume, as possessing discrete spectra in a deeper description rather than presupposing a fundamentally continuous geometry. Spin networks and the loop representation show that smooth effective geometry and fine-scale discreteness are not logically incompatible (Rovelli and Smolin, 1995a, 1995b).

13.15 A Breakdown of Smoothness Is Not the Bottom Layer

Consider an ordinary road. At the scale of a vehicle, asphalt behaves approximately as a smooth surface. The tires need not resolve each grain of

aggregate or the molecular structure of the binder in order to respond to the road's curvature.

A pothole changes this. The vehicle now encounters a resolvable failure of the smooth-road approximation. But encountering the pothole does not suddenly reveal the molecular structure of asphalt.


■ detecting non-smoothness $\neq$ resolving fundamental structure

The same possibility must remain open for effective geometry. A failure of smoothness at one scale may expose only an intermediate organizational regime.

■ fine relational distinctions $\rightsquigarrow$ local geometric microstructure $\rightsquigarrow$ mesoscopic irregularity $\rightsquigarrow$ smooth effective space

A probe may therefore encounter a geometric analogue of a pothole without reaching the finest relational distinctions from which the geometry ultimately derives.

■ failure of one coarse-graining $\neq$ access to ontology's terminal level



Detecting where a smooth description fails is not the same as reaching the level beneath it.

Figure 13.5. Effective smoothness and what lies beneath it. Four levels of organization, with a probe that reaches the second and stops. The everyday counterpart is a road: at the scale of a vehicle the asphalt is smooth, a pothole is a resolvable failure of that smoothness, and the tyre still never resolves the aggregate or the molecular structure below it. The insight governs how any evidence of granular geometry should be read: detecting where a smooth description fails is not the same as reaching the level beneath it, and the failure of one coarse-graining is not access to the terminal level of the ontology. The analogy's limit is that a road has a known bottom, and the framework does not claim to know its own.

13.16 Spatial Coordination Can Be Responsive

Nothing in the definition of coordination requires the resulting spatial organization to be rigid. If the lower-order relational organization changes, the localization relations it supports may change with it.

■ $\text{Geo}_n \mapsto \text{Geo}_{n+1}$

A distributed relational transformation Φ might alter local couplings, $\Phi \mapsto \Delta K_{ij}$, which in turn alter effective metric relations, $\Delta K_{ij} \mapsto \Delta d_{ij}$, and therefore neighborhood organization, $\Delta d_{ij} \mapsto \Delta \text{Geo}_{\text{eff}}$. The resulting geometry can then constrain subsequent relational transformation.

■ $\Phi \mapsto \Delta \text{Geo}_{\text{eff}} \mapsto \Delta \Phi'$

relational transformation $\leftrightarrow$ spatial coordination

This is a candidate proposition, not yet a derived dynamical law. It does not establish gravity. It does not establish quantum dynamics. It only prevents Space from being prematurely defined as an immutable stage on which later physical processes must occur.

Cao, Carroll, and Michalakis (2017) provide an interesting diagnostic comparison because perturbations of their underlying entanglement structure lead to changes in recovered spatial curvature. Their mechanism is specific to their Hilbert-space construction; the relevance here is only the broader possibility that effective geometry can respond to changes in deeper relational organization.




Figure 13.6. Responsive coordination. A distributed relational transformation alters couplings, which alter separations, which alter the effective geometry, and the altered geometry then constrains what the next transformation can do. The loop is

the content: coordination need not be rigid, and a space that responds is still a space. The analogy is deliberately thin here, because the familiar case would be gravitation and that is precisely what the figure does not claim. It shows a candidate proposition to be modelled, not a dynamical law.


13.17 Smooth Neighborhoods and Irregular Regions Can Coexist

Effective smoothness need not be globally uniform. A single coordinated spatial domain can support locally smooth neighborhoods together with mesoscopically irregular transition regions.

Suppose several distributed relational transformations $\Phi_1, \Phi_2, \dots, \Phi_m$ intersect. If their effects on the underlying organization are nonlinear, then $\Delta G(\Phi_1 + \Phi_2) \neq \Delta G(\Phi_1) + \Delta G(\Phi_2)$. Intersections can therefore generate organization not present in either transformation independently.

The word turbulent should remain analogical unless the mature dynamics exhibit genuinely turbulence-like properties such as nonlinear transfer across scales, characteristic spectra, cascade structure, or related mathematical signatures.

- intersecting transformations + nonlinear response $\rightsquigarrow$ multiscale geometric irregularity
- irregular geometric response $\neq$ derived turbulence



Coordination need not be rigid. A responsive space is still space, and this is a proposition to be modelled, not a dynamical law and not gravity.

Figure 13.7. Smooth neighborhoods and an irregular region in one domain. Two distributed transformations cross, and where they meet their effects do not simply add. The everyday counterpart is a junction where two orderly flows of traffic tangle while the roads either side stay orderly. The insight is that effective smoothness need not be uniform: one coordinated domain can hold smooth neighborhoods and mesoscopically irregular regions at once. The limit is the section's own: turbulent remains an analogy until nonlinear transfer across scales, characteristic spectra or a dimensionless control parameter is actually derived.

13.18 Relational Rescaling Can Alter Space Without Destroying Locality

Spatial coordination also allows a distinction between local structural persistence and global metric persistence. Suppose local neighborhoods remain approximately invariant while larger-scale separations change.

- $N_n(A) \sim N_{n+1}(A)$, while $d_{n+1}(A,B) > d_n(A,B)$

A localization role can remain identifiable, $L_n(A) \sim L_{n+1}(A)$, without preserving every metric relation to distant loci.

- persistence of localization $\neq$ persistence of global metric separation

This preserves a conceptual route by which later cosmological expansion could be interpreted as evolving relational scale rather than motion through an external container. That interpretation is not derived here. Space merely keeps the possibility structurally available.

13.19 Boundary Can Now Become Spatial

Boundary was introduced earlier as preserved non-equivalence, not as a wall or surface. Only now can that earlier distinction acquire literal spatial realization. Suppose a domain D contains localization classes whose relations distinguish membership in D from non-membership. Once those classes are spatially coordinated, a relational membership boundary may be represented geometrically as partial D .

- relational boundary $\rightsquigarrow$ geometric boundary $\rightsquigarrow$ spatial boundary

Only at this stage do familiar terms such as inside, outside, region, enclosure, and surface acquire literal spatial interpretation.

13.20 Closure Is Still Not Enclosure

Spatial realization must not erase the earlier distinction between Closure and Boundary. A system may be dependency-closed without occupying a spatially enclosed region. A region may be spatially enclosed while remaining relationally open.

- closure $\neq$ enclosure

Once Space exists, however, enclosure can become one possible realization of relational closure. This distinction will later become important wherever spatial membranes, bounded physical systems, or higher-order self-maintaining structures appear.

13.21 Space Is Intrinsic Before It Is Embedded

Nothing yet requires the spatial domain to sit inside a larger spatial container. If its localization relations are internally sufficient, then physical spatiality does not require external spatial embedding.

An embedding may be mathematically useful, for example $\iota: S \rightarrow E$. But the existence of E cannot be inferred merely because such a representation is convenient. The intrinsic relations remain primary.

13.22 Spatial Objectivity Is Cross-Frame Invariance

Different probing frames may represent the same spatial organization differently. Let $Sp_F = \Pi_F(I_F(R))$ denote the spatial organization resolved through interaction I_F and frame-relative resolution map Π_F .

We need not require $Sp_{F1} = Sp_{F2}$ at the level of raw representation. What matters is whether declared spatial invariants agree across admissible heterogeneous probes.

$$H(Sp_{F1}) \sim H(Sp_{F2}) \sim \dots$$

■ spatial objectivity = cross-frame stability of coordinated localization invariants

This guards against two opposite errors: treating frame-dependent representation as evidence that space itself is subjective, and treating one frame's representation as ontologically exhaustive. Neither follows.

13.23 Candidate Formal Criterion for Space

Let an effective geometric organization be $Geo = (X, d, N, K)$, where X is a family of recoverable loci, d represents inherited metric organization, N represents effective neighborhoods, and K represents admissible relational couplings. A candidate spatial regime S is present when the following conditions jointly hold:

Condition	Candidate requirement
1. Joint resolvability	There exist distinct loci A and B recoverable within one effective geometric configuration.
2. Stable localization	$Loc(A)$ and $Loc(B)$ remain recoverable under admissible variation.
3. Mutual coordination	Changing $L(A)$ changes at least part of the surrounding localization relation structure.

Condition	Candidate requirement
4. Non-collapsible extension	$L(A) \neq L(B)$, and collapsing them destroys a declared spatial invariant.
5. Consequential locality	Geometric neighborhood constrains independently specified admissible coupling.
6. Cross-frame robustness	Declared spatial invariants remain approximately stable across admissible heterogeneous probes.

■ Sp = a physically consequential coordinated localization structure

This remains a candidate definition until explicit generative models establish that these properties can arise without spatial locality being inserted into the lower-order rules.




Figure 13.8. Space as a derivational bridge.

13.24 Counterfactual Distinctions

The chapter depends on keeping neighboring concepts apart. Each distinction below functions as a counterfactual control: if the right-hand concept has been assumed merely because the left-hand concept exists, the derivation has overreached.

Distinction A	Distinction B	Why the distinction matters
geometry	space	Geometric coherence alone does not establish physical localization consequence.
coordination	coordinates	Coordination constitutes mutual position; coordinates label or represent it.
joint resolvability	simultaneity	Joint configuration precedes metric Time.
edge	spatial neighbor	Primitive connectivity cannot carry hidden locality.
metric proximity	physical accessibility	Locality must be independently demonstrated.

Distinction A	Distinction B	Why the distinction matters
physical	material	Physical consequentiality can precede Matter.
extension	pre-existing container	Extension can emerge from non-collapsible coordinated localization.
geometric dimension	spatial dimension	Only modes that alter physical localization deserve the spatial interpretation.
effective smoothness	fundamental continuity	Smoothness may be resolution-relative.
detectable irregularity	fundamental resolution	A failed coarse-graining may expose only the next level.
responsive geometry	derived gravity	Dynamic spatial coordination merely preserves a later possibility.
wave-like relational transformation	quantum wavefunction	A wavefunction requires additional unearned quantum structure.

13.25 The Spatial Interpretation Is Conditional

Geometry becomes Space in this framework only when geometric localization does work that a merely mathematical geometry need not do. Localization relations must constrain admissible couplings, remain recoverable when coordinate labels are removed, and survive enough variation of probe and scale to count as organization rather than as one chosen representation.

This is an interpretive threshold, not a new primitive. The inherited geometry supplies loci, metric relations, neighborhoods, and effective dimensional organization. Space is the stronger reading licensed when those structures become mutually consequential for what can be instantiated and coupled within the domain.

■ geometric coherence + consequential coordinated localization ⇔ candidate spatial regime

The threshold remains provisional until generative models show that the coupling rule does not already contain the locality it is later said to recover. Section 13.26 therefore treats coordinate removal, locality prediction, heterogeneous probing, scale robustness, and responsive geometry as diagnostics rather than as premises.

13.26 Computational and Formal Tests

The project's methodological distinction between constitutive and diagnostic use is especially important here. Mature geometric tools may test the output of

a generative model, but spatial coordinates, locality, dimensionality, or smooth manifolds may not quietly enter its lower-order update rules.

Coordinate-removal test. Strip coordinate labels, embeddings, drawing positions, and target spatial metadata. Attempt to recover the same localization relations intrinsically. If Space disappears when the coordinates disappear, Space was encoded.

Locality-prediction test. Generate geometry without specifying spatial adjacency as a target. Test afterward whether recovered geometric neighborhood predicts independently specified coupling accessibility better than randomized controls.

Perturbation-coordination test. Change one recovered localization and measure whether the surrounding localization relations change systematically rather than arbitrarily.

Probe-heterogeneity test. Apply substantially different resolution maps and determine whether candidate spatial invariants survive.

Scale test. Coarse-grain repeatedly and measure whether localization, adjacency, and dimensional rank remain stable over a finite regime.

Smoothness-failure test. Search for scales or regions in which a smooth approximation ceases to fit while higher-order localization remains recoverable.

Responsive-geometry test. Permit lower-order relational transformations to perturb the substrate without explicitly changing geometric variables. Ask whether the recovered effective geometry changes as a consequence.

■ continuum failure $\neq$ localization failure

13.27 What Space Earns

If the candidate derivation succeeds, Space earns coordinated localization, physical spatial position, spatial separation, consequential locality, spatial adjacency, physical extension, spatial dimensionality, spatial regions and boundaries, intrinsic spatial organization, scale-relative smoothness, the possibility of responsive spatial coordination, and distinct neighboring local reference frames.

■ $W_A \neq W_B$ can now mean distinct spatially localized frames within one coordinated domain

13.28 What Space Does Not Earn

Space still does not establish metric duration, propagation interval, velocity, causal speed, temporal simultaneity, proper time, Lorentzian signature, spacetime, cosmological expansion as an actual physical law, gravity, gravitational field equations, matter, particles, quantum fields, wavefunctions, Hilbert space, superposition, Born statistics, energy, or action.

Nor does it establish that geometry is fundamentally continuous or fundamentally discrete. The chapter permits either possibility to remain testable.

13.29 Ontological Defensibility Pulse: Space

This is the chapter's Pulse sidebar. It applies to the central proposition, and it is set apart from the argument so that a reader can skip it on a first pass.

Pulse question	Applied to Space
1. Entities required	Effective geometric loci, relational identities, metric neighborhoods, localization profiles and admissible relational couplings. No spatial substance and no external container
2. Ontological level	Higher-order effective organization of already-earned geometry. Spatiality belongs to coordinated localization rather than to primitive relations
3. Lower-order dependencies	Distinction, retained identity, Relation, Closure, Orientation, Return, Formalism, Scale, Distance and Geometry
4. New emergent properties	Mutual localization constraint, consequential adjacency, locality, extension, spatial dimensionality, and possibly responsive geometric organization
5. Claim types	Relational and functional at the core; formal where localization and coordination can be specified; speculative on responsive geometry and on unresolved fine structure
6. New primitives	Ideally none. The principal danger is an admissible-coupling rule that already contains spatial locality
7. Fewer assumptions?	Strongest where locality and extension follow from inherited relational dynamics; weakened wherever adjacency, dimension, continuity or coordinates must be inserted separately

Pulse question	Applied to Space
8. Observational constraints	The seven tests of 13.26: coordinate removal, locality prediction against randomized baselines, perturbation, probe heterogeneity, scale robustness, smoothness failure and responsive geometry

The principal vulnerability is best stated on its own, since everything in the chapter depends on the answer.

Does spatial coordination emerge from the relational organization, or has spatial locality been reintroduced through the coupling rule?

If that question cannot be answered, the chapter has not earned Space.

13.30 Questions Opened by This Framework

What is the weakest formal condition under which geometric localization becomes mutually coordinated rather than merely consistent?

Can spatial localization be recovered uniquely from intrinsic relations, or can multiple inequivalent spatial interpretations correspond to the same geometry?

What independent criterion should determine admissible coupling before spatial locality is tested?

Can a model produce locality without primitive graph adjacency functioning as disguised spatial neighborhood?

Under what conditions does a geometric mode become physically spatial rather than remaining an unobserved relational degree of freedom?

Can spatial dimensionality differ from total geometric dimensionality?

Can several lower-order relational structures project to the same effective spatial localization?

Over what scale range must localization remain invariant before it deserves to be called spatially objective?

Can local neighborhoods remain effectively smooth while adjacent regions exhibit detectable failures of the same approximation?

Does a breakdown of smooth geometry reveal fundamental structure or only an intermediate relational regime?

Can lower-order relational dynamics be locally discrete while producing an effectively continuous spatial metric?

What observables could distinguish genuinely continuous geometry from unresolved discrete relational organization?

Can changing relational organization alter effective geometry without geometric response being explicitly inserted into the update rule?

What mathematical conditions would make such response nonlinear?

Can intersecting distributed transformations produce stable defects, irregularities, or scale-transfer behavior?

Can global relational scale change while stable local neighborhoods remain approximately invariant?

Under what conditions can a relational boundary acquire spatial realization without collapsing Closure into enclosure?

Can intrinsic spatial organization remain complete without any external embedding?

How much frame dependence is compatible with objective spatial localization?

Which invariants must survive heterogeneous probing for two frames to count as resolving the same space?

Can the same lower-order relational organization support both stable geometry and distinct propagating collective modes without either description exhausting the substrate?

What additional structure is required before propagation through spatially distinct frames can acquire comparative interval?

13.31 Implications and Handoff to Time

Space has now produced something that earlier chapters could not legitimately assume: distinct, neighboring, spatially coordinated local frames.

■ W_A, W_B

A relational transformation begins to alter the state recoverable at W_A . Eventually, that transformation becomes consequential at W_B :

■ $W_A \mapsto W_B$

Space tells us that the frames are distinct. It tells us that their separation is spatially meaningful. It tells us that their localizations belong to one coordinated domain. It may even permit their geometric organization to respond dynamically while the transformation propagates.

But Space cannot yet tell us how much propagation separates these two relational events.

■ coordinated spatial frames $\rightsquigarrow$ propagation between frames $\rightsquigarrow$ comparative propagation interval $\rightsquigarrow$ Time

Handoff to Time. Space makes relational loci mutually situated. Time must determine how relational change acquires measurable separation as it propagates among them.

Selected References Cited in Space

The neighboring work shows that emergent locality, discrete underlying organization and scale-dependent geometry are technically meaningful possibilities; none of it supplies the derivation proposed in this chapter.

Bombelli, L., Lee, J., Meyer, D., & Sorkin, R. D. (1987). Space-time as a causal set. *Physical Review Letters*, 59, 521-524. <https://doi.org/10.1103/PhysRevLett.59.521>

Cao, C., Carroll, S. M., & Michalakis, S. (2017). Space from Hilbert space: Recovering geometry from bulk entanglement. *Physical Review D*, 95(2), 024031. <https://doi.org/10.1103/PhysRevD.95.024031>. Preprint arXiv:1606.08444.

Konopka, T., Markopoulou, F., & Severini, S. (2008). Quantum graphity: A model of emergent locality. *Physical Review D*, 77(10), 104029. <https://doi.org/10.1103/PhysRevD.77.104029>. The earlier preprint by Konopka, Markopoulou and Smolin (arXiv:hep-th/0611197, 2006) introduces the model.

Rovelli, C., & Smolin, L. (1995a). Discreteness of area and volume in quantum gravity. *Nuclear Physics B*, 442, 593-622. Erratum: *Nuclear Physics B*, 456 (1995), 753. [https://doi.org/10.1016/0550-3213\(95\)00150-Q](https://doi.org/10.1016/0550-3213(95)00150-Q). Preprint arXiv:gr-qc/9411005.

Rovelli, C., & Smolin, L. (1995b). Spin networks and quantum gravity. *Physical Review D*, 52(10), 5743-5759. <https://doi.org/10.1103/PhysRevD.52.5743>

Van Raamsdonk, M. (2010). Building up spacetime with quantum entanglement. *General Relativity and Gravitation*, 42, 2323-2329. <https://doi.org/10.1007/s10714-010-1034-0>

Chapter 14

Time: When Retained Transformation Acquires Order

Claim ~ Time emerges where retained-dependency precedence, inherited from Boundary, supports an intrinsic order: where dependency cycles can be separated from ordered precedence, where that order is recoverable from retained structure itself, and where recurrent processes furnish endogenous standards of comparison. Time is thus earned from within; metric duration remains conditional.

Epistemic status. Dependency precedence itself is inherited from Boundary rather than newly derived here. This chapter is strongest where it specifies the extra conditions under which that weak relation yields a strict partial-order candidate after mutually dependent cycles are collapsed into equivalence classes. It becomes conditional where it proposes endogenous temporal standards from recurrent update structure.

14.1 The Last Background Variable

Space ended with a coordinated domain of localization, adjacency, extension, and neighboring local reference frames. It did not tell those frames how long anything takes. That omission is deliberate. If duration had already been hidden inside retention, recursion, propagation, update, or the ordering of the earlier chapters, Time would not be an emergence at all. It would be a background parameter disguised as bookkeeping.

Time is therefore the final major background structure Book I must confront. The problem is not to redescribe familiar clock time in relational vocabulary. The problem is to identify the weakest inherited structure from which a physically interpretable temporal order could become possible without assuming seconds, trajectories through a temporal dimension, or a universal before-and-after relation at the outset.

The chapter begins from a fact already established by Boundary and carried forward by later chapters: retained distinctions can constrain admissible successor structure, yielding retained-dependency precedence $<$. That fact is weaker than physical time. In particular, Boundary does not guarantee that $<$ is transitive, acyclic, total, or asymmetric. Time must therefore earn any stronger ordering property it uses.

14.2 What Time Must Not Presuppose

Several ordinary words become dangerous here because each can import the target structure before it has been earned. “Earlier,” “later,” “during,” “rate,” “delay,” and “propagation” are useful once temporal structure exists, but they cannot serve as primitives in the derivation. The chapter therefore separates five orders that are often collapsed in ordinary language:

logical order: one statement or condition is required to formulate another;

derivational order: one element of the framework is constructed before another in the argument;

dependency order: one relational state contains retained consequences of another;

temporal order: dependency structure is stably interpretable as succession among transformations;

metric time: temporal separation admits a reproducible quantitative standard.

Only the first three are available at the start of this chapter, and even dependency order is available only in Boundary’s deliberately weak sense. The task is to determine when additional structural conditions warrant a temporal ordering and what further conditions would be required for metric time.

■ logical order $\rightsquigarrow$ derivational order $\rightsquigarrow$ retained dependency $<$ $\rightsquigarrow$ derived temporal order $\rightsquigarrow$ metric time

The arrows in this hierarchy indicate candidate dependence, not elapsed duration. Even the diagram must not be read as a clock.

14.3 Inheritance from Retained Distinction

Boundary established that a distinction can remain available after transformation and that retaining or removing it can change the admissible possibility set $\mathcal{P}$. It then defined retained-dependency precedence $<$ between configurations without assuming that relation to be transitive, acyclic, total, causal, or temporal. Time inherits exactly that weaker structure.

■ $\mathcal{P}(\Sigma, r) \neq \mathcal{P}(\Sigma, \emptyset)$

The formal point is modest. A relational configuration can carry inherited structure whose removal changes what remains admissible. Repeated occurrences of such dependence generate a directed dependency graph, but a

directed graph is not automatically a temporal order: it may contain branches, merges, incomparable events, or cycles.

This is the bridge Time needs. No clock has appeared. No temporal coordinate has appeared. What has appeared is counterfactually consequential retained dependence. The remaining burden is to determine when the dependency organization itself supports a stable order rather than merely a network of mutual constraints.

14.4 Dependency Precedence

We write the dependency relation as:

$$\blacksquare \Sigma_a < \Sigma_\beta$$

where $<$ means generative or retained-dependency precedence. The intended reading is not yet “ Σ_a occurred at an earlier physical time than Σ_β .” It means that Σ_β contains consequences whose form depends on structure retained from Σ_a , such that removing the relevant retained contribution changes Σ_β or the admissible path to it.

A useful counterfactual criterion is therefore:

$\Sigma_a < \Sigma_\beta$ only if removing the retained contribution inherited from Σ_a changes Σ_β or changes the admissibility of a dependency chain leading to it.

This prevents mere notation from generating order. Writing states in a list does not make them temporally ordered. The order must be recoverable from dependency structure itself.

Boundary does not grant asymmetry as a global property of $<$. A particular dependency may be one-way, but reciprocal or cyclic retained dependence is not excluded at this stage. Therefore:

$$\blacksquare \Sigma_a < \Sigma_\beta \text{ does not by itself settle whether } \Sigma_\beta < \Sigma_a$$

Where one-way retained dependence is recovered, it supplies a candidate ingredient of temporal direction. Where mutual reachability occurs, Time must not force a before-and-after relation onto the cycle. The distinction between one-way precedence and mutually dependent closure becomes the burden of the next section.

14.5 Earning a Partial Order from Weak Dependency

Ordinary narratives tempt us to imagine a single line of states: Σ_0 , Σ_1 , Σ_2 , and so on. Boundary does not license that picture, and raw $<$ is not yet a partial

order. The first task is therefore to separate directed dependency from mutually dependent cycles without imposing acyclicity by fiat.

Let $\mathcal{E}$ be a set of resolvable relational events or update states and let $<$ be Boundary's retained-dependency relation. Write $<^+$ for non-empty reachability through one or more $<$ links. Define mutual dependency by:

$$\blacksquare e_i \approx e_j \text{ iff } e_i <^+ e_j \text{ and } e_j <^+ e_i$$

The equivalence classes $[e]_{\approx}$ collect events that belong to the same mutually dependent cycle. On the quotient $\mathcal{E}/\approx$, define a strict candidate temporal precedence relation $<_t$ by:

$$\blacksquare [e_i] <_t [e_j] \text{ iff } e_i <^+ e_j \text{ and not}(e_j <^+ e_i)$$

This quotient construction does not assume that the original dependency graph is acyclic. It collapses each strongly mutually dependent component to one unresolved dependency unit; the remaining condensation relation is acyclic by construction.


The transitive reachability relation then supplies strict partial-order structure on the quotient: irreflexivity and asymmetry follow from excluding mutual reachability, transitivity follows from concatenating dependency chains, and incomparability remains possible between quotient events for which neither reachability relation holds.

A temporal interpretation is still not automatic. $<_t$ is a structural order candidate. Time must additionally show that it is intrinsic, frame-coherent, and robust enough to organize admissible histories rather than merely classify a graph.


Incomparability is especially important. A universal total order would already resemble a hidden global clock. A strict partial order permits multiple locally ordered transformations without assuming that every pair has a meaningful global before-and-after relation.

Order is earned in two steps: collapse mutual dependency, then order what remains

1 collapse the cycle



2 order the classes



Neither edit depends on the other, and nothing in the organization says which came first.

A single line through every event would be a global clock in disguise.

Figure 14.1. Order is earned in two steps. First, events that depend on each other in a cycle are collapsed into one: two co-authors trading revisions of a paragraph produce a single edit. Then the resulting classes are ordered by dependency. Both edits build on the draft and the merge builds on both, yet neither edit depends on the other, so nothing orders them.

14.6 Latent Integration Without Duration

Retention also permits unresolved internal reorganization between configurations that later become resolvable. Such an interval may be represented without treating $\mathcal{U}$ as a function or importing duration.

■ $\Sigma_n \mapsto L_n \mapsto \Sigma_{n+1}$, with $(\Sigma_n, \Sigma_{n+1}) \in \mathcal{U}$

L_n is a latent integration interval in the dependency structure. The word “interval” is functional, not metric. It denotes unresolved reorganization associated with an admissible transition; it does not denote any amount of duration.

$\mathcal{U}$ remains the admissible transition relation inherited from Distinction. Functional notation is legitimate only in a restricted regime where that relation has independently been shown to select a unique successor.

Accordingly, $\mathcal{U}$ is not a temporal evolution operator in the established physical sense. It contains no physical time parameter merely by relating admissible successor configurations. If a model realizes $\mathcal{U}$ by a rule containing an external time variable, that realization cannot count as a derivation of time.

The methodological rule is therefore strict: latent integration may carry dependency structure before it carries duration.

14.7 From Dependency to Succession

The quotient precedence $<_t$ becomes a candidate temporal order when three conditions are jointly satisfied. First, it must be reconstructible from retained dependency after external indices are removed. Second, it must remain stable enough under admissible transformations and coarse-graining to support consistent comparisons. Third, distinct resolving frames must recover compatible local orderings wherever they share access to the same dependency structure.

A working definition follows.

Working definition of temporal order. A temporal order is a stable, recursively recoverable strict ordering of relational transformations derived from retained dependency, such that the ordering constrains admissible histories without requiring an external time parameter. Raw $<$ is the inherited dependency relation; $<_t$ denotes the stronger order earned only after cycle reduction and the additional coherence conditions stated here.


This definition is deliberately weaker than metric time. It tells us what can count as succession. It does not yet tell us how much time separates successive states.

14.8 Derivation Order Is Not Physical Time

The framework itself was developed in an order: Distinction before Relation, Relation before Closure, and so on. That order cannot by itself ground physical time. A proof has premises before conclusions, but the paper containing the proof does not thereby generate a physical temporal field. The same caution applies to recursive construction.

A derivation can be represented by an acyclic graph of dependencies. To become physically interpretable as temporal order, the dependency must belong to the relational system being modeled, not merely to the theorist's description of it.

This gives a simple diagnostic. If the ordering disappears when equation labels, program loop counters, or manuscript sequence are removed, then the model has not derived time. If the ordering can be reconstructed from the retained consequences encoded in the modeled states themselves, then it has at least earned an endogenous succession relation.



The order survives because it is recoverable from what the states contain, not from labels attached to them.

Figure 14.2. The index-removal test, read as undated photographs. Four pictures of the same candle, shuffled, with every timestamp stripped away. The order can still be recovered, because each state carries a consequence of the ones before it: the candle is shorter. The insight is the chapter's sharpest criterion. If the ordering vanishes when iteration counters, equation labels and manuscript sequence are removed, the model has not derived temporal order; if it survives, the order belongs to the organization rather than to the notation describing it.

14.9 Chains, Branches, and Histories

A temporal chain is a set of mutually comparable quotient events under $<_t$. Along such a chain, the derived order supplies an unambiguous succession:

■ $[e_0] <_t [e_1] <_t [e_2] <_t \dots <_t [e_n]$

A branch occurs when one event constrains more than one admissible successor. A merge occurs when one event depends on retained consequences from more than one predecessor. These structures matter because physical histories need not be simple strings.

■ branch: $[e_a] <_t [e_\beta]$ and $[e_a] <_t [e_\gamma]$, with $[e_\beta]$ and $[e_\gamma]$ incomparable

■ merge: $[e_a] <_t [e_\gamma]$ and $[e_\beta] <_t [e_\gamma]$, with $[e_a]$ and $[e_\beta]$ possibly incomparable

The candidate temporal structure therefore resembles a directed dependency network more naturally than a universal timeline. A familiar one-dimensional time coordinate, if it later becomes useful, would be a higher-order representation of suitable portions of this order rather than the primitive source of the order.

14.10 Concurrency and the Refusal of Premature Simultaneity

If two quotient events are incomparable under $<_t$, the framework should not immediately call them simultaneous. Incomparability means only that the derived temporal candidate does not order them within the relevant frame or domain.

■ $\text{not}([e_a] <_t [e_\beta])$ and $\text{not}([e_\beta] <_t [e_a]) \Rightarrow$ temporally unordered at this stage

Simultaneity is a stronger physical relation. In relativity it is frame-dependent and tied to the structure of spacetime. Dependency-incomparable events may later map to spacelike-separated events, to unresolved ordering, to independent local updates, or to something else entirely. Treating incomparability as simultaneity would prematurely import relativistic interpretation.

14.11 Counting Change Is Not Yet Measuring Time

Once ordered chains exist, one can count transitions. If a chain C contains N distinguishable retained updates between e_a and e_β , then N is a legitimate structural quantity:

■ $N_C(e_a, e_\beta) =$ number of retained update steps along chain C

But N is not automatically duration. Two chains may contain different numbers of lower-order updates while representing the same higher-order transformation. A coarse-graining map may compress several updates into one. Different local mechanisms may reorganize relational states at different granularities. Without a standard that survives such variation, step count is resolution-dependent.

The chapter therefore distinguishes update count from temporal measure. Counting provides a candidate precursor of duration only when the counted unit is itself stable, reproducible, and relationally accessible.

14.12 Recurrent Structure and Endogenous Standards

Metric time requires a repeatable standard. In ordinary physics, clocks supply such standards by exploiting approximately recurrent processes. A relational derivation should recover the logic of a clock without assuming a temporal parameter in the clock's definition.

Suppose a subsystem K returns through a sequence of distinguishable relational configurations:

$$\blacksquare K_0 \mapsto K_1 \mapsto \dots \mapsto K_m \approx K_0$$

where $\approx$ means sufficiently equivalent at the resolution relevant to the clock function. If repeated cycles preserve their internal dependency structure under a range of external conditions, then another process can be compared against the number of recovered cycles.

$$\blacksquare \tau_K(A,B) = n_K(A,B) \cdot u_K$$

Here n_K is the number of stable K-cycles occurring across the dependency interval between A and B, and u_K is the conventional unit assigned to one cycle. The formula is not yet a claim that τ_K equals proper time. It shows how a metric-like temporal quantity could arise from relational recurrence rather than from an independently flowing temporal substance.

14.13 Clockhood as a Relational Role

A subsystem is not a clock because time flows through it. It functions as a clock when its recurrent transformations provide a sufficiently stable comparison standard for other transformations. Clockhood is therefore a role that a relational subsystem can acquire.

A candidate clock K should satisfy at least four conditions:

recurrence: the system repeatedly returns to a comparison-equivalent state;

countability: cycles or phases can be distinguished and retained;

stability: the relevant cycle structure remains sufficiently invariant across the domain of use;

couplability: other processes can be compared with the clock without the comparison relation itself silently defining the desired temporal result.

The last condition is easy to violate. If the model defines every process by reference to the clock variable from the outset, then agreement with the clock has been built in. A genuine relational time standard must be cross-checkable against independently organized recurrent processes.

14.14 From Local Temporal Standards to Shared Metric Time

One recurrent subsystem gives a local standard. Physical time becomes more compelling when multiple independently realized clocks can be calibrated so that their comparative ratios remain stable under transformations relevant to the domain.

■ $\tau_K(A,B) / \tau_J(A,B) \approx \text{constant over an admissible regime}$

This cross-clock invariance is stronger than recurrence. It suggests that a common temporal measure may be recoverable even though no primitive universal clock exists. The measure is then an invariant relation among recurrent processes, not a substance carried by one preferred oscillator.

However, the word “common” must be handled carefully. A shared temporal calibration within a local or weakly varying domain does not establish a global cosmic time. Nor does it establish relativistic proper time. The chapter earns at most a route by which metric temporal standards could become endogenous to organized relational dynamics.




Figure 14.3. Cross-clock calibration, read as a pendulum and a dripping tap. Neither is the standard. What earns a temporal measure is that two independently realized recurrences hold a stable ratio across a regime, so that $\tau_K(A,B) / \tau_J(A,B)$ stays put whichever pair of events is compared. The insight is that a shared measure can be recovered without any primitive universal clock. The condition is easy to lose and the chapter states it at 14.13: the test is worthless if either clock was defined by reference to the other, since agreement would then have been built in rather than found.

14.15 Local Rate Without a Universal Flow

If clocks are relational subsystems, their apparent rates may vary with local organization. Nothing in the derivation requires a single metaphysical flow that every subsystem samples identically. What must remain stable is the rule by which rates are compared once the relevant coupling conditions are specified.

This distinction will matter later. A physical theory may permit local clock rates to differ while preserving cross-frame laws that relate those differences. Curvature, acceleration, environmental coupling, or deeper relational structure

could affect realized clock behavior without making the governing relation arbitrary.

Book I does not derive the relativistic law governing such variation. It only avoids foreclosing the possibility by refusing to identify time with a single universal succession parameter.

14.16 Propagation Is Not Yet Earned

It is tempting to interpret an ordered transition from a state localized at one spatial region to a later state localized elsewhere as propagation. That interpretation is premature. Propagation requires a relation between spatial separation and temporal order. Space earned spatial localization; this chapter is constructing temporal order. Their coupling has not yet been derived.

Accordingly, the present chapter can describe changes whose retained consequences appear in distinct local relational states, but it must not assign a propagation speed:

■ $\text{speed} = \text{spatial separation} / \text{temporal duration}$

because the numerator and denominator have not yet been shown to participate in one invariant physical structure. The equation is familiar physics, not a premise available to the derivation.

This boundary becomes the central handoff at the end of Book I.

14.17 Temporal Direction and Reversibility

Asymmetric dependency does not imply that every microscopic transformation is dynamically irreversible. A reversible law can relate two states symmetrically while the realized history contains records or retained consequences that distinguish one dependency orientation from the other.

The chapter therefore separates three questions:

Is the dependency relation asymmetric?

Are the transformation rules dynamically reversible?

Does a higher-order statistical arrow arise from the distribution of retained records and accessible states?

Only the first is directly addressed here. The second belongs to the eventual physical dynamics. The third invokes entropy, coarse-graining, boundary conditions, and statistical mechanics, none of which Book I has yet earned.

14.18 Records, Memory, and the Structural Arrow

Retained distinction nevertheless supplies a minimal record asymmetry. If state B contains a recoverable consequence of A while A does not contain a corresponding consequence of B, then B can encode information about the dependency relation in a way A cannot encode about B under that realized chain.

■ $\text{Record}_B(A) \neq \emptyset$ while $\text{Record}_A(B) = \emptyset$ for the realized dependency chain

This can support a structural distinction resembling past-directed record access: some states contain retained traces of dependencies from which they arose. But the interpretation must remain modest. A record structure is not by itself the thermodynamic arrow of time, psychological memory, or cosmological temporal asymmetry. Those require additional mechanisms.

The important result is narrower: retention can make the dependency orientation internally recoverable. Temporal direction need not be painted onto the system from outside.

14.19 Causal Order Is Stronger Than Temporal Order

Boundary introduces $<$ as a dependency ordering and leaves open whether it supports causal or temporal order (4.11). “Precursor of causal order” is therefore the correct level of claim. Dependency is necessary for many forms of causation, but causation adds constraints not yet present here: locality or admissible influence structure, intervention-sensitive counterfactual relations, and—within relativistic physics—a causal geometry that separates possible influence from impossible influence.

The chapter therefore states the hierarchy with the open bridge made explicit:

■ retained dependency $\rightsquigarrow$ temporal ordering $\rightsquigarrow$ spatiotemporal constraint $\rightsquigarrow$? $\rightsquigarrow$ physical causal structure

The question mark is methodological, not decorative. It marks the point at which Book II must determine whether a causal geometry emerges from the structures Book I has earned.

14.20 Comparison Class: Causal Sets

Causal-set theory provides an important mathematical comparison because it treats a locally finite partial order as fundamental and seeks to recover continuum spacetime from order plus discreteness. The present framework should not be identified with causal-set theory: its dependency relation is

derived from retained relational consequence rather than postulated as a causal order, and local finiteness has not been assumed as a primitive.

If the Time construction is viable, one should ask whether the quotient order ($\mathcal{E}/\approx < , <_t$) can satisfy or approximate the structural conditions from which causal-set approaches recover Lorentzian manifold behavior. Failure here would be informative: it could mean that retained dependency is too weak, that additional constraints are required, or that the physical extension of the framework is wrong.

The crucial discipline is that causal-set results may serve as diagnostics or comparison targets. They cannot be imported as proof that $<$ is already a relativistic causal relation.

14.21 Comparison Class: Logical Time

Distributed computing offers a second comparison class. Logical clocks order events by dependency among messages and processes even when no single global clock is available. This demonstrates, in a non-foundational setting, that useful order can be reconstructed from dependency relations without presupposing one universal time coordinate.

Again, analogy is not derivation. Computer processes already exist in physical time, and their communication delays are physical. The relevance is formal: dependency can carry order information that a total clock variable need not supply. The framework borrows no physical conclusion from the analogy.

The comparison sharpens a criterion for Time: if the relational substrate supports only arbitrary labels but no dependency-recoverable order, it has not earned even logical-time-like structure. If it does support such order, the next question is whether physical temporal metrics can arise from that order endogenously.

14.22 Temporal Coarse-Graining

A viable emergent time should survive changes of resolution over some regime. Suppose a fine-grained chain contains many retained updates while a coarse-graining map C groups them into stable higher-order transitions:

■ $C: \{[e_0] <_t [e_1] <_t \dots <_t [e_n]\} \mapsto \{[E_0] <_t [E_1] <_t \dots <_t [E_m]\}, \text{ with } m < n$

The exact update count changes, but the higher-order precedence relation should remain recoverable if temporal order is objective at that scale. This

suggests a temporal analogue of the scale-robustness tests used for Geometry and Space.

Metric duration may renormalize under coarse-graining, while precedence remains invariant. That separation is useful because it identifies which part of Time is structurally fundamental in the candidate account and which part may be an effective quantitative representation.

14.23 The Candidate Formal Object

Collecting the pieces, the weakest candidate temporal object developed here is:

$$\blacksquare \mathcal{T} = (\mathcal{E}/\approx<, <_t, \text{Rec}, \text{Cyc})$$

where:

$\mathcal{E}/\approx<$ is the quotient of resolvable relational events by mutual dependency reachability;

$<_t$ is the strict partial-order candidate induced by one-way dependency reachability between those quotient classes;

Rec is the family of retained records or constraints by which precedence can be recovered, lettered to stay clear of the relation set $\Re$ of Formalism;

Cyc is an optional family of recurrent comparison processes, lettered to stay clear of the configuration set $\mathcal{C}$ of Formalism, that can support endogenous metric standards when they satisfy stability conditions.

The tuple is intentionally not a spacetime manifold. It is already stronger than Boundary's raw dependency relation because mutual cycles have been quotiented and a strict order has been earned on the remainder, but it still contains no spatial coordinates, Lorentzian metric, lapse function, light cone, or invariant constant c . Those structures would have to arise when $\mathcal{T}$ is coupled to the spatial organization earned in Space and then subjected to physical consistency tests.

14.24 Minimal Conditions for Metric Time

The chapter can now state a conditional route from temporal order to metric time without claiming the route is complete. A metric temporal quantity becomes defensible only if at least the following conditions can be satisfied:

ordered comparability: the relevant states admit stable precedence relations;

repeatable standard: a recurrent process provides distinguishable, countable cycles or phases;

cross-standard calibration: independently realized recurrent processes exhibit stable comparative ratios over a regime;

resolution robustness: the inferred temporal measure is not an artifact of one arbitrary decomposition into update steps;

frame coherence: overlapping local frames agree on precedence where dependency is shared, even if their quantitative clock readings later differ;

non-circularity: no external time variable or target relativistic behavior is built into the update rules that supposedly derive the measure.

These conditions do not prove that metric time must emerge. They define what the computational and mathematical program must demonstrate before the stronger claim is licensed.

14.25 Candidate Diagnostics and Failure Tests

A chapter on emergent time should be falsifiable at the level of its proposed mechanism. The following tests are therefore more important than rhetorical resemblance to familiar temporal concepts.

Index-removal test. Remove all external iteration counters, timestamps, and manuscript-order labels. Determine whether the precedence relation can still be reconstructed from retained relational structure.

Counterfactual-dependency test. Delete or perturb a purported predecessor and test whether the admissibility or structure of the claimed successor changes in the predicted way.

Cycle-calibration test. Construct at least two independently organized recurrent subsystems and test whether their comparative cycle ratios stabilize without one clock being defined from the other.

Coarse-graining test. Change temporal resolution and determine whether precedence and any proposed metric ratios remain stable over a finite regime.

Branching test. Introduce incomparable or branching update structures and verify that the formalism does not force an artificial global total order.

Frame-overlap test. Give neighboring local frames partial access to the same dependency network and test whether they recover compatible orderings on the shared portion.

Reverse-rule test. Use transformation laws that are microscopically reversible and determine whether the framework incorrectly manufactures thermodynamic irreversibility from dependency notation alone.

Spacetime-withholding test. Verify that no propagation speed, Lorentzian signature, null relation, or invariant c is required to make the temporal construction work.

A candidate model that fails the index-removal or counterfactual-dependency tests has not derived temporal order. A model that passes those but fails cross-clock calibration may have earned succession without metric time. That would be a meaningful partial result rather than a disguised success.

14.26 Objections and Replies

Objection 1: The symbol $<$ already means “before,” so time has been smuggled in through notation.

Reply: The symbol $<$ is defined operationally as retained-dependency precedence, not physical temporal precedence. The stronger $<_{\text{r}}$ relation appears only after the dependency graph is reduced by mutual reachability and passes the chapter’s coherence conditions. Replacing either symbol with arbitrary relation labels would leave the formal content unchanged.

— — — —

Objection 2: Any update rule presupposes time because updating is a temporal verb.

Reply: The ordinary-language verb is indeed dangerous. Formally, $\mathcal{U}$ remains the admissible transition relation introduced in Distinction. A particular functional update map may represent it only where unique succession has separately been earned. Neither representation may contain a physical time parameter if the model is to count as deriving temporal structure.

— — — —

Objection 3: A partial order is mathematical structure, not physical time.

Reply: Correct. A partial order alone is insufficient, and Boundary does not even supply one. The proposal is that retained dependency first yields a directed relation; mutual cycles are quotiented; one-way reachability yields a strict partial-order candidate; and only an intrinsic, recursively recoverable, frame-coherent version of that order deserves temporal interpretation. Stable recurrent measures are an additional requirement for metric time.

— — — —

Objection 4: Recurrence already requires time, because a cycle means returning later.

Reply: At the formal level, recurrence can be defined as repeated return to comparison-equivalent relational configurations along an already earned dependency chain. What is counted is ordered transformation, not elapsed seconds. The clock interpretation appears only after repeatability and calibration are established.

— — — —

Objection 5: The framework cannot explain the arrow of time.

Reply: This chapter does not claim to derive the thermodynamic arrow. It derives, at most, a structural dependency orientation and a record asymmetry. Entropic, cosmological, and psychological arrows remain separate problems.

— — — —

Objection 6: If incomparable events exist, the framework has abandoned objective time.

Reply: Objective temporal structure need not be a universal total order. Modern relativistic physics already denies a frame-independent global simultaneity relation in general. The present framework goes no further than its evidence permits: shared dependency can ground shared order, while incomparable events remain unordered until additional physical structure justifies a stronger relation.

— — — —

Objection 7: The proposal simply redescribes causal-set theory.

Reply: Causal-set theory ordinarily begins with a causal partial order as fundamental. This framework begins earlier, with retained relational consequence, and asks whether a causal order can later be earned. Causal sets are therefore a comparison class and diagnostic target, not an imported ontology.

14.27 What Time Earns

If the candidate derivation succeeds, Time earns the following structures:

inherited retained-dependency precedence $<$ as the pre-temporal substrate for ordering;

a derived strict partial-order candidate $<_t$ on dependency-cycle equivalence classes, without a universal external clock;

ordered chains, branches, merges, and dependency-incomparable events;

a distinction between succession and mere manuscript or algorithmic indexing;

a structural record asymmetry by which some dependency orientations can be internally recovered;

a candidate route from recurrent relational processes to endogenous temporal standards;

a candidate route from cross-clock calibration to metric temporal comparison;

local temporal organization compatible with, but not yet equivalent to, later relativistic time.

The strongest earned claim is therefore not that “time flows.” It is that retained dependency can, under explicit additional conditions, be reduced to an internally recoverable strict order of succession without assuming a universal clock, and that sufficiently stable recurrent structures can in principle furnish quantitative standards for comparing that succession.

14.28 What Time Does Not Earn

Time still does not establish relativistic structure (a Lorentzian metric, invariant light speed, light cones and intervals, proper time, relative simultaneity, time dilation, gravitational redshift); any global time (cosmological time, a preferred foliation, a universal present); a thermodynamic arrow (entropy increase, microscopic irreversibility); or physical content (gravity, field equations, matter, quantum fields, energy, action, or the observed value of any physical constant).

It also does not establish that space and time are ontologically identical aspects of one metric structure. Book I has now earned a candidate spatial organization and a candidate temporal organization. Whether and how they become one physically constrained spacetime is a separate question.

This boundary is not a weakness to be concealed. It is the exact seam at which the constructive ontology becomes a physical research program.

14.29 Ontological Defensibility Pulse: Time

This is the chapter’s Pulse sidebar. It applies to the central proposition and is set apart from the main argument so that a reader can skip it on a first pass.

Pulse question	Applied to Time
1. Entities required	Resolvable relational update states; retained constraints or records; a dependency-precedence relation; optional recurrent comparison subsystems for metric candidates. No temporal substance and no external universal clock.
2. Ontological level	Higher-order organization of retained transformation. Temporal order belongs to stable dependency among changes rather than to primitive relation itself.

Pulse question	Applied to Time
3. Lower-order dependencies	Distinction, Boundary, Relation, Closure, Orientation, Return, Formalism, Scale, Distance, Geometry and Space—especially retained consequence, admissible possibility structure $\mathcal{P}$, and Boundary's deliberately weak dependency relation $<$.
4. New emergent properties	Mutual-dependency cycle classes, a strict partial-order candidate $<_t$ on their quotient, dependency-incomparability, recoverable record orientation, and possibly endogenous temporal standards through recurrent comparison.
5. Claim types	Formal and relational at the dependency-order level; functional and conditional at the clock/metric level; interpretive where the structure is called temporal; speculative wherever later physical spacetime behavior is anticipated.
6. New primitives	Ideally none. $<$ is inherited from Boundary; $<_t$ is derived from reachability after mutual cycles are quotiented. The principal danger is an update realization, iteration variable, acyclicity condition, or recurrence criterion that already contains external time.
7. Fewer assumptions?	Strengthened by not assuming raw $<$ is transitive or acyclic. Strongest if temporal order survives index removal, cycle quotienting, coarse-graining, and heterogeneous-frame recovery, and metric standards arise from independently recurrent subsystems.
8. Observational constraints	The eight diagnostics of 14.25, followed in Book II by the stronger requirement that the resulting structure support empirically adequate relativistic spacetime without importing Lorentzian structure as a premise.

The principal vulnerability is best stated on its own:

Does temporal order emerge from retained dependency inside the relational organization, or has physical time been reintroduced through the update rule used to generate the states?

If that question cannot be answered, the chapter has not earned Time.

14.30 Questions Opened by This Framework

What is the weakest formal criterion under which retained dependency deserves interpretation as temporal succession rather than merely logical precedence?

Can dependency precedence be derived uniquely from retained constraints, or can the same relational state support inequivalent temporal interpretations?

When should the raw dependency relation $<$ itself be treated as transitive, and when is only its reachability closure $<^+$ justified?

When mutual dependency cycles are quotiented, does the resulting $<_t$ order remain robust under coarse-graining, or can changes of resolution create or eliminate cycle classes?

What distinguishes genuine dependency-incomparability from merely unresolved order at a limited frame?

Can recurrent relational subsystems provide clock standards without recurrence criteria importing duration?

What independent conditions make two candidate clocks sufficiently independent for cross-calibration to count as evidence rather than circularity?

Can stable metric ratios emerge when lower-order update counts vary strongly across scales?

How should temporal coarse-graining be defined when branches and merges prevent a unique chain length?

Can local clock variability coexist with globally coherent transformation laws without a preferred universal rate?

Can record asymmetry arise in a microscopically reversible relational dynamics, and if so, what additional conditions are needed for a thermodynamic arrow?

Does retained dependency naturally generate structures comparable to causal sets, or is an additional locality or finiteness constraint required?

Can a computational model recover a robust temporal order after all external timestamps and iteration counters are removed?

Can such a model generate reproducible clock-like recurrence without target periodicity being encoded in its rules?

When Space and Time are coupled, what structural reason—if any—causes spatial and temporal contributions to enter a common invariant with different sign?

Can a null boundary or invariant maximal rate emerge from the coupled relational dynamics rather than being imposed from known relativity?

What would count as a decisive failure to convert the temporal structure earned here into empirically adequate physical spacetime?

14.31 Book I Frontier: The Problem of Spacetime

Book I began by refusing to assume the structures it hoped to explain. Relation was not allowed to mean spatial adjacency. Recursion was not allowed to mean elapsed time. Orientation was not allowed to become a hidden axis. Geometry had to be earned before Space, and Space had to become physically consequential before locality could be claimed.

Time now closes the same discipline from the other side. Retained consequence can generate an order of transformation without requiring a universal clock. Recurrent relational processes can, conditionally, supply endogenous standards by which ordered transformation is compared. But the derivation stops before the decisive physical synthesis.

Retained dependency can now yield an internal order once mutual-dependency cycles are collapsed, without an external clock.

Space and Time now coexist as distinct achievements of the relational framework. Space organizes where relational states can be localized and how neighboring regions constrain one another. Time organizes how retained transformations can stand in ordered dependency and how recurrent processes might provide temporal standards. Physical reality, however, does not present these as two independent ledgers.

The next question is therefore unavoidable:

Under what conditions do spatial localization and temporal order become mutually constrained aspects of one physical spacetime structure?

Nothing in Book I licenses writing a Lorentzian interval by fiat. It has not earned the minus sign, null separation, invariant c , causal cones, Lorentz transformations, or a 3+1-dimensional spacetime regime. Nor has it established that spatial mediation and temporal update should be commensurable at all.

Those are no longer background assumptions. They are research targets.




Figure 14.4. Book I as a whole. The fourteen chapters are the stages, and the mechanisms that carry one stage into the next are written on the arrows: distinguishing, retaining, relating, closing, orienting, recurring, formalizing, comparing, measuring, neighboring, coordinating, and ordering. The arrangement makes the chapter's inheritance visible, since retention and raw dependency are mechanisms established earlier and carried forward rather than renamed as temporal results. Book I ends only after Time has tested what additional structure is required to turn dependency into order.

The frontier can be summarized as:

- retained distinction $\rightsquigarrow$ relational organization $\rightsquigarrow$ geometry $\rightsquigarrow$ Space
- retained consequence $\rightsquigarrow$ dependency $<$ $\rightsquigarrow$ cycle quotient and coherent precedence $<_t$ $\rightsquigarrow$ Time
- Space + Time + unknown coupling constraints $\rightsquigarrow$? $\rightsquigarrow$ physical spacetime

Book II begins at the question mark. Its task is to test whether constrained extrapolations of the structures earned here can generate stable dimensionality, metric coupling, causal geometry, Lorentzian signature, and physical dynamics without those results being encoded in advance. If they can, the relational program has crossed from ontological possibility into a candidate account of physical instantiation. If they cannot, the failure identifies the boundary of the framework.

That is where Book I should end: not with spacetime assumed, but with spacetime made into a precise problem.

Selected References Cited in Time

Barbour, J. (1999). *The End of Time: The Next Revolution in Physics*. London: Weidenfeld & Nicolson; New York: Oxford University Press, 2000. The British edition carries the subtitle *The Next Revolution in Our Understanding of the Universe*. Used as

a contrasting relational/timeless interpretation and as a reminder that temporal ordering and fundamental temporal substance are separable questions.

Bombelli, L., Lee, J., Meyer, D., & Sorkin, R. D. (1987). Space-time as a causal set. *Physical Review Letters*, 59(5), 521–524. doi:10.1103/PhysRevLett.59.521. See also the exchange with Moore, *Physical Review Letters*, 60 (1988), 655 and 656. Used as a comparison class for partial-order approaches in which causal order is fundamental and continuum spacetime is emergent.

Lamport, L. (1978). Time, clocks, and the ordering of events in a distributed system. *Communications of the ACM*, 21(7), 558–565. doi:10.1145/359545.359563. Used as a formal comparison showing how dependency can establish event order without one global clock; not used as evidence for fundamental physics.

Price, H. (1996). *Time's Arrow and Archimedes' Point: New Directions for the Physics of Time*. New York: Oxford University Press. The double standard fallacy of chapter 1 is the objection nearest to this chapter's own index-removal test: an explanation of temporal asymmetry that assumes an asymmetry at the outset. Used for conceptual comparison on temporal asymmetry and the need to distinguish dynamical laws from arrows generated by boundary and statistical structure.

Rovelli, C. (2018). *The Order of Time*. Translated by E. Segre and S. Carnell. New York: Riverhead Books. Originally published as *L'ordine del tempo* (Milan: Adelphi, 2017). Used for conceptual comparison with relational and non-universal treatments of time in modern physics; not treated as a derivation of the present framework.

Appendix A. Formal Notation

This appendix is the book's reference for its notation: how to read a formula (A.1), the book's arrows (A.2), its notation conventions (A.3), the symbol table (A.4) and the core equations (A.5). Readers new to formal notation will find a full introduction in the companion volume, *Emergent Existence: A Companion to the Formalism*, which explains every kind of formula the book uses, with examples from these chapters, exercises and answers.

A.1 How to Read the Formulas

Most formulas stand on a line of their own, opened by a small square, ■. Each is a sentence written in compressed form and can be read aloud:

$$\blacksquare a \neq b \Rightarrow b \neq a$$

Read aloud: “if a differs from b, then b differs from a.” Three habits help. Translate a formula into words before judging it. Notice what it does not claim; the book often uses notation to show how little has been asserted. And check the surrounding prose for the formula's status, since a definition, a working hypothesis and established mathematics look alike on the page.

The notation is standard logic and mathematics: connectives and quantifiers, sets, relations and their properties, equivalence and order, maps and transformations, symmetry, and comparison without numbers. The companion volume explains each of these in turn. The one convention particular to this book is its use of arrows, set out next.

A.2 Arrows: Three Symbols, Separate Jobs

Arrows do several jobs in this book, and the jobs sit close together: the argument distinguishes the order in which it earns its concepts, the succession produced by an update, and genuine direction, and it must not let one pass for another. Following the notation discipline of A.3, jobs that could be confused have different symbols.

$$\blacksquare \text{Difference} \rightsquigarrow \text{Distinction} \rightsquigarrow \text{Retained distinction} \rightsquigarrow \text{Information}$$

The squiggle arrow, $\rightsquigarrow$, marks a chain of stages in the argument. Read it as “is followed in the derivation by.” It never means cause, time or physical direction. The book earns each of those later, and a chain written before they are earned must not borrow them.

$$\blacksquare \Sigma_n \mapsto L_n \mapsto \Sigma_{n+1}$$

The barred arrow, $\mapsto$, marks what an update, transformation or assignment does to a particular state or item. Read it as “is sent to” or “is succeeded by,” or, in a perturbation such as $r_{01} \mapsto r'_{01}$, “is replaced by.” It is the standard notation for what a map does to a single member. The succession it records is the order of the update, not physical time, which Time earns separately.

■ $\text{CG}_s : \mathcal{C} \rightarrow \mathcal{C} / \approx_s$

The plain arrow, $\rightarrow$, has two established uses, each in its own syntax. With a name and a colon, it states a map from one set to another. Read as “tends to,” as in $d_{\text{eff}}(\sigma) \rightarrow 3$, it states a limit. The two uses never meet in one expression, so they may share a symbol, and neither asserts direction. When Orientation earns direction, it writes it as orientational dependency, $<_o$ (7.2, 7.6), and introduces no directed arrow of its own. A coupling between a variation and its consequences, such as $K_{ij} : \Delta r_i \mapsto \Delta \mathcal{P}(r_j)$, uses the barred arrow.

Two further symbols are easily mistaken for arrows of motion and are not. The double arrow $=$ is logical implication. The curved sign $<$ is dependency precedence (14.4).

A.3 Conventions

Notation discipline. A symbol may carry established meanings in formally distinct syntactic domains where confusion is unlikely. Where two meanings can occur in the same conceptual or mathematical neighborhood, they must be separated explicitly.

The notation follows the author’s frozen notation table, and any change needs an entry here before it appears in a chapter.

Established physical symbols (c , G , S_{BH} , l_{P}) keep their standard meanings and take precedence over model symbols.

A chapter may not introduce a symbol without an Appendix A entry. Letters are chosen to stay clear of symbols already in use: in Formalism’s signature, for example, $\mathcal{C}$ avoids closure notation, $\Re$ avoids the matrix R and the relational domain $\mathcal{R}$, and fraktur $\mathfrak{G}$ names the formal carrier.

Script and blackboard-bold letters ($\mathcal{C}$, $\mathcal{D}$, $\mathcal{R}$, $\mathcal{I}$, $\mathfrak{S}$, $\mathbb{T}$) must be set in a face that stays distinct from the plain letters in print.

The Status column uses three labels. Defined term is stipulative. Working definition may be refined as chapters test it. A proposition label, such as Proposition 1B, means the entry depends on a claim that is not yet Retained.

A.4 Symbol table

Symbol	Meaning	Note
Ω	Origin: the minimally resolved reference condition	Origin
$\mathfrak{D}$	Primitive difference: the dyad $\langle a, b; \emptyset \rangle$, taken as one structure	Difference
$\emptyset$	The primitive difference relation, symmetric and irreflexive	Difference
$\mathcal{C}_{\mathfrak{D}}$	The minimal configuration carrier $\{a, b\}$: Difference's poles promoted to configurations once admissible succession is introduced	Distinction
$\mathcal{U}_{\min}$	The minimal admissible transition relation $\{(a, b), (b, a)\}$, with no primitive self-transition	Distinction
$J_{\mathcal{U}}$	The reciprocal map induced by $\mathcal{U}_{\min}$; $J_{\mathcal{U}}^2 = \text{id}$, so identity arises from composition	Distinction
$\mathfrak{T}_{\text{test}}$	Diagnostic transformation family used to test retention, declared in the metalanguage and not an internal update law	Boundary
Pres_W	Preservation predicate: the images of a and b under a transformation remain non-equivalent as resolved by frame W ; kept distinct from Return's $\text{Ret}(A_F; \cdot)$	Boundary
$\rightsquigarrow$	Derivational sequence: “is followed in the derivation by”; never cause, time or direction	All chapters; A.2
$\mapsto$	Update, transformation or assignment applied to a particular state or item: “is sent to”, “is succeeded by”, “is replaced by”	A.2
$\rightarrow$	Map (with a name and colon) or limit (“tends to”); never direction, which Orientation writes with $\prec_o$	A.2
r_{ij}, r_{ab}	Retained distinction between i and j (r_{ab} at the minimal dyad); symmetric until Orientation	Boundary to Relation
$R = [r_{ij}]$	The retained relations r_{ij} arranged as a pairwise array	Relation
$\mathcal{R}$	Relational set $\{q_i, R_{ij}\}$	Relation
Π_F	Projection: a resolution map from a richer relational substrate to effective geometry, possibly many-to-one	Geometry
$\text{CG}[\cdot]$	Coarse-graining operator	Space to Gravity

Symbol	Meaning	Note
$\mathfrak{S}$	Substrate state, reserved for Book II	Book II (Gravity)
d_{ij}	Correlation-based emergent distance	Distance
$d_o(A,B)$	Ontological distance: raised in Orientation as an open question, not constructed in Book I	Orientation
I	Information	Boundary
$\iota_i, \mu_i, \rho_i, \sigma_i, \alpha_i, n_i$	Information capacity, memory depth, recursive depth, self-model, agency, accessible degrees of freedom	Vol II
$\mathcal{C}_i, \Xi$	Consciousness of entity i , and the function that combines the six quantities above	Vol II
$\mathcal{A}, W_i$	Reference frame and its weighting operator	Boundary; Vol II
Φ	Substrate field, with $\langle \Phi \rangle$ the vacuum value and Φ_{eff} the effective field	Gravity to Quantum Gravity
Z_a	Complex amplitude of oriented distinction, $A_a e^{i\theta_a}$	Orientation
φ, F_n	Golden ratio; Fibonacci numbers	Scale
f_k, Θ	Layer map and network parameters	Vol II
$\mathcal{U}$	Admissible transition relation on configurations, the second foundational commitment; a subscript names what it updates	Distinction to Closure, 8, 16
a^*, E_{req}	Optimal intervention; required evidence	Vol III
$\mathcal{P}$	Possibility function: the set of relational states reachable from a configuration; $\mathcal{P}(r_{ij} / \mathcal{R})$ is the same set for a relation embedded in a domain	Boundary (4.10); Relation
$\mathcal{A}$	Aggregation, by convention only: $\mathcal{A}_{\exists}, \mathcal{A}_{\forall}$ abbreviate $\exists$ and $\forall$ over a shared membership predicate; not a primitive	Boundary (proposed); Relation (5.12)
$M_{\mathcal{R}}(r)$	Membership predicate: r participates in the organization $\mathcal{R}$ exactly when $\mathcal{P}(r \text{ given } \mathcal{R}) \neq \mathcal{P}(r)$	Relation (5.12)
$\sim\#, \hookrightarrow, \leftrightarrow$	Equinumerosity, injection and bijection between organizations; $[A]_{\sim\#}$ is a magnitude class. All available before numerals	Scale
$\text{mag}(X), \text{Cmp}(X, Y)$	Earned finite cardinal magnitude, and the comparative relation between two organizations. Lettered to stay clear of the marker vector m (3.6) and of Γ , which Book II reserves	Scale

Symbol	Meaning	Note
$\lambda^*, \sqcup, \approx_s, CG_s$	A stable scale factor as a fixed point of the ratio map; disjoint composition, implying no spatial separation; scale-relative equivalence and its coarse-graining operator	Scale
$\mathfrak{G}, \mathcal{C}, \mathfrak{R}$	The formal core and its parts: admissible configurations $\mathcal{C}$ (clear of $\mathfrak{C}_F$ and C_{ij}) and the relation family $\mathfrak{R}$ (clear of $\mathcal{R}$ and the matrix R)	Formalism
$\mathcal{U}[\Sigma], \mathcal{U}, \tilde{T}$	The successor set of a configuration; the quotient transition relation; a transformation acting on identity classes. $\mathcal{U}$ is a relation, and determinism is the case where every configuration has exactly one admissible successor	Formalism (Distinction to Return notation)
$\sim_W, \approx_{\mathcal{U}}$	Frame equivalence, where a resolving frame cannot separate two configurations, and behavioral equivalence, where they support matching patterns of admissible transition. Neither is interchangeable with $\sim_F$	Boundary (4.5, 4.15); Formalism
$\text{Ind}_R = (V_R, \mathcal{I}_R)$	Candidate independence system over relational modes, offered as a possible pre-metric formalization of d_R . Lettered to avoid $\mathcal{I}$ (information) and I (the identity triple of 4.8)	Formalism (5.14)
$\text{Ret}(A_F; \cdot), \text{Dom}_F$	Return predicate for the organizational anchor A_F , and the identity domain of the closed identity O_F . $\text{Ret}(A_F; \cdot)$ takes a configuration (8.3) or an orientation structure (7.8, 8.16)	Return (named Orientation)
χ	Internal condition of a realization that is not constitutive of the identity criterion F ; two realizations may satisfy the same F while differing in χ	Return
K_{ij}	Constraint relation: how admissible variation in r_i constrains that of r_j , $K_{ij} : \Delta r_i \mapsto \Delta \mathcal{R}(r_j)$	Orientation
$<_o$	Orientational dependency: $A <_o \Sigma_1 <_o \dots <_o \Sigma_k$. Not temporal precedence and not necessarily transitive or acyclic	Orientation
$\mathfrak{O}, \text{Ret}(A_F; \mathfrak{O})$	An orientation structure (fraktur O , clear of O_F and $O^{(n)}$), and whether a recursive organization under it returns to the identity class of anchor A	Orientation

Symbol	Meaning	Note
$W^{(L)}, \text{Res}_{W_0}$	The resolving map of a frame at organizational level L , in the sense of 4.5 and not a length scale; $\text{Res}_{W_0}(\Omega) = \emptyset$ states that no distinction is resolvable in the framework's initial frame	Orientation (Origin, Origin.5)
d_0	Number of independent orientational modes; weaker than vector-space dimension, and its relation to d_R and d_P is open	Orientation
$\text{Closed}_F(\mathcal{R})$	Closure predicate: $\mathcal{R}$ satisfies the structural closure test relative to F ; a predicate, not an operator	Closure
$\mathcal{I}_F(\mathcal{R})$	Set of configurations of $\mathcal{R}$ satisfying the constraints constitutive of F ; realizability requires $\mathcal{I}_F(\mathcal{R}) \neq \emptyset$ (script S , to stay clear of S_0 and S_1)	Closure
$\mathbb{C}_F$	Class of configurations satisfying the structural closure conditions for F (fraktur C , to stay clear of $\mathcal{C}_i$, C_{ij} and CG)	Closure
V_F	Set of admissible variations that preserve F ; a useful closure needs $V_F \neq \emptyset$	Closure
$F_{\text{dyn}}, F_{\text{obs}}$	Invariant actually preserved by the dynamics, and a frame's inferred criterion for it; F_{obs} need not equal F_{dyn}	Closure
$\lambda_i, \lambda_W(O)$	Relational profile of a state-position, or of an object as resolved by a frame W	Relation
$\mathfrak{T}$	Class of admissible transformations for a structural invariant (fraktur, to stay clear of T_{ijkl} and $\mathbb{T}^2$)	Relation
d_R	Relational rank, $d_R := \text{rank}(\text{Ind}_R)$, available once a suitable finite independence structure is earned; Geometry evaluates it on the stable independent modes of a geometric regime	Formalism (9.22); Geometry
d_P	Dimension of whatever space a system's components occupy; named in Book I only as a Book II quantity. $d_R \neq d_P$ in general; any comparison is withheld until both are earned	Relation (named); Distance
κ	Diffusion coefficient	Distance
ε, h, Δ	Curvature ratio $l_*/L_{\text{curvature}}$; derivative step; finite difference	Distinction, Quantum Gravity
$\text{Closed}_F(\mathcal{R})$	Closure predicate for domain $\mathcal{R}$ with respect to invariant F ; true or false, not an operator	Closure

Symbol	Meaning	Note
$\mathfrak{C}_F$	Class of configurations satisfying the structural closure conditions for F	Closure
V_F	Admissible variations that preserve F	Closure
$F_{\text{dyn}}, F_{\text{obs}}$	The invariant preserved by the dynamics, and an observer's criterion inferred from a resolving map W_O ; in general $F_{\text{obs}} \neq F_{\text{dyn}}$	Closure
$O_F^{\wedge}(n), A_F^{\wedge}(n)$	A closed identity and its organizational anchor at organizational level n; the superscript is level, not scale or time	Closure; A.5
$\mathfrak{M}_S$	Internal model a system forms of its own state, reserved for Volume II	Vol II
A_H, S_{BH}	Horizon area; Bekenstein-Hawking entropy	Black Holes
$d_u(A,B)$	The least magnitude of admissible relational mediation between two loci under the declared standard u; not a spatial length	Distance
u	The reusable relational standard against which chain magnitudes are compared; lettered to stay clear of the coarse-graining standard s of Scale	Distance
$\kappa, K(A,B)$	An admissible relational chain, and the set of such chains joining two loci; the minimum is taken over $K(A,B)$, which must be non-empty and finite	Distance
$L_u(\kappa)$	The magnitude of a chain: the comparative burden of the mediation it contains, additive only where composition is earned	Distance
$\mathfrak{Q}, \mathfrak{Q}_\alpha$	The layered relational substrate, and one metric-relational layer within it; distinct from the formal core $\mathfrak{G}$ of Formalism	Geometry
$K_\alpha, K_{\alpha\beta}$	The constraints internal to a layer, and those coupling two layers; an extension of the constraint relation K_{ij} of Orientation	Geometry
Π_F, I_F	The resolution map of a frame and the interaction it induces on the substrate; measurement is written $O_F = \Pi_F(I_F(\mathfrak{Q}))$	Geometry
d_{probe}	Effective dimension in the operational sense: the fewest independent parameters preserving the declared invariants across probes; whether it always agrees with d_R is open	Geometry
σ	The scale regime index, distinct from the magnitude standard u of Distance	Geometry

Symbol	Meaning	Note
ℓ_r, ℓ_F	The resolution scale of the underlying organization and of the frame examining it; effective smoothness requires ℓ_r much smaller than ℓ_F	Geometry
Geo	An effective geometric organization: the coordinated structure on which localization is defined	Space
$\lambda_{\text{Geo}}(A), \text{Loc}(A)$	The localization profile of A within Geo, and its localization class under the equivalence preserving that profile	Space
$\text{Adm}(A, B \mid \cdot)$	The admissible relational couplings between two loci under a given geometric organization; the rule through which spatial locality would hide if it were assumed	Space
Sp, Sp_F	A physically consequential spatial organization, and its resolution by a frame	Space
$<$	Retained-dependency precedence: the later state contains consequences whose removal would change it or its admissibility; not yet physical succession	Time
$<^+$	Reachability through one or more $<$ links	Time (14.5)
$\approx<$	Mutual dependency: $e_i \approx< e_j$ when each is reachable from the other; its classes collect dependency cycles	Time (14.5)
$<_t$	Temporal precedence between mutual-dependency classes; a strict partial order by construction	Time (14.5)
$\mathcal{T} = (\mathcal{E} / \approx<, <_t, \text{Rec}, \text{Cyc})$	The candidate temporal object: resolvable events taken up to mutual dependency, temporal precedence between the resulting classes, the retained records by which precedence is recoverable, and an optional family of recurrent comparison processes	Time
Rec, Cyc	The record family and the recurrence family of $\mathcal{T}$; lettered to stay clear of Formalism's relation set $\mathfrak{R}$ and configuration set $\mathcal{C}$	Time
$N_c(e_a, e_b)$	The count of retained update steps along a chain: a structural quantity, and not yet a duration	Time
$\tau_K(A, B)$	The temporal measure supplied by a candidate clock K, as cycle count times the unit assigned to one cycle	Time

A.5 Core equations

Each equation is tagged by type, following the standing rule that established mathematics, model mathematics and conceptual notation stay distinct.

Recursive cycle (conceptual)

$$\blacksquare \mathcal{R}^{(n)} \rightsquigarrow \mathcal{O}_F^{(n+1)} \equiv \mathcal{A}_F^{(n+1)} \rightsquigarrow \mathcal{R}^{(n+1)}$$

Read this only when $\mathcal{R}^{(n)}$ satisfies the relevant closure and higher-order addressability conditions. The sequence is derivational and organizational, not temporal. Ω is not recursively copied forward; higher-order originhood is earned by closure (6.12, 6.13).

Fibonacci recurrence and golden ratio (established mathematics)

$$\blacksquare F_{n+1} = F_n + F_{n-1}, \varphi = (1 + \sqrt{5}) / 2$$

Consciousness vector (conceptual, Volume II)

$$\blacksquare \mathcal{C}_i = \Xi(\iota_i, \mu_i, \rho_i, \sigma_i, \alpha_i, n_i)$$

Bekenstein-Hawking entropy (established physics)

$$\blacksquare S_{\text{BH}} = k_B A_H / (4 \ell_P^2)$$

Intervention rule (normative model, Volume III)

$$\blacksquare a^* = \operatorname{argmax}_a [\text{Benefit}(a) - \text{StructuralCost}(a) - \text{OtherHarm}(a) - \text{Uncertainty}(a)]$$

Evidence rule (normative model, Volume III)

$$\blacksquare E_{\text{req}} \propto \text{Depth} \times \text{Irreversibility} \times \text{Reach}$$

Appendix B. Conceptual Lexicon

The terms below carry technical senses narrower than their ordinary ones. Where a word is doing work the framework has earned, this is what it means; Appendix A carries the symbols.

Term	Symbol	Definition	First appears	Status
Origin	Ω, Ω_n	The minimally resolved reference condition: a condition from which no operative distinction is available within the framework's initial relational frame. Undifferentiated at that resolution; not defined as the absolute ontological absence of distinction. Not a place, moment, substance or cause. Successive origins in the recursive cycle are indexed Ω_n	Origin	Defined term
Distinction	$\mathcal{D}$	The primitive operation that produces difference, so that one relational state differs from another. Distinction is primitive; a derivative measures change in distinction	Distinction	Working axiom (Proposition 1B)
Retained distinction	none	Distinguishability that survives transformation long enough to constrain later states	Preface; Distinction	Defined term (Proposition 1A)
Relational bit	r_{ij}	The smallest persistent unit of relational distinction between states i and j . Distinct from the computational bit b , an engineered encoding of distinction, written $b = \Pi(r)$	Distinction to Boundary	Defined term

Term	Symbol	Definition	First appears	Status
Boundary	none	The relational condition under which two states remain non-equivalent, a criterion of separability rather than a spatial surface; symmetric in the states even though the designation marking one of them as Ω is not	Boundary	Working definition
Higher-order membership	$M_{\mathcal{R}}$	A relation r belongs to the organization $\mathcal{R}$ exactly when embedding it there changes its admissible possibilities, $\mathcal{P}(r \text{ given } \mathcal{R}) \neq \mathcal{P}(r)$. Not a new primitive: quantification over members stays in the metalanguage, and $\mathcal{A}$ survives only as notation for it. Threshold and weighted membership are deferred until magnitude is earned	Relation	Convention ($\exists/\forall$ Derived; threshold Deferred)
Relational profile	$\lambda_i, \lambda_F(O)$	The ordered collection of retained relations a state-position (or, relative to a frame F , an object) participates in; two positions with different profiles are structurally distinguishable without intrinsic properties	Relation	Working definition
Relational structure	$\mathcal{R}, R = [r_{ij}]$	A set of retained relations whose admissible states are constrained by the organization of the other relations in the set, $\mathcal{P}(r_{ij} / \mathcal{R}) \neq \mathcal{P}(r_{ij})$; stronger than coexistence or connectivity	Relation	Working definition (Provisional)
Structural persistence	$F(T(\Sigma)) = F(\Sigma), T \text{ in } \mathfrak{T}$	Preservation of an identity-relevant relational invariant F through an explicitly stated class $\mathfrak{T}$ of admissible transformations; distinct from state persistence and from carrier persistence	Relation	Working definition

Term	Symbol	Definition	First appears	Status
Relational re-instantiation	$\sim_F$	The production of a new state or realization whose organization preserves selected relational invariants of an earlier structured state; $\sim_F$ is equivalence with respect to the invariant F, never physical identity	Relation	Defined term
Relational position	$p_A = \lambda_F(O_A)$	The distinctive relational profile an object occupies relative to a persistent reference frame; not a coordinate, and carrying no order, interval, metric or adjacency	Relation	Working definition (Provisional)
Relational degrees of variation	d_R	The number of independent ways a relational domain can vary; relation count is not relational dimension, and d_R is not yet rank, which Formalism must earn	Relation	Working definition (Deferred formalism)
Information	I	What distinction becomes when preserved: preserved distinguishability, not by default a separate substance	Boundary	Working definition (Proposition 2)
Memory	μ_i (depth)	Retained change that becomes internally consequential for a self-maintaining system: retained distinctions from the system's own transformations alter its available responses. Requires self-maintenance, not a self-model or self-awareness. Distinct from retention, dependency order and path dependence (Boundary to Closure), which are foundational and are not yet memory	Memory	Working definition (Proposition 3B)

Term	Symbol	Definition	First appears	Status
Relation	$R_{ij}, \mathcal{R}$	A persistent distinction viewed as linking the states it distinguishes. R_{ij} is the pairwise relational matrix and $\mathcal{R}$ the relational set $\{q_i, R_{ij}\}$	Relation	Working definition
Recursion	ρ_i (depth)	The process in which prior relational states become inputs to later ones, summarized $\Omega_n \rightsquigarrow \mathcal{D} \rightsquigarrow I \rightsquigarrow \mathcal{R} \rightsquigarrow \Omega_{n+1}$	Closure, Scale	Working definition
Closure	$\text{Closed}_F(\mathcal{R})$	A relational domain is structurally closed with respect to an invariant F when every dependency constitutively required to maintain F is supplied within it, the constitutive relations actually participate in maintaining F , and the requirements are jointly realizable (6.4). Structural closure is a property of a state; dynamic closure adds persistence, the preservation of that sufficiency under $\mathcal{W}$ (6.7), and robust closure adds survival across a preregistered class $\mathfrak{z}$ (6.8). A predicate, not an operator, and not isolation from an environment. Simplicial completion (a tetrahedron, whose edge graph is K_4) is one possible later mathematical realization of structure, not the meaning of closure; the earlier K_4 definition is superseded (6.1)	Closure	Working definition (Provisional)

Term	Symbol	Definition	First appears	Status
Comparative magnitude	$A \sim\# B; A \hookrightarrow B; \text{Cmp}(X, Y)$	Sameness of amount by bijection, order of amount by injection, and the comparative relation between two organizations. Earned before any numeral: $A \sim\# B$ is not an alias for equal cardinal labels, since the label names the class the correspondence established	Scale	Working definition (Retained)
Endogenous standard	$\text{Cmp}(O_{n+1}, O_n) \approx \text{Cmp}^*$	A comparative relation the structure supplies repeatedly through recurrence, rather than one imported from outside. Not a unit: a unit needs a calibration scheme later chapters must earn	Scale (Return)	Working definition (Provisional)
Scale-relative coarse-graining	$\text{CG}_s : \mathcal{C} \rightarrow \mathcal{C} / \approx_s$	Reduction of detail indexed to an earned comparison standard s , admissible only in that order: magnitude, then standard, then scale-relative equivalence, then the operator. Smallness by metric distance remains unavailable	Scale (deferred here by Orientation)	Working definition (Provisional)
Formal core	$\mathbb{G} = (\mathcal{C}, \mathcal{R}, \mathcal{U})$	The weakest carrier in which the earned ontology can be stated: admissible configurations, the family of earned relations at unrestricted arity, and the admissible transition relation $\mathcal{U} \subseteq \mathcal{C} \times \mathcal{C}$. Closure, orientation and return are predicates over it, not components of it. Compatible with graphs, hypergraphs, transition systems and other faithful representations; identical with none of them	Formalism	Working definition (Provisional)

Term	Symbol	Definition	First appears	Status
Quotient dynamics	$[\Sigma]_F \not\approx [\Sigma']_F$	Transition descending to identity classes. When an independently constrained equivalence is compatible with admissible transformation, the higher-order identity supports dynamics independent of the choice of lower-order representative. Sufficient for higher-order autonomy; not claimed necessary for every emergent phenomenon	Formalism (6.12)	Working definition (Provisional)
Identity-class fixed point	$\bar{T}([\Sigma]_F) = [\Sigma]_F$	A macro-identity preserved while the lower-order state changes; distinct from an exact fixed point $T(\Sigma) = \Sigma$. Attractor and invariant-set language is deferred, since it presupposes topology or metric neighborhoods	Formalism	Working definition
Return	$\text{Ret}(A_F; \cdot)$	Departure from an independently specified identity class, oriented transformation, and re-entry into that class: $\text{Ret}(A_F; \Sigma_k) = 1$ iff $\Sigma_k \in O_F$ after genuine departure. A predicate over earned relations, not a new operation. Return of identity does not require exact repetition of state; persistence without departure is not return; and departure requires F to remain applicable, since a configuration to which F_A no longer applies has dissolved rather than departed (8.4). “Origin” in the chapter title means the anchor, not Ω	Return (Orientation uses it in anticipation)	Working definition (Provisional)

Term	Symbol	Definition	First appears	Status
Identity domain	Dom_F	The set of configurations satisfying a closed identity's criterion F , the members of O_F . Deliberately weaker than a basin of attraction, which would presuppose state-space structure the framework has not earned	Return	Working definition
Retained path consequence	$\chi(A') \neq \chi(A)$	Difference in internal condition, not constitutive of F , left behind by the route through which an identity returned. Distinct from retention (Boundary) and from memory, which requires internal consequence for a self-maintaining system (Memory)	Return	Working definition
Orientation	$K_{ij} \not\sim K_{ji}, <_o$	Persistent, consequential non-equivalence between otherwise exchangeable relational dependency roles. Derived, not primitive: an arrow is notation applied once the non-equivalence is established. Not partial order, causality, metric time or spatial direction (7.13)	Orientation	Working definition (Provisional)
Effective asymmetry	$W^{(L)}(\Sigma) \neq W^{(L)}(g\Sigma)$	A lower-order non-equivalence that survives a higher-order identity's resolving criterion and changes its admissible organization. Distinct from latent asymmetry, which stays below that threshold, and from orientation, which additionally persists into dependency structure	Orientation	Working definition

Term	Symbol	Definition	First appears	Status
Relational irreversibility	$\text{Ret}(A_F; \mathfrak{D}) = 1, \text{Ret}(A_F; \mathfrak{D}^{-1}) = 0$	Anchor-relative: reversing the orientational dependencies destroys, changes or redirects return to the same identity anchor. Not thermodynamic irreversibility and not an arrow of physical time	Orientation	Working definition (Speculative extension)
Higher-order origin	$O^{\wedge}(n)$	A closed, relationally addressable organization taken as a new starting unit for further relational construction, $\mathcal{R}^{\wedge}(0) \rightsquigarrow O^{\wedge}(1) \rightsquigarrow \mathcal{R}^{\wedge}(1) \rightsquigarrow \dots$; the superscript marks organizational level, not scale or time. Does not replace Ω or by itself relocate the anchor	Closure	Working definition (Provisional)
Constitutive dependency	none	A dependency without which the identity-relevant organization F is not specified or maintained; contrasted with an enabling condition, an input the organization operates under without being constituted by it. Closure requires every constitutive dependency to be internal, not every input	Closure	Working definition
Relational addressability	$\tilde{E}([\Sigma]_{\sim F}) = [E(\Sigma)]_{\sim F}$	The condition under which a closed organization enters higher-order relations as one relatum: an external relation E is well defined on the equivalence class O_F exactly when $\Sigma_a \sim_F \Sigma_b$ implies $E(\Sigma_a) \sim_{F'} E(\Sigma_b)$, so that E descends to the class, as in a quotient construction or a lumpable Markov chain. The sense in which completion becomes a new origin; not yet causal addressability	Closure	Working definition (Provisional)

Term	Symbol	Definition	First appears	Status
Substrate	$\mathfrak{S}$	The evolving totality of relational structure from which effective geometry is projected. The preferred parsimonious reading treats it as the structure itself and not a medium beneath it	Formalism	Working definition (Open in the Register)
Metarelation	none	A relation among relations, the basis of the deeper state space treated in Formalism	Formalism	Working definition
Ontological distance	$d_o(A,B)$	A vector (d_p, d_i) of physical or spatiotemporal distance and informational or relational distance. Distinct from the correlation-based emergent distance $d_{ij} = -l_0 \ln(C_{ij}/C_0)$	Formalism, Distance	Working definition (Proposition 10)
Reference frame	$\mathcal{A}_i, W_i$	A stable entity treated as a local filter of a larger relational reality, with weighting operator W_i so that experienced reality $O_i = W_i(X)$	Boundary (concept); Vol II	Working definition
Projection	$\Pi, P^{\wedge}A_m$	A map from relational structure to effective spacetime coordinates or fields, $\Pi: M_{\text{rel}} \rightarrow M^{\wedge}(3,1)$, with components $P^{\wedge}A_m$	Space	Working definition (Proposition 6)
Coarse-graining	$CG[\cdot]$	Averaging over microscopic relational structure to give an effective description; $g_{mn} = CG[G_{AB}]$ is the shorthand	Space to Gravity	Working definition
Epistemic mode	none	The kind of claim a passage makes: Observed, Established, Interpretive, Speculative, Predictive or Formal (Normative in Volume III)	Preface	Defined term
Hypothesis status	none	The project's decision about a claim: Retained, Derived, Provisional, Deferred, Rejected or Open	Preface; Register	Defined term

Terms introduced in later chapters, such as the torus and Hopf structures, are added here as those chapters are drafted.

Appendix C. Hypothesis Status Register

Every proposition this book leans on appears here with its status, the reason for that status, and what would resolve it. The Preface promises this register and the Methodology explains why: a gap explicitly located is worth more than a conclusion reached by hiding an assumption. A reader who wants to audit the framework rather than follow it should begin here.

The eight statuses carry the meanings used throughout:

Status	Meaning
Retained	Held as part of the framework, having survived the objections raised against it
Provisional	Held for now, on stated conditions, and revisable if those conditions fail
Derived	Obtained from what earlier chapters earned, rather than assumed
Open	Genuinely unsettled; the book states the question and does not answer it
Deferred	Set aside deliberately, with the chapter that must take it up named
Rejected	Considered and dropped, recorded so the reasoning is not repeated
Speculative	Proposed beyond present evidence or derivation, and kept visible as conjecture
Superseded	Replaced by a better-bounded formulation, and kept so the framework's history stays auditable

Entries are numbered for reference only; the order is the order in which they entered the project, not an order of importance. Where an entry names a chapter, it names the reference frame rather than a position in the sequence.

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-1	The relational substrate is intrinsically oscillatory (waveform) at the foundational level	Deferred	Wave-like modes may arise from spectral dynamics of relational structures, so assuming a waveform ontology adds a primitive before derivation requires it	Coherent phase dynamics cannot emerge without an oscillatory primitive, or a prediction requires one	Matter (scoped section); App B, D

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-2	The substrate follows diffusion dynamics, wave dynamics, or separate regimes of one deeper evolution	Open	The diffusion and wave equations behave differently, and the book must say which governs which regime	A formal statement of substrate dynamics that assigns each regime	Distance; App D
H-3	A discrete relational spectrum is sufficient for quantum behavior	Rejected	Discrete eigenvalues do not equal quantum mechanics; phase and superposition structure are also needed	A derivation of phase-carrying dynamics and superposition from the relational formalism	Matter
H-4	“Information is fundamental” (strong form)	Rejected	Replaced by the more defensible substrate claim: a universal relational substrate encodes primitive distinctions, and its higher-order organization projects into experienced reality	None planned	Boundary, 10
H-5	The substrate is a medium beneath relations, or the evolving relational structure itself	Open	The parsimonious version, substrate as the total evolving structure of relational distinction, is preferred	A result that requires a medium, or shows the structure alone suffices	Formalism
H-6	Conventional information theory is a coarse-grained special case of relational distinction	Open	Framed as a research question, not a conclusion	A derivation of Shannon entropy from the relational formalism	Boundary, 9; App B
H-7	The physical universe is literally a mathematical empty set	Rejected	The empty/non-empty distinction is a logical analogy only	None planned	Origin

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-8	Hopf-fibration structure derives particle spin	Deferred	Used as inspiration for linked fibers, phase and orientation; a direct derivation of known spin is premature	A construction recovering spinor structure from the relational formalism	Orientation to Return
H-9	The torus is dynamically selected rather than assumed	Open	Currently a candidate stable topology; selection is untested	A toy model in which closed circulation emerges as an attractor	Return
H-10	The Riemann zeta function is a physical foundation	Deferred	Considered as an analogy between global analytic structure and irreducible prime structure only	A derivation linking relational structure to zeta-type analytic structure	App C (analogy note)
H-11	Nature universally prefers the golden ratio	Rejected in universal form; Retained in conditional form	The ratio phi is the stable fixed point only under the canonical two-state additive recurrence	None planned for the universal form	Formalism; App C
H-12	Dimension and 3+1 Lorentzian geometry emerge from simple recursive relational rules	Open	Toy-model targets: first, stable low-dimensional geometry; second, 3+1 Lorentzian geometry as an attractor	Computational toy-model results	Closure, 9, 13; Computational Companion
H-13	Lorentzian signature $(-, +, +, +)$ can be recovered	Open	Acknowledged in the outline as a hard challenge	A causal-order construction that yields the signature	Space; Computational Companion
H-14	General relativity is the laminar regime of relational dynamics	Open	The book asks what microscopic relational dynamics could recover Einstein-like curvature and approximate Lorentz invariance	A derivation of Einstein-like behavior in the continuum limit	Gravity

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-15	The singularity is an evolving compressed relational state	Open	A speculative reconception of the static point-object	A model of how infalling information updates the compressed state	Black Holes to Recursive Cosmogenesis
H-16	Our universe is simply inside a black hole	Rejected	Replaced by the more defensible conjecture in the next row	None planned	Recursive Cosmogenesis
H-17	Black-hole formation and cosmological origin are opposite reference-frame descriptions of a deeper spacetime transition	Open	Conjecture; needs a bounce or topology-change mechanism	A model of horizon crossing into a new expanding domain	Recursive Cosmogenesis
H-18	The cosmic web is literally a global T^3 cosmology	Rejected	The cosmic web is kept separate from literal global 3-torus cosmology	None planned	Complexity
H-19	Cosmic voids and filaments carry signatures of scale-recursive circulation	Open	Highly speculative and kept explicitly separate from standard structure formation	A testable signature that distinguishes it from standard structure formation	Complexity
H-20	Sacred-geometry claims are evidence	Rejected	Flower of Life and similar motifs serve as structural metaphor (center, boundary, new center), not empirical support	None planned	Lineage note
H-21	An external creator is the first explanatory primitive	Open	The framework does not disprove creation; it asks whether recursive distinction and stability suffice without one	Not resolvable by the framework alone	Vol III

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-22	Any observable physical reality containing persistent states requires retained distinction (Proposition 1A)	Retained	A near-definitional necessary condition that adds no primitive; the status applies to the necessity of retained distinction, not to any claim about the ultimate primitive (see H-128)	None planned	Preface; Distinction; Boundary
H-23	Distinction is the primitive operation from which relational physical structure ultimately emerges (former Proposition 1B)	Superseded	Replaced by H-128. Distinction is now the operative resolution of a prior difference, not the primitive	None planned	Preface; Difference (2.2)
H-24	Two distinguishable states, one of which is the origin Ω itself, are the minimum scaffold for relational existence	Superseded	Replaced by H-128. The minimum is a symmetric dyad whose poles are not Ω ; Origin is a resolution condition, not a pole, and the Ω designation moves to Distinction (H-25)	None planned	Difference (2.3, 2.9)
H-25	Designating one pole of the primitive dyad as Ω is a stated cost, paid in Distinction	Superseded	Distinction no longer designates a reference pole: reciprocal exchange preserves the dyad's symmetry (3.6), and a reference role is deferred to Closure (4.18)	None planned	Distinction; Boundary (4.18); Closure

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-26	The primitive dyad could be reconstructed from a recursive rule whose only prior reference role is Ω , so that Origin's recursive self-relation would generate Difference	Speculative	Retained from the distinction-first architecture as a reduction hypothesis, not a working claim; no rule yet yields the dyad without already containing two differentiated states, orientation, metric, time or an external mark (2.12)	Such a rule would make Difference derived rather than primitive and move this entry toward Provisional	Difference (2.12); Closure, 10
H-27	Recursion at the foundation presupposes physical time	Rejected	n indexes the order of derivation, not duration	None planned	Time
H-28	The poles of the primitive dyad are weakly discernible only via $\emptyset$; telling them apart from within needs a structural resolver, an Ω designation, or an oriented relation	Provisional	Follows from the swap automorphism of the dyad (2.5); each route to breaking it is a separate later cost	Tested in Distinction, Orientation and Geometry	Difference (2.5); Distinction; Orientation, 12
H-29	An oriented relation makes order a consequence of direction rather than a further, independent cost	Retained	Definitional: telling source from target is what a directed relation means (3.6, Scaffold B). Distinguished from the rejected claim that a state's own change must be asymmetric on some intrinsic property	None planned	Distinction (3.6); Orientation, 12

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-30	First-order recursion does not exclude finite-order retained history, since a finite-order recurrence is first-order on an enlarged state	Retained	Standard mathematics, used in 3.7	None planned	Formalism, 20
H-31	A designation marking one pole as Ω could eventually be replaced by content-based distinction	Superseded	No pole is ever designated as Ω : reference is earned as an organizational role of a closed identity (H-133)	None planned	Closure (6.13)
H-32	Retention is the survival of the reciprocal distinction under admissible transformation, the images of a and b remaining non-equivalent as resolved by a frame W, not the invariance of the transformed state itself	Retained	Near-definitional core of Proposition 1A, stated symmetrically: no pole is distinguished from Ω , and the preserved distinction may change its realization (4.6, 4.8, 4.9)	None planned	Boundary (4.6, 4.8, 4.9)
H-33	Loss of retention is collapse, not return to Ω : a transformation after which no admissible frame recovers the distinction between a and b	Retained	Follows from the preservation predicate once no pole is designated as Ω (4.7); collapse removes the distinction without restoring an origin	None planned	Boundary (4.7)
H-34	Information is retained relational distinguishability that remains resolvable by at least one frame and constrains later relational possibilities	Provisional	A working definition, deliberately functional and pre-statistical; extends the $\mathcal{D}$ to persistence to r_{ij} to I chain from 3.9	Derivation of conventional information measures as special or coarse-grained cases would move it toward Retained	Boundary (4.10); Formalism

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-35	At the minimal domain the anchor is Ω	Superseded	No anchor is inherited from Ω at any stage; the first reference role is earned in Closure as the organizational anchor A_F (H-133)	None planned	Boundary (4.18); Relation (5.15); Closure (6.13)
H-36	Whether the anchor stays fixed at Ω , relocates, or distributes once a domain grows past the primitive pair	Superseded	The question presupposed an inherited anchor. Relation withholds reference (5.15), and Closure earns it as a role of the closed organization as a whole; whether that role later localizes or distributes is recorded in H-133	None planned	Relation (5.15); Closure (6.13)
H-37	Retained dependency order ($\Sigma_a < \Sigma_b$) is a candidate precursor of causal order, possibly the same asymmetry as orientation or derivation order seen a third way	Open	Defined without a metric or clock, consistent with 3.7 and 4.5, but not yet shown sufficient for causal-set-like structure	A construction recovering relativistic causal cones from dependency order alone would move it to Provisional; Chapter 12 is where the three candidate asymmetries are to be reconciled	Boundary (4.9); Time
H-38	A primitive boundary is a relational criterion of separability, not a spatial surface	Retained	Definitional at this stage; spatial boundary is deferred to later geometric chapters	None planned	Boundary (4.7); Relation to Closure
H-39	A frame's failure to resolve two states does not entail their ontological identity	Retained	Follows from the separation of difference from its resolution (2.8) and from weak discernibility (2.5): resolvability is frame-relative, non-equivalence is not	None planned	Difference (2.5, 2.8); Boundary

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-40	Measurement in this chapter means structural resolvability, not observer-mediated interaction	Retained	Observer-mediated measurement is one later implementation of a resolving frame, not a primitive requirement	None planned	Boundary (4.2, 4.13 Obj. 4)
H-41	$\mathcal{P}$ names the admissible-possibility set generated by $\mathcal{U}$ and adds no primitive beyond the two foundational commitments	Retained	$\mathcal{P}$ is defined from admissible succession (4.10) so that retained distinction can be said to constrain it; $\mathcal{U}$ itself is the second commitment (H-131)	None planned	Boundary (4.10, 4.11); Relation; notation table
H-42	The capacity and saturation formalism drafted for Chapter 4 (resolving capacity, relational density, effective dimensionality) is archived pending a chapter with more than one relation	Deferred	Needs a multi-relation domain Chapter 4 does not have; placed in Chapter 10 (Scale) on 22 September 2026	Placement decided once the relevant chapter is drafted (Blueprint Reminder 3)	Boundary (archived); Scale
H-43	Independence of relational variation requires more than one retained distinction, and Relation earns an independence problem rather than a numerical dimension	Retained	Counting is not earned until Scale, so the number of independent modes cannot yet be stated (5.14)	None planned	Relation (5.14); Formalism; Scale
H-44	The “informational black hole” is a scoped analogy for representational saturation, not a claim about gravitational black holes	Open	Boundary defers any substantive link to Book II; verbal similarity alone is not evidence	A nontrivial physical prediction connecting the two would move it to Provisional	Boundary; Book II

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-45	Volume I divides into Book I (Formal Existence, Chapters 1-9) and Book II (Physical Existence, Chapters 10-21), split where the argument turns from combinatorial/topological structure to metric structure	Superseded	The rebuilt derivation shows that Scale through Time are still prephysical prerequisites; metric structure alone does not mark the transition to physical instantiation	None planned	Superseded by H-134
H-46	Existential and universal boundary aggregation over a multi-relation domain need no new primitive: judged by one shared predicate P (the constraint test of 5.4), they are quantification over P , and $\neg$ survives only as a notational convention. Distinct from frame reconciliation, which combines verdicts not judged by a shared predicate	Derived	Derived in 5.12 within stated assumptions: a structural shared predicate, and quantification declared as a logical resource at 4.2. Order-independence of $\exists$ and $\forall$ keeps any computing enumeration from becoming an ordering of the relations	A case in which $\exists/\forall$ membership over a shared predicate still needed an operation beyond quantification would reopen it	Boundary (4.2, 4.8); Relation (5.12)
H-47	Transitional membership cases are cases in which the constraint predicate $P(r)$ has not yet stabilized; latent integration (4.9) settles the inputs and quantification then settles the verdict, so no further primitive is needed	Provisional	Follows once aggregation is quantification (5.12): a verdict over a settled predicate cannot be disputed. Not yet shown in a worked example	A worked edge case in which $P(r)$ stabilizes under $\Sigma_n \mapsto L_n \mapsto \Sigma_{n+1}$ and the quantified verdict follows	Boundary (4.9); Relation (5.13)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-48	Threshold boundary aggregation (membership when enough relations satisfy P, absolutely or proportionally)	Deferred	Needs a count of satisfying relations, a comparison with a bound and, for proportions, a ratio; describing a finite collection does not earn its cardinality, and Book I has not earned it	Chapter 10 (Scale), which earns relative magnitude and with it cardinality	Relation (5.12); Scale
H-49	A relational structure is a set of retained relations whose admissible states are mutually constrained by the organization of the set, $\mathcal{R}(r_{ij} \mid \mathcal{R}) \neq \mathcal{R}(r_{ij})$	Provisional	Central working definition; separates structure from connectivity without causation, but needs formal sharpening against counterexamples	A formalization of constraint free of probabilistic or metric language would move it toward Derived	Relation (5.4); Formalism
H-50	Structural persistence can preserve relational invariants without preserving particular states or carriers	Retained (logical form); Provisional (ontological extension)	The logical distinction is strong and mirrors multiple realizability; the claim that nature works this way remains under development	None planned for the logical form; a physical case for the extension	Relation (5.6-5.7)
H-51	Object-like identity can be modeled as an equivalence class of configurations preserving identity-relevant organization, $O = [\Sigma]_{-F}$	Speculative	Useful formal scaffold; not established as a general ontology of physical objects, and vacuous if F can be chosen after the fact	Nontrivial persistence criteria or a computational test that separates integrated clusters from arbitrary groupings	Relation (5.9, 5.16); Computational Companion
H-52	Two internally equivalent persistent objects require a higher-order relational difference, $\lambda_F(O_A) \neq \lambda_F(O_B)$, to remain observably distinguishable within one frame	Provisional	Extends weak discernibility recursively; needs formal treatment of exchange symmetry and observables	A worked case identifying the minimum reference structure that breaks exchange symmetry	Relation (5.10); Orientation

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-53	Relational position precedes spatial position	Provisional	Defined as a distinct relational profile to a persistent frame; spatial interpretation explicitly deferred	Chapters 7 and 11 must show that spatial order can be built on it	Relation (5.11); Orientation, 11
H-54	Independent relational degrees of variation d_R can later support dimensional geometry	Deferred	Relation earns only the independence problem (5.14). Formalism introduces d_R conditionally, as the rank of an independence system Ind_R , once a suitable finite independence structure is earned (9.22); metric dimensionality and orthogonality belong later	Geometry showing that stable, decoupled relational modes realize d_R	Relation (5.14); Formalism (9.22); Geometry
H-55	Stable dynamics can select effective orthogonality through decoupling rather than orthogonality being a capacity of the domain	Deferred	Reserved for the physical-emergence program; must not be assumed in Book I	A model in which cross-coupling between collective modes decreases under coarse-graining	Relation (5.14); Distance to Space
H-56	Closure is simplicial completion: an origin plus three independent differentiations gives minimum three-dimensional closure, whose edge graph is K4	Rejected	Superseded by Chapter 6 as a definition: it inserts geometric structure (simplices, a target dimension) that Book I is trying to earn. Survives only as one realization (next entry)	None planned	Closure (6.1); App A, G

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-57	Simplicial completion (K4 and higher simplices) is one possible mathematical realization of closure, not its definition	Provisional	Useful where structure is given a simplicial encoding (T_{ijkl} , G.4); whether closure is ever realized simplicially is a Book II question	Chapters 9 and 11 showing that a simplicial realization satisfies the 6.4 test	Closure (6.1); Formalism, 11; Computational Companion
H-58	Structural closure is internal sufficiency, participation and joint realizability of the dependencies constitutive of an invariant F; dynamic closure adds persistence under $\mathcal{U}$, and robust closure adds survival across a preregistered $\mathfrak{T}$	Provisional	Working definition; the three-part test is stated as necessary, not yet shown sufficient	A necessary-and-sufficient formal criterion (Chapter 9)	Closure (6.2-6.8)
H-59	Closure is a predicate, not an operator, and $\mathcal{U}$ keeps its state-to-state type	Retained	Required by the parsimony rule; avoids a new primitive and keeps dynamic closure a property of trajectories rather than a meaning of $\mathcal{U}$	None planned	Closure (6.3, 6.7)
H-60	A closed organization is relationally addressable, and can serve as a new higher-order origin, exactly when external relations descend to its equivalence class (the quotient, or lumpability, condition)	Provisional	A precise criterion (6.12), not yet tested on generated networks. When the closed identity is also dynamically persistent, addressability earns an organizational reference role, the anchor A_F (6.13; H-133)	The addressability diagnostic of 6.17 against matched controls (Computational Companion, module 5)	Closure (6.12, 6.13, 6.17)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-61	Closure does not require exclusive membership; one relation can belong to several compatible closures	Retained	The definition contains no exclusivity axiom. Incompatible overlap, two closures demanding contrary states of one relation, remains open	None for compatible overlap; incompatible overlap needs a resolution rule	Closure (6.11)
H-62	The invariant F that individuates an object can be constrained by dynamics and perturbation (F_{dyn}) rather than chosen after the fact by a frame (F_{obs})	Open	The chapter's most serious risk: without an observer-independent constraint on F , objecthood reduces to descriptive coarse-graining	Preregistered perturbation and ablation tests showing F_{dyn} is recoverable	Closure (6.14; 6.19, Objection 4)
H-63	Relational independence is not embedding dimension: a system can have many non-redundant relational modes without each becoming a spatial axis	Retained (distinction); comparison of d_R with d_P Deferred	Relation keeps the two apart but withholds any comparison such as $d_R \leq d_P$ until both quantities, and the magnitude needed to compare them, are earned (5.14)	Earning d_R (see H-54) and d_P (Book II)	Relation (5.14); Book II
H-64	Retention, dependency order and path dependence are foundational and are not yet memory; memory requires a self-maintaining system for which retained change is internally consequential, and does not require a self-model or self-awareness	Retained	Separates two senses the book had run together; removes the circularity of using temporal-sounding memory before time is earned; keeps memory short of Knowing	None planned; the later chapters on Life, Memory and Knowing must respect the thresholds	Boundary to Closure, 19-21

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-65	Volume I architecture: Memory placed at Chapter 20 between Life and Knowing; 21 chapters kept; Book I/II seam at 9/10; pre-life “memory” titles renamed to record	Superseded	The entry bundles claims that no longer share one status: the 9/10 seam and the fixed 21-chapter cap are retired, while the ordering of Memory and the terminology discipline survive	None planned	Superseded by H-134 and H-135
H-66	Recursion can yield relative magnitude, a comparison of the size of organizations across recursive levels, before metric distance; relative magnitude is not distance	Provisional	Chapter 10’s central claim; it must earn comparison of size, and with it cardinality, without importing a metric	A construction of comparative size from recursion alone, checked against Chapter 11’s distance for independence	Scale, 11
H-67	Scale must be derived as a stable relation among relational changes, not introduced as an external ruler	Retained	Methodological constraint on Chapter 10: the book’s rule against importing what it must derive, applied to magnitude	None planned; a Chapter 10 draft that assumes a unit or numeral before earning it fails the constraint	Scale
H-68	Sameness and comparison of size can be earned relationally before any numeral: two collections are the same size when their members pair one-to-one (Hume’s principle), and one is no larger than another when it maps one-to-one into it (made well-behaved by the Cantor-Schröder-Bernstein theorem)	Provisional	Established mathematics supplies the route; it remains to show that the framework’s recursive levels support the needed correspondences without assuming them	A Chapter 10 construction deriving the correspondences between recursive levels from relational structure alone	Scale; Relation (5.12, threshold aggregation)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-69	Ω is the minimally resolved reference condition: the condition from which no operative distinction is available within the framework's initial relational frame; undifferentiated at that resolution, not defined as the absolute ontological absence of distinction	Retained	Definitional choice agreed 22 September 2026. Aligns Ω with frame-relative resolvability (4.5) and with erasure as loss of resolvability (4.4), and removes an ontological overclaim. The initial frame is the framework's own starting resolution, identity and non-identity (3.4), not an observer	None planned	Origin (1.3); Distinction (3.1, 3.2); App A
H-70	Whether any difference exists in Ω below the framework's initial resolution, and whether a richer frame could resolve it	Open	The definition of Origin deliberately makes no claim either way, and Difference preserves that modesty (2.1, 2.14). If such structure were resolvable it would bear on the symmetry-breaking objection (1.7, Objection 4) and on retiring the designation cost (H-25)	A construction in which a richer frame resolves structure in Ω without reintroducing an external marker	Origin (1.3, 1.7); Difference (2.1, 2.14); Distinction
H-71	Orientation is derived, not primitive: it is persistent, consequential non-equivalence among relational dependency roles ($K_{ij} \not\sim K_{ji}$), and an arrow is notation applied after that non-equivalence is established	Provisional	Chapter 7's central claim. Excludes latent and transient asymmetry by requiring entry into dependency structure and persistence to return	The role-exchange and reversal tests of 7.15 under rules that encode no direction (Computational Companion, module 6)	Orientation (7.2, 7.5); Computational Companion

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-72	A lower-order non-equivalence becomes effective at a higher level when it survives that level's identity and resolution criterion and alters its admissible transformations	Provisional	Separates latent from effective asymmetry; uses 4.3's frames only, since the coarse-graining operator is earned in Chapter 10	A worked case in which unresolved variation crosses a higher-order threshold	Orientation (7.4)
H-73	An orientational asymmetry need persist only long enough to alter the conditions or state of anchor-relative return; this uses 6.12's identity criterion and nothing from Chapter 8	Provisional	Makes persistence functional rather than a matter of duration. The dependency runs one way: if Chapter 8 revises what return means, this threshold moves with it	Resolved 22 September 2026: Chapter 8 (8.5) defines the return condition as re-satisfaction of F after genuine departure, and the 7.7 threshold is unchanged. Now a cross-reference, not a forward dependency	Orientation (7.7); Return
H-74	An oriented recursive organization is anchor-relatively irreversible when reversing its orientational conditions fails to recover the same identity anchor	Speculative	A candidate precursor of temporal irreversibility, with no duration, entropy or metric invoked	Later chapters showing physical irreversibility as a realization of it, or showing it cannot be	Orientation (7.8); Time
H-75	Structural selection: among accessible asymmetric configurations, compatibility with recursive closure and anchor-relative return can differentially stabilize some orientations without a primitive preferred direction	Speculative	"Differential" means persistence under the declared dynamics, not probability, optimization or fitness. Does not explain the first fluctuation, and should not be raised to a universal law	Simulations in which symmetric rules yield branch-specific persistence without programmer-supplied direction	Orientation (7.9, 7.10); Computational Companion

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-76	A relational domain may support multiple independent orientational modes (d_o); orientation implies no single global axis, and is weaker than partial order, so directed cycles remain admissible	Retained	Follows from the constraint structure being a network rather than a line; the relation of d_o to d_R and d_P is open	None planned for the claim itself; d_o needs a definition before linear algebra is earned	Orientation (7.11, 7.12); Formalism, 10
H-77	Return is departure from an independently specified identity class, oriented transformation, and re-entry into that class; $\text{Ret}(A_F; \cdot)$ is a predicate over earned relations, not a new primitive	Provisional	Chapter 8's central claim, and the definition Chapter 7 used in anticipation at 7.8	The ten diagnostics of 8.23 under rules containing no cycle template (Computational Companion, module 7)	Return (8.3, 8.5); Orientation (7.8); Computational Companion
H-78	Return of higher-order identity does not require exact repetition of lower-order state, so difference can accumulate within an equivalence class	Retained	Follows from identity being an equivalence class (5.9, 6.12); separates "is this still A?" from "in what condition is this realization of A?"	None planned	Return (8.6, 8.13)
H-79	Persistence without departure is not return; recurrence requires at least one configuration that fails the tested identity criterion	Retained	Without it every stable object would count as continuously returning to itself	None planned	Return (8.4)
H-80	Identity-class recurrence can occur through distinct state tokens, so it need not violate acyclic dependency order	Retained	Lets any later causal order stay acyclic while higher-order organizations recur; keeps physical cycles distinct from closed timelike curves	None planned; relevant when causal order is derived	Return (8.7); Time to Space

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-81	A returned identity may carry traversal-dependent internal difference (χ) without that difference yet constituting memory	Retained	Keeps the retention, path-dependence and memory thresholds apart, as Propositions 3A and 3B require	None planned	Return (8.14); Memory
H-82	Robust recurrence can make a relational identity reusable as a comparison standard, a prerequisite for later Scale and Time	Provisional	The justification for placing Return before Scale: measurement needs a re-identifiable reference. Return makes unit-like reuse conceivable without creating a unit	Chapter 10 deriving endogenous standards from recurring structures	Return (8.22); Scale, 12
H-83	Return-compatible organizations may be differentially retained or re-instantiated under recursive dynamics, without reproduction, fitness or a preferred direction	Speculative	The Chapter 8 counterpart of Chapter 7's structural selection; invalid if a model rewards return explicitly	Simulations showing differential retention with no return reward encoded	Return (8.17); Computational Companion
H-84	Non-identical recurrence supplies a structural precursor to phase: the same identity invariant with a different internal condition	Speculative	Phase itself needs a parameterized cycle, algebra and often metric time or angle; a return count is an external index until Formalism earns more	Chapter 9 earning the algebra, and Chapter 12 the metric, that would turn a count into winding or phase	Return (8.21); Formalism, 12

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-85	Departure is not dissolution: return requires an identity criterion that stays applicable while unsatisfied. Whether an identity whose criterion ceased to apply can later be reconstructed, and whether that re-instantiation is a stronger form of return or a different relation, is unresolved	Open	A criterion can be evaluated only while the relations and roles it speaks about are present. Departure leaves it applicable and false; dissolution leaves it without a subject. Chapter 8 defines return on the weaker case only. The distinction matters downstream for death and recovery, phase change, horizons, reconstruction from records and substrate replacement	An account of reconstruction after dissolution that does not rely on an external record of the lost criterion	Return (8.4, 8.5); Black Holes, 19, 20
H-86	Whether $\mathcal{U}$ is genuinely a single-valued function on relational states, or shorthand for an admissible-transition relation that may permit more than one successor	Superseded	Settled: $\mathcal{U}$ enters Distinction as a relation on configurations (3.3), and Formalism states that a unique successor must be separately earned (9.5). See H-88 and H-131	None planned	Distinction (3.3); Formalism (9.5)
H-87	The earned ontology can be carried by one weak formal signature, $\mathfrak{G} = (\mathcal{C}, \mathfrak{R}, \mathcal{U})$, with closure, orientation and return as predicates over it rather than components of it	Provisional	Chapter 9's central claim. The core assumes no metric, topology, vector structure or measure, and does not restrict relations to binary arity	Whether a weaker adequate carrier exists, or $\mathcal{U}$ reduces to a dependency already in $\mathfrak{R}$ (Question 1)	Formalism (9.4, 9.26)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-88	Determinism is a property of a transition relation, the case of exactly one admissible successor, not a feature of the update notation	Retained	Resolves the open question about $\mathcal{U}$. Branching is not stochasticity and not metaphysical indeterminism: a coarse frame can merge states whose distinct successors it cannot resolve	None; the diagnostics of 9.28 test typing case by case	Formalism (9.5); Distinction (3.7); Orientation (7.9, 7.10)
H-89	Quotient-compatible dynamics is sufficient for higher-order formal autonomy: an independently constrained equivalence compatible with admissible transformation yields dynamics independent of the lower-order representative	Provisional	Gives emergence a testable criterion. Deliberately not claimed necessary for every emergent phenomenon, and 9.27 exhibits an equivalence that fails it	Conditions for branching transitions (Question 2), and whether exact congruence is too strong for real systems (Question 10)	Formalism (9.9, 9.10, 9.27); Closure (6.12)
H-90	An ontological result must survive faithful changes of representation; one that exists in a single encoding is a representational artifact	Retained	Representational pluralism as a falsifiability gain rather than a loss. Generalizes the relabeling invariance of 5.2 to the whole formal apparatus	Diagnostic 1 of 9.28, applied to the results of Chapters 5 to 8 (Question 5)	Formalism (9.26, 9.30); Relation (5.2)
H-91	Finite historical dependence is first-order update on a sufficiently specified state, so retained dependence needs no primitive memory	Retained	Discharges the formal debt left by 3.7. The ontology stores no literal tuple; the present configuration carries the retained consequences	Diagnostic 10 of 9.28	Formalism (9.21); Distinction (3.7); Memory

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-92	No medium is required beneath the relations: the formal carrier is the relational organization itself, and “substrate”, if retained, names that structure rather than a substance	Retained	Discharges RM-14 conservatively. If later physics requires a further carrier, the framework must declare it	None; a later chapter needing a medium would reopen it	Formalism (9.24)
H-93	Whether binary relations are expressively sufficient for every higher-order constraint, or genuine n-ary relations are required	Open	Has a known repair bill: Chapter 5’s matrix formulation and Chapter 7’s K_{ij} are both pairwise, and both change if higher arity is required	Diagnostic 7 of 9.28, comparing binary and hypergraph encodings for changed invariants (Question 6)	Formalism (9.18); Relation (5.2); Orientation (7.2)
H-94	A matroid-like independence system may give d_R a pre-metric definition, formalizing independence before orthogonality	Provisional	Formalism adopts it as the conditional definition $d_R := \text{rank}(\text{Ind}_R)$, available only once a suitable finite independence structure is earned (9.22); no inner product is presupposed	Diagnostic 11 of 9.28 (Questions 13 and 14)	Formalism (9.22); Relation (5.14)
H-95	Magnitude is earned by correspondence before any numeral: bijection gives sameness of amount, injection gives order, and a numeral labels a class the correspondence established	Retained	Chapter 10’s central result, and the route the Register had recorded as the intended one. Supersedes the earlier Provisional entry on cardinality by correspondence	The ten diagnostics of 10.25, in particular the correspondence-first and relabeling tests (Computational Companion, module 9)	Scale (10.4, 10.5, 10.7); Relation (5.12)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-96	Threshold aggregation, deferred at 5.12, is expressible as an injection from a standard collection and needs no primitive beyond comparative magnitude	Derived	Resolved 23 September 2026 by 10.8. The Chapter 5 deferral is discharged: $K \leftrightarrow A_P$ states the condition before any numeral, and $\text{mag}(A_P) \geq k$ is its compression	Diagnostic 3 of 10.25, which reconstructs the condition from a standard collection before using numeral shorthand	Scale (10.8); Relation (5.12); Closure (6.9)
H-97	Recursive composition can produce a stable comparative ratio, and the stability belongs to the relation rather than to any level's magnitude; φ is one such ratio among many	Provisional	This is what scale was defined to be. Section 10.16 demonstrates the existing rejection of golden-ratio universality rather than asserting it: the general recurrence selects other ratios for other coefficients	Diagnostics 6 to 8 of 10.25: ratio convergence, recurrence perturbation and robustness to initial conditions	Scale (10.13 to 10.17); Distinction (3.7)
H-98	Whether the membership and decomposition criteria that fix an organization's magnitude can be constrained independently, or whether magnitude is an artifact of how the analyst divides the structure	Open	Chapter 10's most serious vulnerability, conceded at Objection 12. It is the same risk the invariant F carries in Chapters 6 and 8, now attached to amount rather than identity	An independent constraint on decomposition, of the kind F_{dyn} would supply for identity	Scale (10.27); Closure (6.14); Return (8.3)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-99	Sameness of comparative form is definable by correspondence alone: W stands to A as A stands to B exactly when $W \times B$ pairs one to one with $A \times A$	Retained	Cross-multiplication written as the bijection it always was. The construction needs only ordered pairs, which Chapter 3 and Chapter 7 supply between them, so proportion does not depend on ratio: 10.11's ratio is a compression of this correspondence, not its foundation. Established 23 September 2026, replacing the declared debt the first draft carried	Whether the construction extends beyond finite organizations, where the product and the correspondences are unproblematic	Scale (10.10, 10.11)
H-100	A scale-indexed coarse-graining operator CG_s is admissible once its comparison standard is earned relationally, and remains pre-geometric	Provisional	Discharges the deferral Chapter 7 made by name at 7.4. Smallness by metric distance stays unavailable until Chapter 11	Diagnostic 10 of 10.25, admitting the quotient only after its standard is independently earned	Scale (10.20); Orientation (7.4)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-101	Distance is the least magnitude of relational mediation sufficient to connect two loci: $d_u(A,B) = \min \text{ over admissible chains of } L_u(\kappa)$	Provisional	Chapter 11's central claim. The minimum is selection over an ordered finite set, not an optimization principle: nothing moves and no action is minimized. Well defined only where the chain set is non-empty and finite, so unconnected loci have no distance rather than infinite distance	Whether minimum mediation is the weakest adequate definition, and whether pairwise invariants could generate metric structure without chains (Questions 1 and 2)	Distance (11.5); Scale (10.5)
H-102	The triangle inequality is derived, not assumed: chain composition plus additive magnitude plus minimality yields $d(A,C) \leq d(A,B) + d(B,C)$	Provisional	The strongest formal result in the volume, and its premise travels with it: additivity is earned only where the organization supports concatenation without interference, so the inequality inherits that status. Where composition is non-additive, a weaker inequality may survive	Diagnostics 8 and the additivity condition of 11.8 (Questions 3 and 4)	Distance (11.8, 11.10)
H-103	Mediation between loci is not the transition relation $\mathcal{W}$ between configurations	Retained	Conflating them would make distance a count of updates, misdescribing separation and leaving Time nothing of its own to earn. Stated in 11.3 rather than left to the apparatus	None; the distinction is definitional and is tested by diagnostic 9, the hidden-geometry control	Distance (11.3); Formalism (9.5)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-104	Metric symmetry is not primitive: orientation permits $d(A,B) \neq d(B,A)$, so a directed metric-like structure appears first	Retained	A consequence of Chapter 7 rather than a concession. Symmetry is recovered only where every mediating relation is reversibly equivalent and every chain has a reverse of equal magnitude	Diagnostic 7 of 11.21, reversing admissible chains and comparing magnitudes (Question 5)	Distance (11.11); Orientation (7.2)
H-105	The decomposition vulnerability inherited from Scale is amplified in Distance: loci, mediating relations, chain admissibility and the scale standard must all be independently constrained	Open	If the analyst may choose these after seeing the desired result, almost any metric can be manufactured. 11.17 calls this the chapter's most important falsifiability condition, and it is the same entry as Chapter 10's Objection 12 with more surface	Diagnostics 3 and 10 of 11.21: decomposition perturbation, and comparison against matched random organizations (Question 7)	Distance (11.17); Scale (10.27)
H-106	Geometry begins where metric relations cease to be pairwise and become mutually constraining: stable neighborhoods under admissible transformation, with overlap as the first collective constraint	Provisional	Keeps Geometry from renaming a metric space as emergent geometry. Distance relates loci; Geometry relates systems of distances	Diagnostics 1 to 3 of 12.25: relabeling and representation invariance, and decomposition perturbation	Geometry (12.2, 12.3); Distance
H-107	A layer is not a dimension: the number of metric-relational layers is independent of the number of geometric dimensions	Retained	The discipline a multilayer proposal most needs, stated before the proposal can be misread. Dimension enters only where a local state can vary in more than one irreducible way	Diagnostic 5 of 12.25, measuring rank from the generated organization rather than stipulating it	Geometry (12.6); Formalism (9.22)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-108	Whether the structural and operational senses of effective dimension agree: d_R , the rank of stable independent modes, and d_{probe} , the fewest parameters preserving declared invariants across probes	Open	A single symbol for both would assume they coincide, which is not argued. They agree when every structural mode is separately resolvable, which the framework has not shown. The two are written separately so the equivocation cannot hide	Diagnostics 5 and 6 of 12.25 run together: measure rank from the organization, then measure it again across heterogeneous probes	Geometry (12.6, 12.18)
H-109	Measurement is an interaction within the organization, not a look at it from outside: $O_F = \Pi_F(I_F(\mathcal{V}))$, separating resolution loss from back-action	Provisional	Relocates objectivity to cross-frame invariance rather than a view from nowhere, and does so without committing to any interpretation of quantum measurement	Diagnostic 6 of 12.25 and the projection-stability programme of 12.27, requiring heterogeneous probes that could have disagreed	Geometry (12.15 to 12.17); Closure (6.14)
H-110	Variation in cross-layer coupling may produce variation in effective metric relations, a candidate route to curvature-like structure	Speculative	The most speculative claim in the volume, and the one place Geometry reaches toward Gravity. A generative hypothesis to be modelled, not an interpretation of known gravitational physics	Diagnostic 8 of 12.25, distinguishing route-dependent failure from coordinate artifacts, and the modelling programme of 12.26	Geometry (12.20, 12.22)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-111	Whether a relational substrate with no target dimensionality in its rules converges on a stable low-dimensional effective rank	Open	The dimensionality programme of 12.26. Convergence on rank three would show that low-dimensional geometric organization can arise from this machinery, not that space is three-dimensional; the guard against fine-tuning must stay adjacent to the target, since a wandering or non-integer result is the outcome most likely to be quietly retuned away	Diagnostics 4, 5, 9 and 10 of 12.25 together: no hidden dimension in the rules, rank recovered rather than stipulated, comparison against matched random organizations, and failure reported	Geometry (12.26); Computational Companion
H-112	Space becomes available when localizations constrain localizations: distinct loci in an effective geometry become mutually coordinated, so that no position can be varied independently of the others	Provisional	The volume's pattern applied a third time, after relations constraining relations and distances constraining distances. A point becomes a place only when its placement belongs to a mutually constraining organization	The coordinate-removal and perturbation-coordination tests of 13.26	Space (13.6, 13.23); Geometry; Relation (5.9)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-113	Physical does not mean material: a geometric distinction is physically consequential when changing it changes the admissible relational organization of other instantiated structures	Retained	Lets Space call itself physical without circularity while Matter remains underived, through $\text{Adm}(A, B \cdot)$, the admissible couplings under a given geometric organization	The locality-prediction test of 13.26, against randomized baselines	Space (13.8)
H-114	Detecting a failure of smoothness is not resolving fundamental structure: a probe may reach an intermediate organizational regime and no further	Retained	Governs how any evidence of granular geometry should be read, in this framework and in quantum-gravity phenomenology generally. The pothole: a tyre finds where the smooth description fails without resolving aggregate or binder	The smoothness-failure test of 13.26, which must distinguish loss of continuity from loss of localization	Space (13.14, 13.15)
H-115	Spatial coordination may be responsive: a distributed relational transformation can alter couplings, hence separations, hence the effective geometry, which then constrains subsequent transformation	Speculative	A candidate proposition, not a dynamical law and not gravity. Its value here is negative: it prevents Space from being defined as rigid before later chapters need it to respond	The responsive-geometry test of 13.26, perturbing the substrate without changing geometric variables explicitly	Space (13.16, 13.17); Geometry (12.22)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-116	Local neighborhoods can persist while global metric separations change, so localization survives what separation does not	Provisional	Preserves a route by which cosmological expansion could later read as evolving relational scale rather than motion through a container. Recorded because later volumes will lean on it; it is a route kept open, not a result	The scale test of 13.26, repeated coarse-graining with localization and adjacency measured separately from global separation	Space (13.18); Scale (10.20)
H-117	Space is intrinsic before it is embedded: an embedding ι may be useful representationally and cannot be inferred from its convenience	Retained	The same discipline Geometry applied to curvature, now applied to space itself, and the reason closure still does not mean enclosure	The coordinate-removal test of 13.26, stripping embeddings and drawing positions before recovery is attempted	Space (13.20, 13.21)
H-118	Whether spatial coordination emerges from relational organization, or spatial locality has been reintroduced through the admissible-coupling rule	Open	The chapter's own statement of its principal vulnerability, and the question on which everything in it depends. It is the decomposition problem of Scale and Distance in its sharpest form, since the coupling rule is where locality would hide	An independent criterion for admissible coupling, fixed before locality is tested; without one the chapter has not earned Space	Space (13.29); Scale (10.27); Distance (11.17)
H-119	Retained consequence defines intrinsic dependency precedence, $\Sigma_a < \Sigma_b$, without physical time as a primitive: Σ_b contains consequences whose removal would change Σ_b or its admissibility	Provisional	Time's foundation, and the chapter's strongest step. The counterfactual criterion stops notation from generating order: writing states in a list does not order them	The index-removal and counterfactual-dependency tests of 14.25, which are the chapter's T-1 condition	Time (14.3, 14.4); Boundary (4.4)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-120	Temporal order is a partial order, not a total sequence: dependency-incomparable events are admitted rather than forced onto one line	Retained	Raw dependency $<$ need not be acyclic, so the order is earned on the quotient by mutual dependency: $<_t$ between classes is a strict partial order by construction (14.5). A universal total order would be a hidden global clock. Incomparability is a feature of the derivation, and it is what lets the framework remain compatible with the absence of frame-independent simultaneity without assuming relativity	The branching test of 14.25: introduce incomparable update structures and verify no artificial global order is forced	Time (14.5, 14.10)
H-121	Derivation order is not physical time: an ordering that vanishes when counters, equation labels and manuscript sequence are removed was never derived	Retained	The sharpest falsifiable criterion in the volume, and a methodological result beyond this framework. The dependency must belong to the system modelled rather than to the account of it	The index-removal test of 14.25, run before any other temporal claim is assessed	Time (14.8); Computational Companion
H-122	Counting retained updates is not measuring duration: $N_C(e_\alpha, e_\beta)$ is a structural quantity, and becomes a temporal measure only where the counted unit is stable and reproducible	Provisional	The temporal counterpart of Distance's warning that counting mediators is not measuring extent. Two chains may differ in update count while carrying the same higher-order transformation	The coarse-graining test of 14.25: change temporal resolution and check that precedence and any metric ratios survive	Time (14.11, 14.22); Distance (11.18)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-123	Clockhood is a relational role, not a property: a subsystem functions as a clock when it satisfies recurrence, countability, stability and couplability	Provisional	Couplability is the condition that catches the hidden failure: if every process is defined by reference to the clock variable from the outset, agreement with the clock has been built in rather than found	The cycle-calibration test of 14.25, with two independently organized recurrences and neither defined through the other	Time (14.12, 14.13)
H-124	Metric time may be recoverable from cross-clock invariance, $\tau_k(A,B) / \tau_j(A,B)$ approximately constant over a regime, without any primitive universal clock	Open	The chapter's most conditional route, and the one the computational programme must demonstrate. A shared calibration within a local domain establishes neither a global cosmic time nor a universal rate	The six minimal conditions of 14.24: ordered comparability, repeatable standard, cross-standard calibration, resolution robustness, frame coherence and non-circularity	Time (14.14, 14.24)
H-125	Propagation is not earned in Book I: speed as spatial separation over temporal duration is unavailable, since numerator and denominator have not been shown to participate in one invariant structure	Retained	The seam Book I hands to Book II, and the reason Time's derivation does not depend on any carrier. Whatever propagates, and at what rate, is the next book's problem	The spacetime-withholding test of 14.25: verify that no propagation speed, Lorentzian signature, null relation or invariant c is required for the temporal construction to work	Time (14.16, 14.28, 14.31)
H-126	Record asymmetry makes dependency orientation internally recoverable: $\text{Record}_B(A)$ non-empty while $\text{Record}_A(B)$ is empty along the realized chain	Provisional	Temporal direction need not be painted on from outside. This is a structural orientation only: the thermodynamic arrow, entropy and cosmological boundary conditions are explicitly not claimed	The reverse-rule test of 14.25: use microscopically reversible laws and check that irreversibility is not manufactured	Time (14.17, 14.18)

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-127	Whether temporal order emerges from retained dependency inside the organization, or physical time has been reintroduced through the update rule used to generate the sequence	Open	The chapter's own statement of its principal vulnerability, and the form Space's coupling-rule question takes for Time. If it cannot be answered, the chapter has not earned Time	An update rule specified without reference to an external time variable, then the index-removal and counterfactual tests run against it	Time (14.29); Space (13.29)
H-128	Relational physical structure can be reconstructed from two foundational commitments so far: primitive Difference, the minimum symmetric, irreflexive dyad whose poles are co-constituted with it (Proposition 1B; stated formally as Proposition 2A), and admissible transformation $\mathcal{W}$ (H-131)	Provisional	Difference carries no magnitude, orientation, persistence, representation or observer (2.3, 2.14). Static non-equivalence cannot license succession, so the second commitment is counted openly rather than hidden (3.2)	A cheaper primitive, an incoherent account of co-constitution, or a later need for absolute or relative discernibility from the start would count against it (2.16)	Difference; Distinction; Boundary; Parts II-III
H-129	Distinction is difference made operative in admissible succession: the poles are promoted to a minimal configuration carrier $\mathcal{C} \mathfrak{D}$, and a nontrivial transition relation $\mathcal{W}$, covariant under $\text{Aut}(\mathfrak{D})$, licenses succession between them, forcing reciprocal exchange without privileging either pole (Proposition 3A)	Provisional	Replaces the resolver definition: the reciprocal map $J_{\mathcal{W}}$ is derived from $\mathcal{W}$, and identity arises from composition rather than primitive stasis (3.8, 3.9)	Counts against it: $\mathcal{W}$ cannot be specified without the Distinction it grounds, or no downstream consequence separates the role of $\mathcal{W}$ from that of $\emptyset$ (3.18). Dependency precedence $<$ (4.11) is the first such consequence	Distinction; Boundary

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-130	Weak discernibility characterizes the primitive dyad's minimal individuation but does not ground its numerical diversity, which Proposition 2A admits as an explicit primitive cost	Provisional	Concedes the circularity objection (Ladyman, Linnebo and Pettigrew, 2012) and Hawley's objection (2006) against any inference from weak discernibility to two poles, and assigns weak discernibility only a diagnostic role (2.5, 2.15)	A later chapter that needs the relation itself to ground numerical diversity, or needs absolute or relative discernibility from the start, would count against it (2.16)	Difference (2.6, 2.15, 2.16)
H-131	Admissible transformation $\mathcal{U}$ is the second foundational commitment so far, not derived from Difference	Provisional	A static relation cannot license succession (3.2). Admissibility is primitive, must not be defined through resolution (3.4), and is constrained by nontriviality and covariance under $\text{Aut}(\mathfrak{D})$ (3.5)	A derivation of $\mathcal{U}$ from Difference, or of both from a single weaker principle, would retire it (3.19)	Distinction; Formalism
H-132	Retention can be defined as counterfactual robustness under a declared diagnostic family $\mathfrak{T}_{\text{test}}$, without a third ontological commitment	Provisional	Distinction's claim is constitutive and requires internality; retention's is modal, so declared tests are legitimate (4.4; 4.24, Objection 2)	A later need for a privileged, underived family of physically realized transformations would add a third commitment (4.25)	Boundary
H-133	A dynamically persistent closed identity O_F that is addressable independently of its lower-order representatives earns an organizational reference role, the anchor A_F , without privileging any primitive pole	Provisional	The anchor is a role of the closed equivalence class, not an added entity or a privileged member; a new origin is a re-instantiated reference role, not a transmitted centre (6.13)	Whether every closed organization yields a unique anchor, and what localizes or distributes it, remains open (6.13)	Closure (6.13); Orientation; Return

#	Hypothesis	Status	Reason	What would revive or resolve it	Revisited in
H-134	Volume I, Book I, comprises Chapters 1 to 14 and ends with Time. Book II begins where the earned structures of Space and Time must be shown to support physical spacetime and subsequent physical dynamics	Retained	The seam tracks the ontological transition from formal and relational construction to physical instantiation, rather than the earlier appearance of metric structure	None planned	Volume I architecture; Time handoff; Book II opening
H-135	Memory remains downstream of Life and upstream of Knowing; before Life, the book uses retention, record or path dependence rather than the stronger biological sense of memory. No fixed total chapter count is imposed in advance	Retained	The ordering preserves the distinction between generic retained consequence and internally consequential retention in a self-maintaining system, while letting Book II's length follow the dependency architecture	None planned	Life, Memory and Knowing; Volume I architecture

The Origin Inheritance Ledger

Origin earns almost nothing, and that is its purpose: it fixes what every later chapter may not assume. This ledger records, for each chapter that follows, what Origin passes forward and what it withholds. It is offered as an audit aid. A reader who suspects that a later chapter has borrowed structure it did not earn can check that chapter's row here, and then the chapter itself.

Later chapter	What Origin passes forward
Difference	Ω as the minimally resolved initial reference condition; logical rather than temporal priority; the prohibition against reading Ω as a place, moment, substance, cause, observer or anchor.
Distinction	The requirement that admissible succession, if introduced, must not be read as physical time; Proposition 1B's second commitment remains explicit rather than hidden in the language of distinction.
Boundary	Resolution-relative undifferentiation; failure to resolve does not establish ontological identity or absence; Proposition 1A supplies the burden that observable structure requires retained distinction. Ω is not a privileged pole.
Relation	The prohibition against importing objecthood or geometry into primitive relation; higher-order structure must arise from mutually constraining retained distinctions rather than pre-existing objects.
Closure	Originhood is a role rather than a unique first moment. A closed higher-order identity may earn a new origin/reference role through representative-independent addressability, yielding A_F without inheriting Ω as an anchor.
Orientation	No spatial or primitive direction is supplied at Origin. Orientation must arise from consequential non-equivalence of relational roles after an organizational reference has been earned.
Return	Origin, anchor and return are distinct. Return concerns re-entry relative to a Closure-earned A_F and identity class; recurrence remains pre-temporal.
Formalism	The metalanguage may be richer than the ontology; mathematical representation must not read unearned structure back into Ω or the early relational stages.
Scale	Origin supplies no magnitude, unit or ruler. Comparative magnitude must be earned from recursive organization and endogenous standards.
Distance	No metric separation is available at Origin. Distance must arise from earned relational mediation and scale rather than being read into the primitive dyad.

Later chapter	What Origin passes forward
Geometry	No coordinate system, topology, dimensionality or embedding is available at Origin. Geometry is constructed only after distance relations acquire stable mutual constraint.
Space	No physical place or extension is available at Origin. Space requires geometrically coordinated localization to become physically consequential.
Time	No physical duration, causal cone or temporal order is available at Origin. Time may use retained dependency only after Boundary and must add the conditions needed to turn weak precedence into an order that warrants temporal interpretation.
Book II	Physical spacetime, dynamics, fields and matter remain beyond Book I. Book II must test whether the separately earned structures of Space and Time can become physically instantiated rather than merely formally coherent.

A Note on the Computational Companion

The open entries in the Hypothesis Status Register are not all matters of argument. Several are claims about what a model would do, and those can be run rather than debated: whether recursive relational rules settle into a stable low-dimensional regime, whether diffusion and wave behaviour diverge on a relational graph, whether an effective metric survives coarse-graining, whether temporal order survives the removal of every index.

Those tests belong to a separate document. Specifying one properly takes more room than a table cell: the generative rule, the initial conditions, the control it is measured against, the declared diagnostic and its threshold, the number of runs, and the criterion that would count as failure. Compressed into a book appendix, each would become a sentence that sounds like a plan and could not be executed.

The companion is therefore published alongside this volume, addressed to readers in computer science and applied physics who intend to run the models rather than read about them. It carries the guardrails this book's methodology imposes on computational work: that a model demonstrates a mechanism rather than a world, that the declared diagnostic and its control are fixed before the run, and that a failed diagnostic is reported rather than retuned. Where the companion produces a result, the Register entry it bears on is updated here.

What matters for the present volume is the commitment rather than the code. A framework that claims to be constrained by more than its own consistency should say what would embarrass it, and say it precisely enough that someone else can check.

List of Figures

Forty figures appear in Book I. Each is explanatory: it uses whatever visual language makes the idea clearest, and the sentences around it say what the framework actually commits to.


Figure	Subject	Chapter	Page
1.1	The descent to origin	Origin	27
2.1	Co-constitution: neither the difference nor its poles comes first	Difference	48
2.2	Three grades of discernibility, and where the dyad sits	Difference	49
2.3	Primitive difference: symmetric non-equivalence	Difference	50
3.1	The same pairs, two different claims: difference and succession	Distinction	59
3.2	Identity from composition: a switch that can only toggle	Distinction	61
4.1	What survives a transformation: two signatures, copied and faxed	Boundary	70
4.2	Precedence is dependence, not earliness: a sauce, its stock and a garnish	Boundary	72
5.1	The same structure drawn twice	Relation	85
5.2	Membership is participation in mutual constraint: stones and an arch	Relation	94
6.1	Connected is not closed	Closure	107
6.2	Addressable as one: an orchestra, hired by name	Closure	114
6.3	The first reference point is a role of the whole: a city as a reference	Closure	116
7.1	The exchange test, and where the arrow comes from	Orientation	129
8.1	Return through a different token	Return	150
9.1	A configuration may have no successor, one, or several: roads and a fork	Formalism	169
9.2	Quotient compatibility, and the single transition that decides it	Formalism	180
11.1	Competing chains and minimum mediation	Distance	210
11.2	Why additivity has to be earned	Distance	212
11.3	Zero separation and quotient identity	Distance	213
11.4	Orientation can produce asymmetric distance, read as a kayak on a river	Distance	215

Figure	Subject	Chapter	Page
11.5	Scale-relative distance under coarse-graining, read as a street map against a subway map	Distance	218
11.6	Distance as a derivational bridge	Distance	226
12.1	From pairwise distance to stable neighborhood	Geometry	230
12.2	Coupled layers and collective modes, read as strings and frets on a guitar	Geometry	233
12.3	One stable projection does not fix the substrate	Geometry	237
12.4	Independence before orthogonality	Geometry	240
12.5	Curvature as failed return of a comparison standard	Geometry	241
13.1	A mouse can traverse a maze blueprint in one step to find the cheese, and needs twenty-nine steps to reach the same cheese in a maze built from that blueprint	Space	253
13.2	Coordination is not coordinates	Space	254
13.3	Localizations constrain localizations, read as one panel moved	Space	256
13.4	Page adjacency is not locality	Space	259
13.5	Effective smoothness and what lies beneath it	Space	261
13.6	Responsive coordination	Space	262
13.7	Smooth neighborhoods and an irregular region in one domain	Space	263
13.8	Space as a derivational bridge	Space	266
14.1	Order is earned in two steps: a shared document	Time	277
14.2	The index-removal test, read as undated photographs	Time	279
14.3	Cross-clock calibration, read as a pendulum and a dripping tap	Time	282
14.4	Book I as a whole	Time	294

Each system was invited to represent itself, without direction from the author.
The images are reproduced as each chose them, at matching proportions (4:5),
and make no claim about what either system is.



Sol



Claude

EMERGENT EXISTENCE

Does the Universe require a Creator—or can existence generate its own complexity?

Emergent Existence follows that question by starting with the fewest assumptions about existence it can justify, and then reconstructing, step by step, how difference, relation, structure, space, time, physics, life, consciousness, and meaning might emerge—testing at each stage what has actually been earned and what remains unexplained.

Volume I: Existence • Book I: Foundations of Physical Reality • Natan Mallinger